

CUMBERLAND
RESOURCES LTD.

MEADOWBANK GOLD PROJECT

PROJECT ALTERNATIVES REPORT

OCTOBER 2005

TABLE OF CONTENTS

DESCRIPTION OF SUPPORTING DOCUMENTATION

EIA DOCUMENTATION ORGANIZATION CHART

PROJECT LOCATION MAP

PROPOSED SITE LAYOUT

BAKER LAKE STORAGE & MARSHALLING AREA

SECTION 1 • INTRODUCTION.....1-1

SECTION 2 • THE “NO-GO” ALTERNATIVE.....2-1

SECTION 3 • SITE & FOOTPRINT.....3-1

3.1	Plant Site Options.....	3-1
3.2	Open Pit Limits & Dewatering Dike Location.....	3-4
3.3	Alternative Control Strategies for Mine Waste Disposal in Cold Regions.....	3-5
3.4	Mine Waste Storage Alternatives.....	3-10
3.5	Evaluation of Waste Rock Disposal Alternatives.....	3-15
3.6	Evaluation of Tailings Storage Alternatives.....	3-20
3.7	Assessment of the Strategy to Freeze the Portage Tailings Facility.....	3-26
3.8	Airstrip.....	3-31
3.9	Vault Access Road	3-31

SECTION 4 • MINING METHODS4-1

4.1	Blast Design Alternatives.....	4-1
-----	--------------------------------	-----

SECTION 5 • PERIMETER DIKES5-1

5.1	Site Conditions	5-1
5.2	Design Alternatives.....	5-1
5.3	Design Basis & Criteria.....	5-4
5.4	Slope Stability.....	5-8
5.5	Seepage	5-12

SECTION 6 • STABILITY ASSESSMENT OF THE PORTAGE ROCK STORAGE FACILITY.....	6-1
6.1 Construction Alternatives.....	6-1
6.2 Stability Analysis.....	6-8
SECTION 7 • TAILINGS DIKE DESIGN ALTERNATIVES	7-1
7.1 Tailings Dike Site Conditions.....	7-1
7.2 Design Alternatives.....	7-5
7.3 Design Basis & Criteria.....	7-9
7.4 Slope Stability	7-10
7.5 Seepage	7-12
7.6 Post-Closure Thermal Analyses	7-14
SECTION 8 • PROCESS SELECTION	8-1
8.1 Gold Recovery	8-1
8.2 Tailings Processing	8-1
SECTION 9 • WATER MANAGEMENT & TREATMENT	9-1
SECTION 10 • WORKFORCE CONSIDERATIONS.....	10-1
SECTION 11 • ENERGY SOURCES	11-1
11.1 Wind Power	11-1
11.2 Solar	11-1
11.3 Hydrogen	11-1
11.4 Hydroelectric Power	11-1
11.5 Options to Reduce Power Consumption	11-2
SECTION 12 • TRANSPORTATION.....	12-1
12.1 Summer Shipping Options.....	12-1
12.2 Access Road.....	12-1
12.3 Ice Road	12-3
12.4 Seasonal Land Road	12-5
12.5 All-Weather Land Route	12-6
12.6 Preferred Alternative.....	12-6
12.7 Permanent Land Route Alternatives	12-6
12.8 Preferred Option – Green Route	12-7
12.9 Stream Crossings	12-14
SECTION 13 • REFERENCES.....	13-1

LIST OF TABLES

3.1	MEND Project – Report Listing.....	3-6
3.2	Acid Mine Drainage Control Strategies for the Arctic.....	3-6
3.3	Relative Contribution of Primary Categories to Decision Analysis.....	3-12
3.4	Example of Scoring System used in Decision Matrix.....	3-13
3.5	Weighting Factors for Sub-Indicators for Rock Storage Facility Selection.....	3-14
3.6	Weighting Factors for Sub-Indicators for Tailings Facility Evaluation	3-15
3.7	Summary of Weighted Scores for Rock Storage Facility Options.....	3-16
3.8	Summary of Initial Tailing Storage Alternatives.....	3-22
3.9	Alternatives Evaluated Using the Decision Matrix.....	3-22
3.10	Summary of Baseline Analysis Decision Matrix Results	3-22
3.11	Summary of Decision Matrix Results – Sensitivity Analysis (Part 1).....	3-23
3.12	Summary of Decision Matrix Results – Sensitivity Analysis (Part 2).....	3-24
3.13	Summary of Decision Matrix Results – Sensitivity Analysis (Part 3).....	3-25
3.14	Summary of Reported Climate Change Rates Used in Northern Projects Engineering Studies	3-27
3.15	Time to Freeze at Base of Tailings (38 m) for Initially Thawed Tailings	3-29
4.1	Range in Charge Weights Considered for the Meadowbank Project.....	4-2
4.2	Minimum Setback Distance for 13 mm/s Peak Particle Velocity Guideline	4-3
4.3	Minimum Setback Distance for a Peak Particle Velocity of 50 mm/s for Various Blast Configurations	4-4
4.4	Properties Used to Assess Setback Distance for Instantaneous Pressure Change.....	4-7
4.5	Minimum Setback Distance for Instantaneous Pressure Change Guideline (<100kPa).....	4-7
4.6	Minimum Setback Distance for Instantaneous Pressure Change Guideline (50 kPa Ice-Covered Water).....	4-9
5.1	Peak Horizontal Ground Accelerations for Meadowbank Site	5-6
5.2	Summary of Long-Term Slope Stability Analyses.....	5-12
5.3	Summary of Material Properties used in Seepage Analyses	5-13
5.4	Seepage Fluxes through the Soil-Bentonite Cutoff Wall.....	5-13
5.5	Seepage Flows through Dikes.....	5-14
7.1	Summary of Material Properties used in Slope Stability Analyses.....	7-10
7.2	Summary of End of Stage 1 Construction Stability Analyses.....	7-11
7.3	Summary of Long-Term Slope Stability Analyses.....	7-11
7.4	Summary of Material Properties used in Seepage Analyses	7-12
7.5	Seepage Fluxes at the Portage Pit West Wall	7-13
7.6	Drilling & Injection Grouting Estimates for the Tailings Dike	7-13
7.7	Summary of Material Properties in Post-Closure Thermal Analyses	7-15
7.8	Summary of Modelling Parameters for Post-Closure Transient Thermal Modelling	7-17
12.1	Tractor-Trailer vs. All-Terrain Vehicle Operations – Winter Road.....	12-4
12.2	Comparison of All-Weather Road Alternatives – Location, Length & Water Crossings.....	12-7
12.3	Characteristics of Soil Sample Test Pits	12-11
12.4	Rock Sample Location & Lithology.....	12-13
12.5	Summary of Analytical Results.....	12-14
12.6	Terrain Conditions at Stream Crossings	12-15
12.7	Evaluation of Terrain Susceptibility to Periglacial Processes.....	12-18
12.8	Engineering & Construction Methods Based on Sensitivity to Freeze/Thaw Induced Displacements	12-19

LIST OF FIGURES

3.1	General Site Plan	3-2
3.2	Plant Site Options.....	3-3
3.3	Waste Rock Storage Facility, Construction Methods	3-8
3.4	Tailings Thin Layered Freezing Design Concept	3-9
3.5	Insulating Cover Design for Freezing in Continuous Permafrost	3-11
3.6	Portage Rock Storage Options.....	3-17
3.7	Vault Rock Storage Options	3-19
3.8	Tailings Storage Options	3-21
3.9	Baker Lake Weather Station Data & Climate Change Trends	3-28
3.10	Time to Freeze Tailings for all Tailings Instantaneously Placed at +6°C	3-30
3.11	Airstrip Alternatives.....	3-32
4.1	Peak Particle Velocity, 13 mm/s Isopleth	4-5
4.2	Peak Particle Velocity, 50 mm/s Isopleth	4-6
4.3	Instantaneous Overpressure, 100 kPa Isopleth	4-8
4.4	Instantaneous Overpressure, 50 kPa Isopleth	4-10
5.1	Second Portage & Bay Zone Dike – Centreline Profile.....	5-2
5.2	Goose Island Dike – Centreline Profile	5-3
5.3	Typical Dike Cross Section – Portage, Goose Island & Bay Zone Dike	5-5
5.4	Seismic Zoning Map Showing Meadowbank Project Location.....	5-7
5.5	Location of Stability Cross-Sections	5-9
5.6	Goose Island Dike Sections	5-10
5.7	Second Portage Dike & Causeway Sections	5-11
6.1	Ground Thermal Regime, Year 2 (Summer), Summer Placement	6-4
6.2	Ground Thermal Regime, Year 11 (Summer), Summer Placement	6-5
6.3	Ground Thermal Regime, Year 2 (Summer), Winter Placement.....	6-6
6.4	Ground Thermal Regime, Year 11 (Summer), Winter Placement.....	6-7
6.5	Ground Thermal Regime, Year 111 (Summer), Summer Placement, no Climate Change	6-9
6.6	Ground Thermal Regime, Year 111 (Summer), Summer Placement, with Climate Change	6-10
6.7	Ground Thermal Regime, Year 211 (Summer), Summer Placement, after Climate Change	6-11
7.1	Proposed Tailings Facility Layout.....	7-2
7.2	Proposed Tailings Dike Plan	7-3
7.3	Proposed Tailings Dike Site Conditions	7-4
7.4	Proposed Tailings Dike Design Alternatives	7-6
7.5	Tailings Storage Facility, Stage Storage Volume Curve	7-8
7.6	Post-Closure Thermal Modelling, Proposed Tailings Dike – Steady-State Analyses	7-16
7.7	Post-Closure Thermal Modelling, Full Cutoff Tailings Dike, Transient Analysis	7-18
7.8	Post-Closure Thermal Modelling, Full Cutoff Tailings Dike, Transient Analysis including Climate Change Effects	7-19
8.1	Simplified Flow Diagram for Proposed Meadowbank Process	8-2
9.1	Water Management Plan.....	9-2
12.1	Marine & Overland Transportation Options.....	12-2
12.2	Alternative Access Routes.....	12-8
12.3	Route Alignment & Soil & Rock Sample Sites.....	12-9

LIST OF APPENDICES

- A Evaluation of Tailings Management Alternatives
- B Evaluation of Waste Rock Management Alternatives
- C Blast Design
- D Perimeter Dike Slope Stability Analyses

DESCRIPTION OF SUPPORTING DOCUMENTATION


Cumberland Resources Ltd. (Cumberland) is proposing to develop a mine on the Meadowbank property. The property is located in the Kivalliq region approximately 70 km north of the Hamlet of Baker Lake on Inuit-owned surface lands. Cumberland has been actively exploring the Meadowbank area since 1995. Engineering, environmental baseline studies, and community consultations have paralleled these exploration programs and have been integrated to form the basis of current project design.

The Meadowbank project is subject to the environmental review and related licensing and permitting processes established by Part 5 of the Nunavut Land Claims Agreement. To complete an environmental impact assessment (EIA) for the Meadowbank Gold project, Cumberland:

1. Determined the VECs (air quality, noise, water quality, surface water quantity and distribution, permafrost, fish populations, fish habitat, ungulates, predatory mammals, small mammals, raptors, waterbirds, and other breeding birds) and VSECs (employment, training and business opportunities; traditional ways of life; individual and community wellness; infrastructure and social services; and sites of heritage significance) based on discussions with stakeholders, public meetings, traditional knowledge, and the experience of other mines in the north.
2. Conducted baseline studies for each VEC and compared / contrasted the results with the information gained through traditional knowledge studies (see Columns 1 and 2 on the following page for a list of baseline reports).
3. Used the baseline and traditional knowledge studies to determine the key potential project interactions and impacts for each VEC (see Column 3 for a list of EIA reports).
4. Developed preliminary mitigation strategies for key potential interactions and proposed contingency plans to mitigate unforeseen impacts by applying the precautionary principle (see Columns 4 and 5 for a list of management plans).
5. Developed long-term monitoring programs to identify residual effects and areas in which mitigation measures are non-compliant and require further refinement. These mitigation and monitoring procedures will be integrated into all stages of project development and will assist in identifying how natural changes in the environment can be distinguished from project-related impacts (monitoring plans are also included in Columns 4 and 5).
6. Produced and submitted an EIS report to the Nunavut Impact Review Board (NIRB).


As shown on the following page, this report is part of a documentation series that has been produced during this six-stage EIA process.

EIA DOCUMENTATION ORGANIZATION CHART




PROJECT LOCATION MAP





Source:Golder Associates Drawing # 051413036A-1400-2.1.dwg





- NOTES**
- 1) Topographic contour interval 2m.
 - 2) Bathymetric contour interval 1m.
 - 3) Scale As shown.

LEGEND

SD: SADDLE DAM

CUMBERLAND RESOURCES LTD.	
Meadowbank Gold Project	
General Site Plan	



LOCATION MAP

LEGEND

- Test Pit Location (Approximate)
- Property Limit
- Contour Interval
- Bedrock Outcrop (Approximate)
- Interpreted Frost-susceptible Ground

NOTES

- 1) Northing and eastings are in metres referenced to UTM Zone 14, NAD83.
- 2) Elevations are in metres referenced to geodetic datum.
- 3) Testpit, bedrock outcrop, seismic line and EM31 survey boundary locations were determined using GPS equipment and are considered approximate.

SECTION 1 • INTRODUCTION

Cumberland is committed to developing a mine that maximizes benefits and minimizes or reduces potential negative impacts. The approach taken by Cumberland is to weigh and consider possible project alternatives before final design decisions are made. Examples of alternatives that have been evaluated for the project include:

- tailings disposal methods
- waste rock storage facilities
- blasting practices
- milling process
- permanent versus winter access road
- power supply at Baker Lake or at site, barge-mounted or on land.

It should be recognized that project development is ongoing, and issues may arise that require the consideration of new alternatives or the re-evaluation of concepts that were previously considered but not selected. Most major project decisions will be made upon completion of the feasibility study, before the commencement of detailed design. Other items, such as blast designs, can be modified during operations as experience is gained during mining and processing activities.

The ensuing sections discuss the main alternatives being considered for the project at this time. Other than the “No-Go” alternative, each issue is described according to service requirements, other selection criteria such as environmental impact, and the ability of the selected option to best meet Cumberland’s objectives.

SECTION 2 • THE “NO-GO” ALTERNATIVE

In the “No-Go” alternative, the Meadowbank mine project would not be developed. None of the potential impacts from project development would occur, and the natural conditions would remain essentially the same. No other currently foreseeable factors would affect the resources.

Possible reasons for implementing the “No-Go” alternative include regulatory denial of one or more of the permits necessary for project development; and/or Cumberland deciding to abandon the project either due to unsatisfactory project economics (higher development and production costs, lower gold prices) or in order to direct its mine development resources elsewhere.

Under this scenario, all existing site facilities would be decommissioned. All buildings, structures, and non-native materials would be removed, and disturbed land would be reclaimed. The test trenches in the Third Portage and Vault areas and adjacent trails would be backfilled to encourage native plant growth and minimize erosion and sediment transport. Contaminated soils would be collected and, if practical, remediated on site.

SECTION 3 • SITE & FOOTPRINT

This section describes the sites and footprints considered during the prefeasibility and feasibility phases for major elements of the project: the process plant, open pits and dewatering dikes, waste rock piles, tailings storage impoundment, airstrip, and Vault haul road. The selected locations for these facilities are shown in Figure 3.1.

3.1 PLANT SITE OPTIONS

The plant site area will include the process facilities, service complex, camp complex, power plant, and fuel storage and distribution facility. Six potential plant site locations were assessed (see Figure 3.2):

- **Site 1**, on the eastern end of South Camp Island, previously used for the exploration camp
- **Site 2**, on a small isthmus east of Goose Island
- **Site 3**, immediately west of the Third Portage deposit, on the isthmus between Second Portage and Third Portage lakes; **Site 4**, to the northwest of Site 3
- **Site 5**, on a prominent ridge to the north of the northwest end of Second Portage Lake
- **Site 6**, on the north side of Second Portage Lake, near to the location of the proposed Portage rock storage facility.


The following criteria were used to evaluate these potential plant sites:

- proximity to ore resources
- flat/gentle grades with good foundation and drainage conditions
- compatibility with future access requirements.

Site 3 was selected for the following reasons:

- central location between the Portage and Goose Island deposits
- proximity to the tailings disposal site
- relatively large area of flat, though elevated, terrain, providing enough room for the proposed facilities and permitting the airstrip to be conveniently located immediately to the northwest
- competent bedrock at or close to surface for good foundation conditions
- remote from culturally sensitive areas
- best opportunity for water management and spill containment
- least overall land disturbance.

CADD FILE: N:\Bur-Graphics\Projects\2005\1413\05-1413-036A\1050\CAD\1300 Project Alternatives\051413036A-1050-3.1.dwg
REVISION DATE: 05/10/19 9:55am By: areddy



LEGEND


SD: Saddle Dam


NOTES

- 1) Topographic contour interval 2m.
- 2) Bathymetric contour interval 1m.

REFERENCES

- 1) Amec Americas Ltd., Drawing Number A1-131395-100-C-0001 (100-C-0001.DWG), Meadowbank Feasibility Study, April 2005.

PROJECT		CUMBERLAND RESOURCES LTD.									
TITLE		GENERAL SITE PLAN									
		PROJECT No.		05-1413-036A		FILE No.		051413036A-1050-3.1			
		DESIGN		CJC	17OCT05		SCALE		AS SHOWN	REV.	0
		CADD		WLI	17OCT05		FIGURE 3.1				
		CHECK		CJC	17OCT05						
		REVIEW		CJC	17OCT05						



REFERENCES

- 1) Amec Americas Ltd., Drawing Number A1-131395-100-C-0001 (100-C-0001.DWG), Meadowbank Feasibility Study, April 2005.

NOTES

- 1) Topographic contour interval 2m.
- 2) Bathymetric contour interval 1m.

PROJECT			CUMBERLAND RESOURCES LTD.		
TITLE			LOCATION OF PLANT SITE OPTIONS		
PROJECT No.	05-1413-036A	FILE No.	051413036A-1050-3.2		
DESIGN	CJC	30SEP05	SCALE	AS SHOWN	REV.
CADD	WLI	30SEP05	FIGURE 3.2		
CHECK	CJC	30SEP05			
REVIEW	CJC	19OCT05			



Site 1 was rejected because of its greater distance from the Portage deposit and consequent higher ore haulage costs. Site 2 encroaches into an area of possible cultural sensitivity. Site 4 is less central than Site 3 and offers no specific advantages. Site 5 was rejected because of its distance from the tailings storage facility, and its distance from the Portage and Goose Island deposits.

3.2 OPEN PIT LIMITS & DEWATERING DIKE LOCATION

The location of the open pit is determined by the position of the ore body and alternatives are focused on pit optimization. Three geological models were built outlining the gold bearing zone. After resource modelling was completed, these models were examined individually to determine the potential for open pit mining of each area. Pit designs were created for each model and measured and indicated mineralization above the economic cut-off. Pit optimization block models was exported from GEMCOM® to Whittle 4X®

A series of pit shells were created at various gold prices utilizing a varying revenue factor between 0.3 and 2.0, these pit shells were then reviewed with Cumberland and a selection was made that best fit the profile selected for the project based on the maximum gold available at a selected base case revenue factor.

The locations of the open pits are as shown on Figure 3.1

3.2.1 Portage Area Open Pits

The footprint area of the Portage and Goose Island open pits have increased since the Meadowbank Prefeasibility Study was completed, as additional reserves have been identified. At the time the Prefeasibility Study was completed, it was envisaged that the Third Portage and North Portage deposits would be mined as two separate open pits. Additional exploration activities have resulted in the delineation of additional reserves beneath Second Portage Lake that allow the Third and North Portage deposits to be mined by a single open pit, known as the Portage pit.

The currently defined Portage pit will be approximately 1,800 m in a north-south direction and approximately 300 m in an east-west direction, and will be mined to a maximum depth of about 120 m. The pit will extend from just south of the Third Portage peninsula, northward across Second Portage Lake to include the North Portage deposit.

The Goose Island pit is located approximately 1,000 m south of the Portage pit, as shown on Figure 3.1. The Goose Island pit will be approximately 650 m in a north-south direction and 380 m in an east-west direction and will be mined to a maximum depth of about 170 m.

The Vault pit is located approximately 6 km north of the Portage area. It is envisaged that the deposit will be mined by a single open pit to a maximum depth of about 160 m. The pit will be approximately 930 m in a northeast-southwest direction, and 550 m in a northwest-southeast direction.

3.2.2 Portage Perimeter Dikes

To mine the Portage and Goose Island deposits, a series of perimeter de-watering dikes will need to be constructed east of the Portage deposit, and extending southward to encircle the Goose Island deposit.

The location of the Portage area dikes are shown on Figure 3.1. The locations and alignments of the dikes were selected to provide a nominal set-back distance of approximately 80 m from the toe of the dikes to the pit crests, and to minimize the depth of water through which the dikes will need to be constructed in order to simplify construction and minimize risk. In general the dikes will be constructed through shallow water, up to about 6 m depth. In certain areas, such as the southeast portion of the Goose Island dike, water depths will be greater, up to 20 m.

3.2.3 Vault Area Open Pit

The Vault deposit is located some 6 km northeast of the Portage area deposits. In order to mine the deposit, Vault Lake will need to be de-watered. To accomplish this, a small dike will be constructed at the narrows joining Vault Lake to Wally Lake to the north. The depth of water through this narrows is estimated to be on the order of 2 to 4 m in depth. The location of the Vault pit and the proposed dike are shown on Figure 3.1.

3.3 ALTERNATIVE CONTROL STRATEGIES FOR MINE WASTE DISPOSAL IN COLD REGIONS

The generation of acidic drainage is a concern for mining projects. In evaluating the potential control strategies for the disposal of the mine waste at the Meadowbank project, consideration was given to control strategies that are effective in cold regions. Many reports have been prepared that relate to the disposal of mine waste in cold regions. The Mine Environment Neutral Drainage (MEND) program was initiated in 1989 by the Canadian mining industry, non-government organizations, and provincial and federal governments to develop and apply scientifically based new technologies for predicting, monitoring, treating, preventing, and controlling acidic drainage from mining activities. The MEND initiative developed a set of technologies available to all stakeholders. Under this program Some reports under this program that are relevant to the Meadowbank project are listed in Table 3.1.

Common control strategies for the prevention or reduction of acid mine drainage are:

1. Control of acid generating reactions
2. Control of migration of contaminants
3. Collection and treatment.

In assessing the overall control strategies for the Meadowbank project, an emphasis has been placed on methods that satisfy items (1) and (2) in the above list, which then have an impact on item (3), collection and treatment by potentially reducing the requirements for these activities.

Various acid mine drainage control alternatives (Dawson and Morin; MEND 1.61.2, 1996) for Arctic areas are listed in Table 3.2.

Table 3.1: MEND Project – Report Listing

MEND Project	Title	Year
6.1	Preventing AMD by Disposing of Reactive Tailings in Permafrost	1993
1.61.1	Roles of Ice, in the Water Cover Option, and Permafrost in Controlling Acid Generation from Sulphide Tailings	1996
1.61.2	Acid mine Drainage in Permafrost Regions: Issues, Control Strategies and Research Requirements	1996
1.61.3	Column Leaching Characteristics of Cullaton Lake B and Shear (S) – Zones Tailings Phase 2: Cold Temperature Leaching	1997
1.62.2	Acid mine Drainage Behaviour in Low Temperature Regimes – Thermal Properties of Tailings	1998
W.014	Managing mine Wastes in Permafrost Zones, Summary Notes MEND Workshop	1997
5.4.2d	MEND Manual, Volume 4 – Prevention and Control, Chapter 4.8 Permafrost and Freezing	2001
1.61.4	Covers for Reactive Tailings Located in Permafrost	2004

Table 3.2: Acid Mine Drainage Control Strategies for the Arctic

Strategy	Tailings	Waste Rock
Freeze Controlled	Total or perimeter freezing options can be considered Can freeze up to greater than 15 m annually if freezing in thin layers Process chemicals could cause high unfrozen water contents	Requires considerable volumes of non-acid waste rock for insulation protection Better understanding of air and water transport through waste rock required for reliable design
Climate Controlled	May not be a reliable strategy for saturated tailings	Requires control of convective air flow through waste rock, infiltration control with modest measures and temperature controls Better understanding of waste rock air, water, and heat transport for reliable design
Engineered Cover	Special consideration for freeze-thaw effects Availability and cost of cover materials are major impediments	
Subaqueous Disposal	Special considerations for winter ice conditions and pipeline freeze-up	Very difficult to dispose of waste rock beneath winter ice
Collection and Treatment	Costly to maintain at remote locations Long term maintenance cost	
Segregation and Blending	Tailings are normally geochemically homogeneous	May be very effective Research and development on-going

Reference: (MEND 1.61.2, 1996).

3.3.1 Summary

A review of control strategies for mine waste disposal, both waste rock and tailings, in cold regions has been presented. The following lists aspects of the project that must be considered in selecting an overall waste management philosophy:

- The Meadowbank project site is located in the zone of continuous 'dry' permafrost.
- The permafrost is classified as 'dry', having ice content of less than 10% based on regional permafrost classification maps.
- The permafrost is continuous, and up to 450 to 550 m in depth based on thermal data collected from site since 1996.
- The mean annual air temperature at the site is about -11.3°C.
- The project site is considered to be arid and dry, with mean annual precipitation on the order of about 290 mm (rainfall and estimated snowfall).
- There is a shortage of naturally occurring thaw-stable materials at the site.
- Most of the waste rock that will be produced during mining is potentially acid-generating.
- There is an abundance of acid-neutralizing ultramafic waste rock material at the site. This material has a buffering capacity about five times that of the other waste rock types, and will be available in large quantities during the middle to late stages of mining.
- All of the tailings are acid-generating and metal leaching.

Based on the summary of conditions at the site, the strategies outlined below for waste management are appropriate from a technical perspective.


3.3.2 Waste Rock Disposal Alternatives

Waste rock should be disposed of on land using a total freezing control strategy, followed by a convective insulating cover of acid-neutralizing waste rock. The waste rock will freeze with time, encapsulating the potentially acid-generating waste material within permafrost. The waste rock could be placed in a heaped dump construction in lifts of about 2 to 3 m to allow freezing during placement if required for control of acid mine drainage. The cover material would be coarse to allow the development of convective cooling during winter, and insulation through trapped air within voids during the summer. Given the high evaporation rate and low annual average precipitation at site, the average annual infiltration into the pile is expected to be low. Freeze and climate control strategies for potentially acid-generating rock are shown on Figure 3.3.


3.3.3 Tailings Disposal Alternatives

Due to the arid climate and permafrost environment, tailings should be disposed of in a manner that encourages total freezing as a control strategy. Subaerial disposal is preferred, given the length of time that water at the site is ice covered, allowing the tailings to be frozen in thin layers rather than one thick layer in order to maximize the total frozen thickness. This can be accomplished through the use of slurry pipelines. The tailings will eventually become encapsulated by permafrost, thus limiting oxygen diffusion and water infiltration into the pile, thereby limiting the generation of acid mine drainage. This is shown conceptually on Figure 3.4.


HEAPED CONSTRUCTION




CONSTRUCTION CONFIGURATION



END-DUMPED CONSTRUCTION



RE-SLOPED CONFIGURATION



Freeze Controlled ARD Strategies

Climate Controlled ARD Strategies

Not to Scale

Reference: MEND 1.61.2, 1996


PROJECT		CUMBERLAND RESOURCES LTD.			
TITLE		WASTE ROCK STORAGE FACILITY CONSTRUCTION METHODS			
		PROJECT No.	05-1413-036A	FILE No.	FIGURE 3.3
DESIGN	CJC	05OCT05	SCALE	NTS	REV.
CADD	SS	05OCT05			
CHECK	CJC	05OCT05			
REVIEW	CJC	17OCT05			




FIGURE 3.3

DRAWING DATE: 21-Oct-05 COREL FILE: N:\Bur-Graphics\Projects\2005\1413\05-1413-036A\1050\Corel\1300 Project Alternatives\Figure3.4.cdr


a) YEAR 1 - Winter




b) YEAR 1 - Summer








c) YEAR 2 - Winter



d) YEAR 2 - Summer



-  Starter Dyke
-  Frozen Cell
-  Thawed Tailings
-  Dam Raise
-  Frozen Overboard Material

Reference: MEND 1.61.2, 1996

PROJECT				
CUMBERLAND RESOURCES LTD.				
TITLE				
TAILINGS THIN LAYERED FREEZING DESIGN CONCEPT				
PROJECT No. 05-1413-036A			FILE No. FIGURE 3.4	
DESIGN	CC	06OCT05	SCALE NTS	REV.
CADD	SS	06OCT05	FIGURE 3.4	
CHECK	CC	06OCT05		
REVIEW				



Capping of the tailings storage facility would consist of the placement of a coarse convective insulating layer of ultramafic rock over the facility to a minimum depth of about 2 m. This thickness is consistent with other cover designs over reactive tailings in the north (see Figure 3.5). During winter, convective heat transfer developed within the coarse cover material will transfer heat out of the tailings pile; during the summer trapped air within the voids will act as insulation. This will limit the depth of annual thaw penetration to within the acid-neutralizing ultramafic waste rock. During detailed design, a cover design will be developed that will consider the addition of a fine-grained layer of soil material as a base layer to the coarse rock cover. This layer would retain moisture within it, resulting in a reduction in the thickness of the active layer. It is possible that this layer could consist of till material dozed in a thin layer over the tailings facility. There are sufficient quantities of till material that will be produced during pre-mining and pre-stripping that could be stockpiled and used for this purpose.

The above discussion has presented a basis for the initial consideration of waste disposal strategies in continuous permafrost environments. Additional discussion and analysis to determine the best management strategy for the Meadowbank project are presented in the following sections, and in supporting documents. The following presents a case history of disposal of reactive mine tailings subaerially within a natural rock basin.

3.4 MINE WASTE STORAGE ALTERNATIVES

Mine waste storage alternatives, both rock and tailings, were evaluated using a decision matrix approach whereby a series of selection criteria were developed to describe environmental, operational, and economic factors and to allow a comparison of the relative importance of these factors for the different sites and for the different waste streams.


The process used to evaluate the alternatives associated with the following:

- identifying potential locations
- developing a site-specific decision matrix model to evaluate, rank, and select the best overall facility or facilities.


Decision matrix types of analyses are also sometimes referred to as Multiple Accounts Analyses (MAA) or alternatives analyses. These types of analyses have been used as site selection tools for tailings facilities and other mining-related decision processes at the following: Zortman and Landusky mine sites, Montana (Shaw et al, 2001); Red Dog mine, Alaska (Northern Liner, 2005); and Questa Molybdenum mine, New Mexico (Molycorp Watch project). Numerous papers have been published on the subject of MAA, including: Robertson and Shaw (1998 and 1999); Caldwell and Robertson (1983); Vick (1990); Brown (2002); and the Decision Makers Field Guide (2005).

Similar types of analyses are also used in the fields of risk assessment, risk management, selection of the best available technologies or options for environmental remediation projects, resource planning, and sustainable development (Canter, 1985; International Atomic Energy Agency, 2000; CH2MHill, 2004, Robson Valley Land and Resource Management Plan, 1999).


CADD FILE: N:\Bur-Graphics\Projects\2005\1413\05-1413-036A\1050\CAD\1300 Project Alternatives\051413036A-1050-3.5.dwg
REVISION DATE: 05/10/21 10:52am By: sreddy




LEGEND:



Typical Insulating Cover Options for Total Freezing in Continuous Permafrost Regions (after MEND 6.1, 1993)



Cover Design Concepts for Reactive Tailings at Existing Mine in Permafrost (reference: MEND 1.61.4, 2004)



Test Pad Statigraphies at Nanisivik Mine (reference: MEND 1.61.4, 2004)

PROJECT		CUMBERLAND RESOURCES LTD.			
TITLE		INSULATING COVER DESIGN FOR TOTAL FREEZING IN CONTINUOUS PERMAFROST			
PROJECT No.		05-1413-036A		FILE No.	
DESIGN		CJC	06OCT05	SCALE	
CADD		BAD	06OCT05	NTS	
CHECK		CJC	06OCT05	REV.	
REVIEW		CJC	17OCT05	0	



FIGURE 3.5

Four reports have been issued describing the strategy for selecting the waste rock storage facility and detailing the mine waste and water management plan:

- Golder Associates Ltd., Report on Evaluation of Tailings Alternatives, Meadowbank Project, Nunavut. October 2005 – See Appendix A.
- Golder Associates Ltd., Report on Evaluation of Waste Rock Management Alternatives, Meadowbank Project, Nunavut. October 2005 – See Appendix B.
- Golder Associates Ltd., Report on Alternative Waste and Water Management Plan, Meadowbank Gold Project, Nunavut. 7 March 2005.
- Golder Associates Ltd., Report on Mine Waste and Water Management, Meadowbank Gold Project, Nunavut. 5 March 2004.

The reports “Evaluation of Tailings Alternatives” and “Evaluation of Waste Rock Management Alternatives” are contained as appendices to this report.

The objectives of the above reports was to identify the most appropriate method for disposal of waste rock and tailings for the Meadowbank project based on an evaluation of technical, environmental, and economic considerations. The requirements for each facility are as follows:

- minimal net adverse effects on the environment, now and in the future
- technically sound with the minimal potential for failure
- economic.

The contributions of the three primary categories to the overall decision-making process are shown for the baseline conditions for the rock and tailings storage facilities in Table 3.3.

Table 3.3: Relative Contribution of Primary Categories to Decision Analysis

Primary Category	Contribution to Overall Weighting Rock Storage	Contribution to Overall Weighting Tailings Storage
Environmental	50%	55%
Operational	30%	33%
Cost	20%	12%

Each of the primary categories was subdivided to consider other sub-indicators.

3.4.1.1 Scale Factor

In order to separate the best alternatives from the worst, a scaling (or scoring) factor was applied. Each sub-indicator was assigned a score between 1 and 9 points, similar to the system described by Robertson and Shaw (1999). The scores provide a relative ranking between the options with the best option receiving a score of 9, and the worst a score of 1. All subsequent options were then compared

to the best option and assigned a lower relative score. An example of the scoring method is shown in Table 3.4.

Table 3.4: Example of Scoring System used in Decision Matrix

	Footprint Area	Points	Notes
Option A	30 ha	9	9 points awarded for least footprint area (BEST)
		8	-
		7	-
		6	-
Option C	60 ha	5	9 points x 30 ha (least area) / 60 ha = 5 points
		4	-
Option B	90 ha	3	9 points x 30 ha (least area) / 90 ha = 3 points
		2	-
		1	-

3.4.1.2 Relative Weighting Factor

Each sub-indicator of the primary categories was assigned a relative weighting factor to introduce a value bias between the individual sub-indicators, based on the relative subjective importance of one indicator versus another. A higher weighting factor indicates a perceived greater relative value or importance between sub-indicators. For example, the relative importance of the impact of acid mine drainage is considered greater than the visual impact of the facility. Consequently, the sub-indicator of acid mine drainage is given a relative weighting factor that is greater than the weighting factor for visual impact.

The weighting factors used for the evaluation of the waste rock storage alternatives are shown in Table 3.5, along with the maximum possible weighted score and category score if a sub-indicator was given the maximum possible individual score of 9.

The weighting factors used for the evaluation of the tailings storage alternatives are shown in Table 3.6, along with the maximum possible weighted score and category score if a sub-indicator was given the maximum possible individual score of 9.

The individual sub-indicator weighting values were then multiplied by the score to arrive at a weighted score. The weighted scores for each category were then summed to arrive at a total weighted score for each option. The best alternative for waste rock and tailings disposal was then determined as the alternative having the highest overall score, relative to the other alternatives.

Table 3.5: Weighting Factors for Sub-Indicators for Rock Storage Facility Selection

Factor	Sub-Indicator	Relative Weighting	Max, Possible Score	Max. Weighted Score ¹	Max. Category Score ¹
Environmental	Sub-catchment area	5	9	45	396
	Footprint area	4	9	36	
	Potential for generating dust	4	9	36	
	Potential for acid rock drainage (ARD) generation during operation	3	9	27	
	Potential for metal leaching (ML) during operation	3	9	27	
	Potential for seepage to impact groundwater	6	9	54	
	Potential for geotechnical hazards ²	6	9	54	
	Lake area impacted	7	9	63	
	Visual impact	6	9	54	
Operational	Difference between crest and adjacent land	5	9	45	234
	Ease of water management	7	9	63	
	Catchment Impacted	6	9	54	
	Ease of decommissioning/closure	8	9	72	
Economic	Distance from north edge of North Portage pit	18	9	162	162
Total					792

Notes: 1. Values represent the maximum score, if 9 points was assigned for each sub-indicator. 2. Includes consideration of foundation conditions, impact of seismicity, and height of structure.

Table 3.6: Weighting Factors for Sub-Indicators for Tailings Facility Evaluation

Factor	Sub-Indicator	Relative Weighting	Max, Possible Score	Max. Weighted Score ¹	Max. Category Score ¹
Environmental	Sub-catchment area	1	9	9	603
	Footprint area	1	9	9	
	Potential for generating dust during operation	6	9	54	
	Potential for generating dust after closure	4	9	36	
	Potential for acid rock drainage (ARD) generation during operation	5	9	45	
	Potential for ARD generation after closure	7	9	63	
	Potential for metal leaching (ML) during operation	2	9	18	
	Potential for ML after closure	5	9	45	
	Potential for seepage to impact groundwater during operation	5	9	45	
	Potential for seepage to impact groundwater after closure	6	9	54	
	Potential for geotechnical hazards ²	5	9	45	
	Lake area impacted	5	9	45	
	Number of lakes impacted	4	9	36	
	Visual impact	2	9	18	
	Relative loss of high value fish habitat	9	9	81	
Operational	Ease of operation	9	9	81	351
	Distance from mill	8	9	72	
	Potential for delays due to freezing	10	9	90	
	Construction risk	4	9	36	
	Disposal system has precedent in arctic environment	8	9	72	
Economic	Total present value of costs (initial cost + delayed costs)	15	9	135	135
Total					1089

Notes: 1. Values represent the maximum score, if each sub-indicator assigned a maximum scoring factor of 9 points.
2. Includes consideration of foundation conditions, impact of seismicity, and height of structure.

3.5 EVALUATION OF WASTE ROCK DISPOSAL ALTERNATIVES

Mine rock storage facilities will be developed in both the Portage and the Vault mining areas. The complexity of disposing of potentially acid-generating mine tailings and mine waste rock in a permafrost environment presents specific challenges primarily due to climatic conditions. Consequently, any type of waste disposal facility in the Arctic must take into consideration these

challenges. Control strategies such as freeze control and climate control are commonly used in permafrost environments as effective methods for controlling ARD.

Because of the distance between the Portage and Vault deposits it was decided that two waste rock storage facilities were required. One storage facility near the Vault pit was selected on the basis of available on-land storage space near this pit, topographic relief, and the desire to have the facility located within the same watershed as the open pit. The rock storage facility near the Portage deposit (called Portage waste rock storage) was selected to dispose of waste rock generated from the Portage and Goose Island open pits.

Primary objectives established for the selection of an appropriate waste rock storage facility (or facilities) were to:

- minimize potential long-term environmental impacts (including ARD generation, metal leaching, seepage to the underlying groundwater regime)
- maximize ease of water management during operation
- maximize ease of decommissioning/closure
- minimize catchment area impacted
- minimize dust generation
- minimize visual impact
- minimize areas of lakes impacted
- minimize footprint area (to reduce the volume of affected runoff)
- minimize the potential for geotechnical hazards (including slope instability, seismic risk)
- minimize haul costs.


3.5.1 Portage Rock Storage Alternatives

Four areas on the north side of Second Portage Lake were considered as potential waste rock storage areas. The weighted scores for the various options are summarized in Table 3.7; the storage options are illustrated on Figure 3.6. The full decision matrix is contained in the supporting documentation in the appendices.

Table 3.7: Summary of Weighted Scores for Rock Storage Facility Options

Option	Description	Weighted Score
A	North from Second Portage Lake – small footprint	560
B	Northwest from Portage Lake – large footprint	459
C	East from Vault Haul Road – small footprint	436
D	East from Vault Haul Road – large footprint	355

Note: The highest score indicates the most desirable option.



The options were evaluated using a decision matrix as described above where individual sub-indicators within three key categories—environmental, operational, and cost considerations—were assigned “weight” values based on subjective estimates of their relative importance. In this exercise, overall weighting factors of 50% were assigned to environmental considerations, 30% to operational considerations, and 20% to cost factors for each option.

The options were allocated a score for each of the evaluation criteria listed above to show the relative difference between options. Weighted scores were derived by multiplying the allocated scores by the individual sub-indicator weighting values and summing the totals. The highest score indicates the most desirable option. On this basis, option A, on-land disposal of rock on the north side of Second Portage Lake, was selected as the preferred rock storage facility. The facility is predicted to eventually freeze, resulting in a reduction in the rates of acid mine drainage over the long-term. This methodology is a common strategy used in cold climates and takes advantage of permafrost and climate conditions. The site will be progressively reclaimed and capped with acid-neutralizing ultramafic rock.

3.5.2 Vault Waste Rock Storage Alternatives

There are few suitable locations for a waste rock storage facility near the Vault pit owing to the presence of numerous lakes adjacent to Vault Lake and the lack of topographical relief in the immediate area. The lack of topographical relief limits the height to which a rock storage facility can be constructed without becoming visible at great distance from the site. In addition, placing waste rock in areas south of Vault Lake would affect a sub-watershed that does not drain toward the Vault open pit.



As with the Portage rock storage facility, the Vault facility was selected based on consideration of the following criteria:

- the potential for long-term environmental impacts, including ARD generation and metal leaching
- ease of water management during operation and closure
- ease of decommissioning and closure
- impact on lakes and catchment areas
- visual impact
- footprint size to reduce the volume of affected runoff
- the potential for geotechnical hazards, such as slope instability and response to seismic activity
- haulage costs.

Alternatives that were considered are shown on Figure 3.7 and listed below:


- *Immediately west of the Vault pit (option A)* – This alternative consists of a broad, relatively flat area within the catchment area of the Vault pit. This alternative offers the advantage of allowing the storage facility to be developed with a low profile, reducing the potential visual impact as well as reducing the potential impact to wildlife movement. The location of option A results in the least travel distance for waste rock haulage and disposal.

REVISION DATE: 05/10/17 4:05pm By: ggoreczynski CADD FILE: N:\Bur-Graphics\Projects\2005\1413-05-1413-036A\1050\CAD\1300 Project Alternatives\051413036A-1050-3.7.dwg



REFERENCES

1) AMEC Americas Ltd., Drawing Number A1-131395-100-c-0001 (100-c-0001.dwg), Meadowbank Feasibility Study, April 2005.

PROJECT		CUMBERLAND RESOURCES LTD.	
TITLE			
VAULT ROCK STORAGE OPTIONS			
	PROJECT No.		05-1413-036A
	FILE No.		051413036A-1050-3.7
	DESIGN	CJC	17OCT05
	CADD	GG	17OCT05
CHECK	CJC	17OCT05	FIGURE 3.7
REVIEW	CJC	17OCT05	
SCALE		AS SHOWN	REV. 0

- *South of the Vault deposit (options B1 and B2)* – This alternative was rejected as it places the waste rock material within a catchment area and sub-watershed that previously remained unaffected.
- *On-land storage to the east of Vault Lake (option C)* – This alternative was rejected due to the small area in which to store the waste rock, and due to the distance from the deposit area, which would result in an increase in the overall footprint area for the mine development, as well as an increase in haulage costs. The smaller area in which to store the material would result in a waste dump with a higher final elevation, resulting in visual impact as well as exposure to wind dispersion. The additional distance for haulage would require the construction of additional roads. Increased traffic would result in increased levels of particulate matter (including dust and exhaust) to the atmosphere to be transported and deposited elsewhere.
- *Disposal into Wally Lake (option D)*. This alternative was rejected because there is no convincing evidence to suggest that placing the Vault waste rock material in a submerged environment will have less impact than placing on land. Placing the waste rock into Wally Lake would unnecessarily impact on fish habitat within that lake.

The best alternative for the storage of the waste rock from the Vault pit is on a broad area of land immediately to the west of the open pit area. A cover layer of non-PAG rock is not presently required at the Vault waste rock storage facility because this rock is considered to be non-PAG. Further testing and monitoring during operations will be completed to confirm this.

3.6 EVALUATION OF TAILINGS STORAGE ALTERNATIVES

3.6.1 Tailings Initial Site Selection Criterion

A list of initial site selection criterion that any tailings storage facility for the Meadowbank mine site must meet was developed. This list was used as an initial screening tool, and any locations that did not meet these criteria were eliminated from further analysis. The following key site selection criteria were utilized:

- the site should have sufficient volume to store planned volume of tailings
- the site should have the potential to provide additional capacity for tailings storage
- the location should be able to accommodate mine expansion
- the location should be within catchments of the open pits
- the site should allow the control and collection of the tailings supernatant.

Sites that failed to meet the initial site selection criteria were removed from further consideration.

3.6.2 Tailings Disposal Alternatives

Initially seven potential tailings storage sites were identified (see Figure 3.8). These are listed in Table 3.8 along with the disposal methodology for each site.



Table 3.8: Summary of Initial Tailing Storage Alternatives

Option	Location	Disposal Type
A	Second Portage Arm and North Portage Pit	Subaqueous Slurry
B	Second Portage Arm	Subaerial Paste or Drystack
C	Second Portage Arm	Subaerial Slurry
D	Third Portage Lake	Subaqueous Slurry
E	East from Vault Haul Road	Subaerial Slurry
F	North of Second Portage Arm	Subaerial Slurry
G	North of Second Portage Arm	Subaerial Paste or Drystack

These alternatives were then compared to the initial site selection criteria, as a pre-screening process, prior to conducting the overall decision matrix analysis. Based on the pre-screening assessment, only four of the initial seven options met the site selection criteria. These four are listed in Table 3.9.

Table 3.9: Alternatives Evaluated Using the Decision Matrix

Option	Location	Disposal Type
B	Second Portage Arm	Subaerial Paste or Drystack
C	Second Portage Arm	Subaerial Slurry
F	North of Second Portage Arm	Subaerial Slurry
G	North of Second Portage Arm	Subaerial Paste or Drystack

All locations and methods that met the initial criterion proceeded to the next phase of analyses which involved the use of the decision matrix as described above.

3.6.3 Base Line Analysis

Tailings facility options B, C, F, and G for the proposed Meadowbank project were evaluated using the decision matrix method of analysis described above. Table 3.10 summarizes the results. The highest score represents the best alternative for site conditions.

Table 3.10: Summary of Baseline Analysis Decision Matrix Results

Factor	Options			
	B Second Portage Arm Subaerial Paste	C Second Portage Arm Subaqueous/ Subaerial Slurry	F West of Waste Rock Storage Subaerial Slurry	G West of Waste Rock Storage Subaerial Paste
Environmental	438	475	372	432
Operational	263	216	160	256
Economic	60	135	75	60
Total	761	826	607	748

The full decision matrix is contained in the supporting documentation in the appendices.

3.6.4 Sensitivity Analyses

In order to evaluate the decision analysis process to changes in the weightings and the perceived relative importance of certain factors, three sensitivity analyses were completed.

3.6.5 Sensitivity Analysis – Part 1

To consider the impact of the weighting factors used in the decision matrix, a sensitivity analysis was conducted with all sub-indicator weightings set equal to one. This results in each of the sub-indicators having equal importance in the decision process and removes the value bias between the sub-indicators that might be imposed by personal preferences. The greatest numbers of sub-indicators were associated with the environmental category, while the lowest numbers of sub-indicators were associated with the economic category. Consequently, the relative importance of each category is determined by the number of sub-indicators representing that category. Based on the revisions to the weightings, the relative distribution of influence on the weighted total is:

Environment.....71%
Operational24 %
Economic5%

The results of this analysis are summarized Table 3.11.

Table 3.11: Summary of Decision Matrix Results – Sensitivity Analysis (Part 1)

Factor	Options			
	B Second Portage Arm Subaerial Paste	C Second Portage Arm Subaqueous/ Subaerial Slurry	F West of Waste Rock Storage Subaerial Slurry	G West of Waste Rock Storage Subaerial Paste
Environmental	106	113	91	104
Operational	31	26	23	34
Economic	4	9	5	4
Total	141	148	119	142

As with the baseline case, option C received the highest overall score although only marginally better than options B and G.

3.6.6 Sensitivity Analysis – Part 2

An additional sensitivity analysis was carried out by excluding economic factors, and by reducing the effect of operational factors. The resulting decision matrix was weighted strongly towards the influence of environmental factors. Based on the revisions to the weightings, the relative distribution of influence on the weighted total is:

Environment.....	89%
Operational	11%
Economic.....	0%

Table 3.12 summarizes the results of the analysis.

Table 3.12: Summary of Decision Matrix Results – Sensitivity Analysis (Part 2)

Factor	Options			
	B Second Portage Arm Subaerial Paste	C Second Portage Arm Subaqueous/ Subaerial Slurry	F West of Waste Rock Storage Subaerial Slurry	G West of Waste Rock Storage Subaerial Paste
Environmental	438	475	372	432
Operational	8	40	72	64
Economic	0	0	0	0
Total	446	515	444	496

The analysis indicates that when the decision matrix is heavily weighted towards the consideration of environmental factors, option C (tailings slurry disposal in Second Portage Lake) is the preferred option.

3.6.7 Sensitivity Analysis – Part 3

A final sensitivity analysis was carried out on the baseline case to evaluate the effect the proposed methods of disposal may have on fish and fish habitat. For this case, issues relating specifically to impact on fish and fish habitat were adjusted to weight these indicators high in the overall analysis. Based on the revisions to the weightings, the relative distribution of influence on the weighted total is:

Environment.....	57%
Operational	31%
Economic.....	12%

The relative weighting factor for “number of lakes impacted” and “impact on fish and fish habitat” were adjusted so that these two indicators carried the highest relative weights of all the environmental sub-indicators. The scale factors for the sub-indicator “number of lakes impacted” remained the same as the previous analyses, as the number of lakes impacted by either on-land or in lake disposal is the same regardless of the disposal method selected. The scale factors for the sub-indicator “impacts on fish and fish habitat” however were increased to the maximum possible value of 9 for on-land disposal, representing the best possible case, and were maintained at the least possible value of 1 for disposal in Second Portage Arm, representing the worst possible case. The result of this re-scaling is that “impacts on fish and fish habitat” and “number of lakes impacted” contribute between 31% and 35% to the overall environmental weighting for on-land storage, compared with 13% to 17% contribution for disposal within Second Portage Arm

Table 3.13 summarizes the results of the analysis.

Table 3.13: Summary of Decision Matrix Results – Sensitivity Analysis (Part 3)

Factor	Options			
	B Second Portage Arm Subaerial Paste	C Second Portage Arm Subaqueous/ Subaerial Slurry	F West of Waste Rock Storage Subaerial Slurry	G West of Waste Rock Storage Subaerial Paste
Environmental	468	520	462	522
Operational	263	216	160	256
Economic	60	135	75	60
Total	791	871	697	838

The analysis indicates that when environmental factors are weighted heavily towards impact on lakes and on fish habitat, disposal on-land or in Second Portage Lake carry equivalent total environmental weighting, resulting in a 'null' decision based on that category alone. When economic and operational issues are considered in the decision analysis, then option C, disposal of slurry tailings in the basin of Second Portage Arm, is the preferred option.

Based on the decision matrix method, option C (tailings slurry disposal in the northwest arm of Second Portage Arm) is the best tailings management strategy for the Meadowbank project site. The primary advantages provided by option C are as follows:

- lowest potential for the generation of acidic drainage and the release of metal constituents to the environment
- lowest potential for the generation of dust from the facility during operations and closure, and consequently the lowest potential for transportation and deposition into lakes or on land downwind of the facility and off-site
- simplest construction methodology requiring construction materials from the mining activities
- simplest closure methodology, requiring least amount of borrow materials, and utilizing the natural environment to encapsulate the tailings
- low risk of instability of tailings facility, and hence lower risk of potential release of tailings to the environment
- ease of operation in harsh Arctic climates
- lowest relative capital cost
- precedence in Arctic climate.

The primary disadvantage of the proposed disposal method is that the northwest arm of Second Portage Lake will be permanently filled. However, regardless of the tailings disposal strategy adopted for the project, the northwest arm of Second Portage Lake will be impacted in one form or another by mining activities. The arm of the lake will need to be completely de-watered in order for mining to be

undertaken. If the tailings are disposed of on land, there will still be a requirement for attenuation storage and reclaim water management. It is likely that the northwest arm of the lake would be used for these purposes.

3.7 ASSESSMENT OF THE STRATEGY TO FREEZE THE PORTAGE TAILINGS FACILITY

A strategy of total freezing of the tailings will be used to control ARD and ML. Permafrost encapsulation of the tailings is the preferred management alternative for the project.

3.7.1 Thermal Modelling

Simplified thermal modelling of the proposed tailings deposit in the northwest arm of Second Portage Lake was carried out to predict the range of time required to freeze the tailings and into the underlying talik. The detailed analyses were presented previously in:

- Golder Associates Ltd., Technical Memorandum - Item #56 - Tailings thermal Modelling and Climate Change Effects. 22 July 2005.
- Golder Associates Ltd., Report on Thermal Modelling of the Tailings Deposit in the Second Portage Lake, Meadowbank Gold Project. 16 February 2004.

The assumptions and results of the modelling are summarized in the following sections.

3.7.2 Assumptions

Site climate data were considered with various snow packs to represent ground covers of snow, soil, and vegetation to estimate the range of surface temperature functions on the bedrock profile. Ground temperatures were estimated using each of the surface temperature functions and compared to site thermistor data for calibration.

Thermal properties for the bedrock and tailings materials were estimated from published correlations for the range of expected geotechnical conditions. In addition, the following assumptions were used in the modelling:

- Only bedrock was considered in the subsurface profile.
- A constant temperature boundary of 4°C was used at the bottom of the lake.
- All the tailings were assumed to be placed instantaneously.
- Tailings were deposited at either 6°C (unfrozen) or -0.2°C (frozen) to bind the expected deposition sequence.

3.7.3 Impact of Climate Change

To investigate the potential effect of climate change, the precautionary principal was applied to consider the effect of a temperature increase of 5.5°C over the next century. For this simplified model, the effect of climate change is considered by uniformly incrementing the annual average temperature

function by 5.5°C over the first 100 years in the model and then maintaining a constant mean monthly temperature for the next 200 years. The prediction of climate change beyond 100 years is considered to be unreliable due to unpredictable variables.

3.7.3.1 Accepted Climate Change Predictions

The climate change considered in the Meadowbank Gold project feasibility design followed the worst case “high sensitivity” models described in the precautionary principal (INAC, 2003 “Implications of Global Warming and The Precautionary Principle in Northern mine Design and Closure”). These models suggest that an increase of 5.5°C to the mean annual air temperature (MAAT) by the year 2100 for a site located at 65°N latitude is reasonable for climate change predictions. Table 3.14 presents a summary of reported climate change predictions used on a number of northern projects that have been reported in the engineering and scientific literature.


Table 3.14: Summary of Reported Climate Change Rates Used in Northern Projects Engineering Studies


Reference	Increase in MAAT by Year 2100 (°C)	Notes
INAC (2003)	5.5	Used in Meadowbank DEIS for site at 65° North Latitude
Hayley (2004)	4.7	Used in design studies for the Inuvik Regional Health Center. Reported as increase of 0.47°C per decade.
Hayley and Cathro (1996)	5.0	Used for Raglan Dam analyses.
Mackenzie Valley Land and Water Board (2002)	3.0	Used for the Ekati mine expansion
Diavik	3.2	Used for the Processed Kimberlite Containment Facility Design
Burn (2003)	6.0	For use in the Western Arctic for pipeline design projects. Reported as increase of 1.75°C over a 29 year period
IPCC (2003)	0.8-5.2	Predicted range for change in the global average surface air temperature

For comparison purposes, climate records for Baker Lake were reviewed. Figure 3.9 presents the complete record of MAAT data from Baker Lake weather station for the period between 1951 and 2004, during which time the long-term MAAT is reported as being -11.9°C. A linear regression of the data for this period indicates an increase in MAAT of about 2°C when projected over a 100-year period. Trend lines for a climate change rates of 2°C and 5.5°C for 100 years are also shown on Figure 3.9.

Consequently, a climate warming trend of 5.5°C for 100 years is considered to be a reasonable upper estimate of the climate change rate for the project area and is consistent with predicted and recommended climate change trends for projects in the north.

**BAKER LAKE, NUNAVUT Latitude=64.3N, Longitude=96.08E, Elevation=18,
WMO Identifier=71926, Data between 1950 and 2004**



PROJECT		CUMBERLAND RESOURCES LTD.			
TITLE		BAKER LAKE WEATHER STATION DATA AND CLIMATE CHANGE TRENDS			
	PROJECT No. 05-1413-036A			FILE No. FIGURE	
	DESIGN	CJC	10OCT05	SCALE	NTS
	CADD	SS	10OCT05	REV.	
	CHECK	CJC	10OCT05	FIGURE 3.9	
	REVIEW	CJC	17OCT05		

3.7.4 Results of Modelling

After establishing the existing ground temperature conditions in the model, the tailings deposit was modelled by instantaneous replacement of the lake with either unfrozen or frozen tailings. The thermal models were run between 100 and 300 years to predict ground temperature profiles beneath the tailings impoundment.

The results indicate that complete freezing of the tailings and bedrock beneath the lake will occur with time. For tailings not frozen during deposition, the time to begin freezing the talik beneath the lake could be as long as 200 years if climate change is not considered and 270 years if climate change is considered.

If the tailings are frozen soon after deposition, the time to freeze 5 m into the talik is between 1 and 45 years, depending on the location within the lake. When climate change is considered, this time is increased to 50 years. Freezing of the tailings will limit the ability of contaminants to migrate beyond the tailings storage facility.

3.7.5 Sensitivity Analysis

To investigate the sensitivity of the model to climate change rate and the predicted time to freeze the tailings deposit, an additional thermal model was developed which considered a 2°C for 100-year climate change rate for the case of the initially thawed (+6C) tailings instantaneously replacing the lake. Table 3.15 presents these results as well as a summary of the predicted times to freeze the initially thawed tailings deposit.


Table 3.15: Time to Freeze at Base of Tailings (38 m) for Initially Thawed Tailings

Ts function (MAGT ¹) Based on	MAGT (°C)	MAGT after 100 Years (°C)	Time to Freeze Initially Thawed Tailings Deposit (Years)
Site Measured Soil Temperature	-9.2	-9.2	170
10 % snow pack	-7	-7	200
10 % snow pack and Climate Change of 2C for 100 years	-7	-5	210
10 % snow pack and Climate Change of 5.5C for 100 years	-7	-2.5	270

Note: MAGT is mean annual ground temperature.

As expected, an increase in MAGT results in a longer time for the tailings deposit to freeze. From the modelling results, a 2°C climate change rate adds 10 years to the time to freeze, while a 5.5°C climate change rate adds 70 years to the case with no climate change. The variation in time to freeze tailings without consideration for climate change is 30 years when comparing the MAGT based on the climate station data and a 10% snow pack. Figure 3.10 provides a summary of the results of freezing time for the tailings deposit vs. the Ts function.

Second Portage Lake Tailings Thermal Model All Tailings instantaneously placed at +6C



LEGEND:

MAGT - Mean Annual Ground Temperature

PROJECT

CUMBERLAND
RESOURCES LTD.

TITLE

TIME TO FREEZE TAILINGS FACILITY



PROJECT No. 05-1413-036A			FILE No. FIGURE 3.10	
DESIGN	CJC	14OCT05	SCALE NTS	REV.
CADD	SS	14OCT05	FIGURE 3.10	
CHECK	CJC	14OCT05		
REVIEW	CJC	17OCT05		

3.8 AIRSTRIP

In coordination with the selection of the plant site, two options were considered for the site of the airstrip: one along the isthmus between the northwest arm of Second and Third Portage lakes, and the other along the southwest side of Third Portage Lake (see Figure 3.11). Although the more southern route requires less cut and fill, it would involve the construction of a roadway crossing over a narrow section in Third Portage Lake. The selected northern alternative, northwest of the plant site, is better aligned with the prevailing wind direction from the northwest and will permit the development of a more compact site with less overall disturbance.

The alignment of the airstrip has been selected based on minimizing cut and fill requirements for construction and has been based on a near balance of the excavation and backfill quantities. However, it is anticipated that additional fill materials will be required from locally available borrow sources to complete the airstrip embankment. The airstrip will be constructed in two development sequences. The first sequence will involve the construction of a gravel-surfaced pioneer airstrip nominally 915 m long x 30.5 m wide for use by aircraft such as the Beechcraft King Air B200 Jet Prop during the first years of development. This will minimize impact to Third Portage Lake as the entire strip will be constructed on land. Drainage ditches, settling ponds, and silt fences will be used to manage runoff during construction and operation of the pioneer strip. Later in mine life, the airstrip will be extended to about 1,525 m long x 50 m wide for use by larger aircraft such as Hercules and 737 aircraft. This will require the extension of the airstrip by about 380 m off-shore of Third Portage Lake. It is expected that the frequency of usage of the airstrip will be less than 100 takeoffs/landings per month.



The design of the airstrip allows for the use of intermediate volcanic (IV) rock produced from mining activities. The majority of the IV rock is non-acid-generating; however, some is expected to generate acid. The rock will be submerged off-shore, which will reduce the potential for acid generation. A capping of non-acid-generating rock will be placed over the main airstrip rock fill. To achieve the full length of 1,525 m, however, approximately 198,000 m³ of fill will need to be placed at the west end of the strip, extending into the lake.

The alignment of the airstrip has been selected based on minimizing cut and fill requirements for construction and has been based on a near balance of the excavation and backfill quantities. However, it is anticipated that additional fill materials will be required from locally available borrow sources to complete the airstrip embankment. With the current alignment, the initial 915 m long strip can be built while minimizing impact to Third Portage Lake through the use of settlement ponds and silt fencing to control runoff during construction. To achieve the full length of 1,525 m, approximately 198,000 m³ of fill will need to be placed at the west end of the strip, extending into the lake. The design allows the use of PAG mine rock from the Portage pit in airstrip construction. A permanent capping of non-PAG rock from the Portage pit will be placed over the mine rock fill.

3.9 VAULT ACCESS ROAD

The Vault pit is approximately 6 km north of the main project facilities in the Portage area and will be connected by a haul road. A road will need to be constructed to access the Vault pit and to haul ore back to the processing facilities at the Portage area. The road will be constructed with rockfill produced from the Portage pit mining activities. The road embankment will be designed to preserve

CADD FILE: N:\Bur-Graphics\Projects\2005\1413\05-1413-036A\1050\1300 Project Alternatives\051413036A-1050-3.11.dwg
REVISION DATE: 05/10/19 2:36pm By: sreddy



LEGEND


- SD: SADDLE DAM
-  POSSIBLE AIRSTRIP LOCATION


NOTES

- 1) Topographic contour interval 2m.
2) Bathymetric contour interval 1m.

REFERENCES

- 1) Amec Americas Ltd., Drawing Number A1-131395-100-C-0001 (100-C-0001.DWG), Meadowbank Feasibility Study, April 2005.



PROJECT		CUMBERLAND RESOURCES LTD.	
TITLE		AIRSTRIP ALTERNATIVES	
			
PROJECT No.	05-1413036A	FILE No.	051413036A-1050-3.11
DESIGN	CJC	17OCT05	SCALE AS SHOWN
CADD	WLI	17OCT05	REV. 0
CHECK	CJC	17OCT05	FIGURE 3.11
REVIEW	CJC	17OCT05	

the permafrost, and will be constructed to thicknesses of at least 2 m over thaw unstable soils. In areas underlain by bedrock, or thaw stable soils, a lesser thickness of rockfill will be required.

The selection of the route considered the following:

- minimizing footprint area of disturbance
- preserving permafrost
- avoidance of any culturally sensitive areas
- minimizing impacts on lakes and streams

Two general routes were considered:

- A route to minimize the haul distance between Portage and Vault, crossing Turn Lake at its narrowest point.
- A route crossing the outflow area of Turn Lake to Drilltrail Lake and requiring the construction of a culvert crossing.

The selected route, shown in Figure 3.1, crosses Turn Lake approximately 4.5 km north of the plant site at its narrowest point where the water is less than about 6 m deep. Other than this crossing, the route avoids major drainages and requires only minor culvert crossings at other watercourses.

SECTION 4 • MINING METHODS

The prefeasibility study considered a total mining rate of 2,000 t/d from both open pit and underground mining at the Portage and Goose Island deposits. This concept was found to be marginally economic. After further exploration and inclusion of the Vault deposit in the mine plan, throughput was increased to 7,500 t/d over approximately 8.3 years or the current feasibility study. Of this amount, the Vault pit will contribute between 1,200 and 1,500 t/d.

Only open-pit mining is contemplated at this time because the reserve grades do not support economical underground development. To ensure the safety of underground mine operations, crown pillars of ore would have to be left in place, resulting in poor resource utilization. Depending on the results of additional exploration, underground mining may be an option for future extraction from deeper sections of the Goose Island and Vault deposits.

The selected size and type of mining equipment take into account the variability of the deposits and the need for flexibility to achieve a steady supply of ore from the various sources. Because of the need for trailing cable and greater difficulty in manoeuvring, electric-powered equipment was rejected in favour of diesel-powered. Diesel-driven equipment is more flexible and is especially suited to the double-bench mining that may be required for operating efficiency in some areas.

4.1 BLAST DESIGN ALTERNATIVES

Because of the remote location, Cumberland expects to use a 70/30 ANFO/emulsion mix for blasting, although this ratio could range from 70/30 to 30/70 depending on the water resistance required and energy yield required. Early conceptual design considered proportions of emulsion as low as 10%, but final design will need to ensure adequate blasting performance while considering the advantages of waste reduction and preservation of water quality (reduced contribution of nitrates to the runoff water).

An assessment of blast-induced vibration (peak particle velocity) and instantaneous pressure change was carried out during the feasibility study to estimate the effects of blasting with various charge weights and how they relate to recommended guidelines by Fisheries and Oceans Canada (DFO). Three blast design reports have been produced for the project:

- Technical Memorandum: Item #85/85a - Meadowbank Gold Project- Blasting Addendum, Golder Associates. October 2005.
- Report: Blast Design, Meadowbank Gold project, Golder Associates. 10 February 2004.
- Addendum: Blasting Report Addendum, Golder Associates. 25 May 2004
- Supporting documentation for blast design is included in Appendix C.

The assessments assumed an ANFO/emulsion ratio of 30/70 to provide an upper bound for the assessment of the impact of explosives use with respect to fisheries guidelines. The greater proportion of emulsion results in a higher energy yield. The assessments were based on design

guidelines governing the use of explosives adjacent to Canadian fisheries waters (Guidelines for the Use of Explosives in or Near Canadian Fisheries Waters; Wright and Hopky, 1998).

The initial analyses were carried out for 3 charge weights for 12 and 6 m high operating benches: 420, 250, and 86 kg. A charge weight of 12 kg was also considered for a 3 m high operating bench in ore. The recently completed feasibility study (AMEC, 2005) specified a bench height of 6 m and charge weight of 77 kg. In the following sections, charge weights of 12, 77, and 250 kg are presented. (see Table 4.1) Charge weights of 420 kg are no longer considered.

For the assessment of blast induced vibration and instantaneous pressure change, the following alternative bench configurations, blasthole sizes, and charge weights have been considered to provide a range in possible blast designs for planning purposes. The proposed 77 kg charge weight used by AMEC in the feasibility study has been incorporated:

Table 4.1: Range in Charge Weights Considered for the Meadowbank Project

Charge Weight (kg)	Blasthole Diameter (mm)	Bench Height (m)
250	165	12
77	165	6
12	165	3

4.1.1 Blast Induced Vibration

Blast induced vibrations have the potential to reduce the stability and performance of nearby earthen structures such as dikes. Where saturated conditions exist within the foundation materials and within the earthen structural fills of the de-watering dikes and the tailings dike, blast induced vibrations could result in the development of increased pore water pressures within the foundation and structural fill materials. This could lead to potential settlement of the structures and consequently impact to the water retaining capacity of the dikes.

The effects of blasting are typically assessed in terms of peak particle velocity (PPV).

4.1.2 Estimates of Peak Particle Velocity

The preliminary estimates of peak particle velocity (PPV) are based on the current understanding of the site layout, mine plan, and blast design. Changes to the current site layout, mine plan, and blast design will result in changes to the estimates of PPV. Certain site-specific factors that are required to calculate PPV have been estimated based on published values. However, site specific parameters can only be determined by site vibration monitoring of actual blasts. Consequently, the actual PPV values may differ from those presented here.

The US Bureau of mines has established that the peak particle velocity, PPV, is related to the scaled distance by the following relationship:

$$PPV = k * (R/W^{0.5})^{-b}$$

Where:

PPV	=	Peak Particle Velocity, mm/s
R	=	Distance from blast to point of concern, m
W	=	Charge weight per delay, kg
k	=	Confinement factor – specific to site
b	=	Site factor

The constants k and b are specific to the site, and can be determined by blast vibration monitoring.

For this evaluation, a value of b = 1.6 was assumed. The PPV was evaluated for a range of values of confinement, 'k', of 400, 800, and 1,500, for downhole blasting. This range in values is considered to be reasonable for the site and to provide an estimate of the sensitivity of PPV to different values of confinement.

Based on the current understanding of site conditions and experience at two other northern sites, the confinement value of 800 is expected to be the most likely representative value for average conditions at the site. The actual value for confinement can only be determined through a detailed field monitoring program.

4.1.3 Minimum Setback Distance for Canadian Fisheries Guidelines

Design guidelines governing the use of explosives adjacent to Canadian fisheries waters (Guidelines for the Use of Explosives in or Near Canadian Fisheries Waters; Wright and Hopky, 1998) indicate that no explosive is to be detonated that produces a peak particle velocity greater than 13 mm/s in a spawning bed during the period of egg incubation.

The PPVs were evaluated for the Second Portage Lake East dike, the Third Portage Peninsula east shoreline, the Bay dike, and the Goose Island east shoreline.

4.1.4 Setback Distance for Peak Particle Velocity

The minimum setback distances to achieve a PPV of 13 mm/s have been estimated for various values of confinement, 'k', and for four potential charge weights per delay. Table 4.2 summarizes the estimates of minimum setback required to achieve a PPV value of 13 mm/s.

Table 4.2: Minimum Setback Distance for 13 mm/s Peak Particle Velocity Guideline

k	Minimum Setback Distance to Achieve PPV = 13 mm/s		
	12 kg Charge Weight per Delay (3 m Bench, 76 mm Hole)	77 kg Charge Weight per Delay (6 m Bench, 165 mm Hole)	250 kg Charge Weight per delay, (12 m Bench, Decked Charge, 229 mm Hole)
400	30 m	75 m	135 m
800	46 m	115 m	208 m
1,500	67 m	171 m	308 m

The relationships presented in the above table are shown on Figure 4.1 for a confinement value, k , of 800.

With the exception of a short segment of shoreline adjacent to the Portage pit wall at the south end of the pit, the proposed charge weight of 77 kg per hole on 6 m benches will result in a PPV less than the required 13 mm/s.

For the portions of the dike or shoreline where the 13 mm/s guideline is exceeded, modified blast designs consisting of lower charge weights on lower bench heights have been shown to result in PPV that meet the guideline requirement. Alternatively, additional fill materials could be placed along the shoreline or dike upstream (lake side) face to increase the distance from the blasting area.

4.1.5 Minimum Setback Distance for Threshold Damage Levels

General guidelines for blasting nears dams indicate vibration damage thresholds on the order of 50 mm/s to be reasonable for dams having medium to dense sand or silts within the dam or foundation materials. Table 4.3 summarizes the estimates of minimum setback required to achieve a PPV value of 50 mm/s for the charge weights considered.

Table 4.3: Minimum Setback Distance for a Peak Particle Velocity of 50 mm/s for Various Blast Configurations

k	Minimum Setback Distance to Achieve PPV = 50 mm/s		
	12 kg Charge Weight per Delay (3 m Bench, 76 mm Hole)	77 kg Charge Weight per Delay (6 m Bench, 165 mm Hole)	250 kg Charge Weight per delay, (12 m Bench, Decked Charge, 229 mm Hole)
400	13 m	32 m	58 m
800	20 m	50 m	89 m
1,500	29 m	74 m	133 m


The relationships presented in the above table are shown on Figure 4.2 for a confinement value, k , of 800.

The analysis indicates that for the proposed 80 m toe setback for the dikes at the Meadowbank project, and the proposed 77 kg charge weight, a PPV of 50 mm/s will not be exceeded in the toe areas of the perimeter dikes or tailings dike. Additional blast monitoring during construction will be required to confirm the assumptions on which these results are based.

4.1.6 Instantaneous Pressure Change for Canadian Fisheries Guidelines – 100 kPa Criteria

The required setback distance for confined explosives to achieve the 100 kPa instantaneous pressure change guideline can be estimated from relationships presented in “Guidelines for the Use of Explosives in or Near Canadian Fisheries Waters” (Wright and Hopky, 1998).

REVISION DATE: 05/10/21 10:21am By: areddy CADD FILE: N:\Bur-Graphics\Projects\2005\1413\05-1413-036A\1050\CAD\1300 Project Alternatives\051413036A-1050-4.1.dwg



LEGEND

- 12 kg Charge Weight, 46m Offset
- 77 kg Charge Weight, 115m Offset
- 250 kg Charge Weight, 208m Offset
- Confinement, k = 800
- Recommended Charge Weight

NOTES

- Contour Interval 2 Metre.
- All Dimensions in Metres.
- Elevations in Metres above Sea Level.
- UTM Zone 14, NAD83.
- Area behind Dikes is De-watered during Operations.
- Reference: Feasibility Study Report, AMEC, June 2005.

REFERENCES


- AMEC Americas LTD, Drawing # A1-131395-100-C-0001 (100-C-0001.dwg), Meadowbank Feasibility Study, April 2005.
- Golder Associates: Report on Blast Design, Meadowbank Golder Project, February 2004.
- Golder Associates: Blasting Report Addendum, May 2004.

PROJECT

CUMBERLAND
RESOURCES LTD.

TITLE


PEAK PARTICLE VELOCITY
13 mm/s ISOPLETH

Golder
Associates

PROJECT No.	05-1413036A	FILE No.	051413036A-1050-4.1
DESIGN	CJC	03OCT05	SCALE AS SHOWN
CADD	WLI	03OCT05	REV. 0
CHECK	CJC	03OCT05	
REVIEW	CJC	17OCT05	

FIGURE 4.1

REVISION DATE: 05/10/21 10:29am By: areddy
CADD FILE: N:\Bur-Graphics\Projects\2005\1413\05-1413-036A\1050\CAD\1300 Project Alternatives\051413036A-1050-4.2.dwg



LEGEND

	12 kg Charge Weight, 20m Offset
	77 kg Charge Weight, 50m Offset
	250 kg Charge Weight, 89m Offset
	Recommended Charge Weight
Confinement, k = 800	

NOTES

1. Contour Interval 2 Metre.
2. All Dimensions in Metres.
3. Elevations in Metres above Sea Level.
4. UTM Zone 14, NAD83.
5. Area behind Dikes is De-watered during Operations.
6. Reference: Feasibility Study Report, AMEC, June 2005.

REFERENCES

- 1) AMEC Americas LTD, Drawing # A1-131395-100-C-0001 (100-C-0001.dwg), Meadowbank Feasibility Study, April 2005.
- 2) Golder Associates: Report on Blast Design, Meadowbank Golder Project, February 2004.
- 3) Golder Associates: Blasting Report Addendum, May 2004.

PROJECT		CUMBERLAND RESOURCES LTD.	
TITLE		PEAK PARTICLE VELOCITY 50 mm/s ISOPLETH	
PROJECT No.	05-1413-036A	FILE No.	051413036A-1050-4.2
DESIGN	CJC 03OCT05	SCALE	AS SHOWN
CADD	WLI 03OCT05	REV.	0
CHECK	CJC 03OCT05	FIGURE 4.2	
REVIEW	CJC 17OCT05		

The properties used to assess the minimum setback distance are shown in Table 4.4.

Table 4.4: Properties Used to Assess Setback Distance for Instantaneous Pressure Change

Medium	Density, g/cm ³	Compressional Wave Velocity, cm/s
Water	1	146,300 ¹
Rock (Intermediate Volcanic)	2.8	457,200 ¹

Notes: 1. Guidelines for the Use of Explosives in or Near Canadian Fisheries Waters; Wright and Hopky, 1998

Based on the above properties, range of potential charge weights, and range in confinement value, the following minimum setback distances—below which the 100 kPa overpressure guideline will not be exceeded—are estimated, as summarized in Table 4.5.

Table 4.5: Minimum Setback Distance for Instantaneous Pressure Change Guideline (<100kPa)

Charge Weight per Delay	Minimum Setback Distance, m		
kg	k=400	k=800	k=1,500
12	10 m	15 m	22 m
77	25 m	38 m	57 m
250	45 m	69 m	102 m


The results in Table 4.5 are presented on Figure 4.3 for a confinement of 800. Based on the currently proposed de-watering dike configuration, the average distance from the pit crest to the outside (lake side) dike face will be on the order of 160 m. In order for the instantaneous pressure change measured on the outside (lake side) face of the dike to exceed 100 kPa, a charge weight in excess of 1,300 kg would be required, based on the assumptions in this report. Consequently, for the range of charge weights considered in the analyses for the Meadowbank project, none will result in an instantaneous pressure change greater than 100 kPa.

4.1.7 Instantaneous Pressure Change for Canadian Fisheries Guidelines – 50 kPa Criteria

In addition to the legislated criteria, Cumberland has assessed the effect of blast induced vibration and instantaneous overpressure resulting from blasting adjacent to waters during ice cover periods. For this condition, the Department of Fisheries recommends an evaluation to consider an instantaneous pressure change of 50 kPa.

For the range of potential charge weights, and for a range in confinement value, the minimum setback distances below which the 50 kPa overpressure guideline will not be exceeded are estimated, as summarized in Table 4.6.

CADD FILE: N:\Bur-Graphics\Projects\2005\1413\05-1413-036A\1050\CAD\1300 Project Alternatives\051413036A-1050-4.3.dwg
REVISION DATE: 05/10/21 10:32am By: areddy



LEGEND

	12 kg Charge Weight, 15m Offset
	77 kg Charge Weight, 38m Offset
	250 kg Charge Weight, 69m Offset
	Recommended Charge Weight
Confinement, k = 800	

NOTES

1. Contour Interval 2 Metre.
2. All Dimensions in Metres.
3. Elevations in Metres above Sea Level.
4. UTM Zone 14, NAD83.
5. Area behind Dikes is De-watered during Operations.
6. Reference: Feasibility Study Report, AMEC, June 2005.

REFERENCES

- 1) AMEC Americas LTD, Drawing # A1-131395-100-C-0001 (100-C-0001.dwg), Meadowbank Feasibility Study, April 2005.
- 2) Golder Associates: Report on Blast Design, Meadowbank Golder Project, February 2004.
- 3) Golder Associates: Blasting Report Addendum, May 2004.

PROJECT		CUMBERLAND RESOURCES LTD.	
TITLE		INSTANTANEOUS OVERPRESSURE 100kPa ISOPLETH	
	PROJECT No.	05-1413036A	FILE No. 051413036A-1050-4.3
	DESIGN	CJC 03OCT05	SCALE AS SHOWN REV. 0
	CADD	WLI 03OCT05	
	CHECK	CJC 03OCT05	
	REVIEW	CJC 17OCT05	
FIGURE 4.3			

**Table 4.6: Minimum Setback Distance for Instantaneous Pressure Change Guideline
(50 kPa Ice-Covered Water)**

Charge Weight per Delay kg	Bench Height m	Hole Diameter (mm)	Minimum Setback Distance, m		
			k=400	k=800	k=1500
12	3 m (ore)	76	15	23	34
77	6 m (ore and waste)	165	38	59	87
250	6 m (waste)	165	69	106	157

The relationships presented in Table 4.6 are shown on Figure 4.4 for a confinement value of 800. Based on the analysis, an instantaneous pressure change of 50 kPa will not be exceeded for the proposed 77 kg charge weight per hole, and for a confinement value of 800.


4.1.8 Conclusions

The following summarizes the conclusions of the previous and current assessment:

- With the exception of a short segment of shoreline adjacent to the southeast wall of the Portage pit, the PPV of 13 mm/s will not be exceeded for the proposed 77 kg charge weight per hole. This relates to fisheries guidelines.
- The PPV of 50 mm/s will not be exceeded in the toe region of the perimeter dikes or tailings dike for the proposed 77 kg charge weight per hole. This relates to the structural stability of the dikes.
- The instantaneous pressure change along the upstream (lake side) face of the East dike, Bay Zone dike, and Goose Island dike is predicted to be less than the 100 kPa guideline for the proposed 77 kg charge weight per hole. This relates to fisheries guidelines.
- The instantaneous pressure change along the upstream (lake side) face of the dikes during periods of ice cover is predicted to be less than 50 kPa for the proposed 77 kg charge weight per hole.
- For the Vault deposit, PPV and instantaneous pressure change guidelines along the Vault dike face will not be exceeded for any of the proposed blast designs or charge weights. The Vault dike lies about 750 m from the nearest crest of the Vault pit.

The analyses have shown that peak particle velocities and instantaneous overpressure can be effectively managed through the use of lighter charge weights, decreased blasthole diameters, and decreased operating bench heights, or a combination of these mitigative measures.

REVISION DATE: 05/10/21 10:38am By: areddy CADD FILE: N:\Bur-Graphics\Projects\2005\1413\05-1413-036A\1050\CAD\1300 Project Alternatives\051413036A-1050-4.4.dwg



LEGEND


<div></div>	12 kg Charge Weight, 23m Offset
<div></div>	77 kg Charge Weight, 59m Offset
<div></div>	250 kg Charge Weight, 106m Offset
Confinement, k = 800	Recommended Charge Weight

NOTES

1. Contour Interval 2 Metre.
2. All Dimensions in Metres.
3. Elevations in Metres above Sea Level.
4. UTM Zone 14, NAD83.
5. Area behind Dikes is De-watered during Operations.
6. Reference: Feasibility Study Report, AMEC, June 2005.

REFERENCES

- 1) AMEC Americas LTD, Drawing # A1-131395-100-C-0001 (100-C-0001.dwg), Meadowbank Feasibility Study, April 2005.
- 2) Golder Associates: Report on Blast Design, Meadowbank Golder Project, February 2004.
- 3) Golder Associates: Blasting Report Addendum, May 2004.



PROJECT

CUMBERLAND
RESOURCES LTD.

TITLE

INSTANTANEOUS OVERPRESSURE
50 kPa ISOPLETH
UNDER ICE CONDITION

Golder
Associates

PROJECT No.	05-1413-036A	FILE No.	051413036A-1050-4.4
DESIGN	CJC	03OCT05	SCALE AS SHOWN
CADD	WLI	03OCT05	REV. 0
CHECK	CJC	03OCT05	
REVIEW	CJC	17OCT05	

FIGURE 4.4

4.1.9 Monitoring

As part of the mine development, a vibration monitoring program will be required to measure the response of the de-watering dikes and tailings dike to pit blasting. The data from this program would be assessed in conjunction with continuous measurements from piezometers that would be installed in the dikes, and within the dike foundation materials. From this analysis, the blasting could be adjusted to minimize the impact on the dikes. Mitigative measures to the blast design to minimize the development of blast induced vibration could include modifications to the blasthole patterns; reduction in blasthole size, and hence charge weight, in critical areas of the pit walls within a certain distance from the proposed de-watering and tailings dike; single blasthole initiation per delay; reduction in operating bench height in critical areas; or a combination of these measures.

A more comprehensive program of blast vibration modelling and test blasting may be required during operations if blast vibration levels remain high and their frequency (cycles per second) is low.

SECTION 5 • PERIMETER DIKES

The Portage, Goose Island, and Vault deposits are all partially overlain by lakes. Consequently, a series of perimeter water-retaining dikes must be constructed to permit mining operations. Three major dike structures are required:

- East (Second Portage) dike (including a causeway)
- Bay Zone dike
- Goose Island dike.

Dike configurations have evolved as the pit limits have become better defined. For the most part, dike alignments have been selected to minimize dike height by connecting shallow sections of lake floor. More recent study has shown that additional shallow diking will be required around the south end of the Portage pit as mining extends into that area.

5.1 SITE CONDITIONS

Dewatering dike locations are as shown in Figure 3.1. The majority of the perimeter dikes will be constructed in shallow water, less than 4 m to 6 m in depth though in deeper water along the east-southeast segment of the Goose Island dike, reaching up to 20 m at the lakeside toe of the dike and about 16 m at the dike centreline. Diagrams showing the centreline profiles along the proposed dikes are shown on Figure 5.1 and 5.2.


Construction in areas of deeper water will be deferred until experience with materials and techniques has been acquired in the initial years. Construction of the deeper dike sections is scheduled over several years to ensure that the types of rock material required are available from the open pits.

The rockfill and till materials that will be used for the construction of the dikes will initially come from pre-stripping operations and from the development of a starter pit at the Portage deposit. Quantity estimates indicate that approximately 380,000 m³ of rockfill and 90,000 m³ of till will be required for the dikes prior to start-up.

5.2 DESIGN ALTERNATIVES

During the pre-feasibility engineering studies evaluations of seepage cutoff alternatives was carried out. The results of the evaluation are presented in:

- Golder Associates Ltd., Letter on Review of Conceptual Dike Cross-Section. 5 December 2001.
- Golder Associates Ltd., Report on Review of Seepage Cut Off Alternatives Open Pit Dewatering Dikes, Meadowbank Gold project, Nunavut Territory. 9 March 2000.




LEGEND

- Up to 6 meters - CAT 320
- 6 to 12 meters - CAT 320BL LONG REACH
- - ? - - Possible Bedrock contact
- Lake bottom


03-GT-BZ-5 Borehole - Golder 2003
02GT-01 Borehole - Golder 2002

NOTES

- 1) Numbers in brackets are the offset from centreline of dike.
- 2) Lake bottom determined from Bathymetric surveys by Golder in 2002 and 2003.
- 3) Depths to bedrock contact based on boreholes logged and tested by Golder in 2002 and 2003.



SECOND PORTAGE DIKE




PROJECT

CUMBERLAND
RESOURCES LTD.


TITLE

SECOND PORTAGE AND BAY ZONE
DIKE - CENTRELINE PROFILE

Golder
Associates

PROJECT No.	05-1413-036A	FILE No.	051413036A-1050-5.1-5.2
DESIGN	DSH	10JUL03	SCALE AS SHOWN
CADD	WSL	29JUL03	REV. 0
CHECK	DAH	03OCT03	FIGURE 5.1
REVIEW	CJC	17OCT05	





LEGEND



Up to 6 meters - CAT 320

6 to 12 meters - CAT 320BL
LONG REACHCUSTOM-BUILT LONG REACH
BOOM >12 meters

Possible Bedrock contact

Lake bottom

03-GT-BZ-5 Borehole - Golder 2003

02GT-01 Borehole - Golder 2002

0 50 100 150 200 250
Horizontal Scale in Meters

0 2 4 6 8 10
Vertical Scale in Meters

NOTES

- 1) Numbers in brackets are the offset from centreline of dike.
- 2) Lake bottom determined from Bathymetric surveys by Golder in 2002 and 2003.
- 3) Depths to bedrock contact based on boreholes logged and tested by Golder in 2002 and 2003.

PROJECT

CUMBERLAND
RESOURCES LTD.

TITLE

GOOSE ISLAND DIKE - CENTRELINE PROFILE



PROJECT No. 05-1413036A			FILE No. 051413036A-1050-5.1-5.2		
DESIGN	DSH	10JUL03	SCALE	AS SHOWN	REV. 0
CADD	WSL	29JUL03	FIGURE 5.2		
CHECK	DAH	03OCT03			
REVIEW	CJC	17OCT05			

The following alternatives were considered during pre-feasibility studies for the seepage cutoff element within the rockfill dike cross section:

- low permeability upstream blanket
- central low permeability core
- slurry trench cut off wall
- interlocking vinyl sheet piles.

In assessing the relevant seepage reduction measures for the tailings containment dikes, frozen dike alternatives were reviewed. However, there is currently no precedent for the construction of a frozen core dike through a body of water. Due to the continual movement of water through the dike, it would not be possible to maintain a frozen core. Furthermore, past experience at the Raglan mine and Kubaka indicates that a hydraulic head of 15 m or more on the frozen core dike potentially could induce instability and may lead to a failure of the dike. Therefore, this alternative should not be considered as an alternative for the pit dewatering dikes.

Various embankment geometries suited to the depth of water and combination of materials were evaluated, and construction methods and considerations were summarized.

5.2.1 Conclusions


It was concluded that a till core combined with a soil-bentonite cutoff wall would be both effective and economical compared to a crushed rock core with slurry cutoff wall. The typical dike section comprises two rockfill embankments with a till core, a filter zone, and a soil-bentonite cutoff wall excavated to the underlying bedrock (see Figure 5.3). The dike crest will be surfaced with material suitable as haul road running course. A capping of ultramafic rock will be placed over materials that are potentially acid-generating.

The preferred option makes use of available stripped material and eliminates the need for crushing and quarrying. The recommended configuration is two parallel rockfill embankments with a core of till. A soil-bentonite cutoff wall will be excavated through the till core and underlying foundation materials to bedrock.

5.3 DESIGN BASIS & CRITERIA

The following design criteria were used:

- Dikes are to be constructed to allow open pit mining operations to be carried out year round.
- A portion of the crests of the Second Portage and Goose Island dikes will be used as mine truck haul roads between the open pit and the crusher.
- The dike sections should maximize the use of materials obtained during pre-stripping operations of the open pits, and during mining of a starter pit at the Third Portage deposit. These materials are till and run-of-mine rockfill.



NOTES

- 1) Sideslopes for rockfill as shown are 1.8H:1V.
Actual slopes will vary depending on water depth, rockfill grain size and foundation conditions.
- 2) NWT Mine Safety and Health Act(1995) states that minimum width of haul road is:
 - for one-lane traffic: 2X width of largest vehicle
 - for two-lane traffic: 3X width of largest vehicle
 - minimum height of safety berm = 0.75X diameter of tire of largest vehicle
- 3) The 80m minimum setback is based on a similar set back of Diavik and to be confirmed during detailed engineering design.

PROJECT

CUMBERLAND
RESOURCES LTD.

TITLE

TYPICAL DIKE CROSS - SECTION
SECOND PORTAGE, GOOSE ISLAND AND
BAY ZONE DIKES



PROJECT	No. 05-1413-036A	FILE	No.051413036A-1050-5.3
DESIGN	DAH	01APR03	SCALE 1:400 REV. 0
CADD	WSL	19JUN03	
CHECK	CJC	13OCT05	
REVIEW	CJC	18OCT05	

FIGURE 5.3

- A minimum setback of 80 m between the open pit side toe of the dike and the edge of the open pit has been assumed, based on similar setback distances at the Diavik project.
- Part of the southeast dike on Second Portage Lake will be constructed as a rockfill causeway to reduce haul distances between North Portage and Third Portage.
- The dike crest width should comply with NWT mine Health and Safety Act and Regulations, or equivalent regulations for Nunavut, for minimum width of haul roads. For single-lane traffic, the minimum width is twice the width of the widest haulage vehicle used on the road; for double-lane traffic the minimum width is three times the width of the widest haulage vehicle. A shoulder barrier of at least three-quarters the height of the largest tire on any vehicle using the road is required.
- The dike alignment should be selected to minimize the height of the dike.
- The dike section incorporates a soil-bentonite cutoff wall keyed into bedrock where possible.
- The dike will be a high consequence structure, based on Canadian Dam Association criteria.
- The minimum required factor of safety for static load conditions is 1.5 (Canadian Dam Association, 1999).
- The minimum required factor of safety for earthquake load conditions is 1.2 (Canadian Dam Association, 1999).
- The minimum required factor of safety for end-of-construction condition is 1.3. The end-of-construction condition for these dikes ends when personnel and equipment begin to enter the area within the dikes. (Canadian Dam Association, 1999).
- The maximum design earthquake acceleration corresponds to the 1,000-year (nominal) return period event (Canadian Dam Association, 1999).
- The minimum allowable freeboard between the crest of the dikes and lake surface will be 2 m. This is required to provide allowance for settlement, and protection for wave and ice run-up.
- The minimum freeboard between the top of the soil-bentonite cutoff wall and the lake surface must be 1 m.


5.3.1 Seismicity

Based on the seismic hazard assessment provided by Pacific Geoscience Centre for this site, the proposed development is located within seismic Zone 0 of the National Building Code, which is negligible seismic risk (see Table 5.1 and Figure 5.4).

Table 5.1: Peak Horizontal Ground Accelerations for Meadowbank Site

Return Period of Seismic Event (years)	Peak Horizontal Ground Acceleration (g)
100	0.018
200	0.025
475	0.034
975	0.044

Source: Seismic Risk Calculation for Meadowbank project Site, Geological Survey of Canada, Natural Resources Canada, Sidney, B.C., July, 2003 – See Appendix VI.



LEGEND

- Meadowbank Project
- Town/Village
- Peak Horizontal Ground Acceleration (g), for 10% probability of exceedance in 50 Year Event
 - 0 - 0.039
 - 0.04 - 0.079
 - 0.08 - 0.109
- Provincial Border
- Water
- Primary Highway
- Railroad

REFERENCE

Base digital data obtained from ESRI Inc.,
DATUM: WGS84 PROJECTION: Geographic

200 0 200 Kilometers
Scale - 1:10,000,000

PROJECT		CUMBERLAND RESOURCES LTD.	
TITLE		SEISMIC ZONING MAP MEADOWBANK PROJECT	
		PROJECT No. 05-1413-036A	SCALE AS SHOWN
		DESIGN DAH 19 Dec. 2003	REV. 0
		GIS CDB 19 Dec. 2003	
		CHECK DAH 10 Feb. 2004	
		REVIEW	
		FIGURE 5.4	

5.4 SLOPE STABILITY

Once the dike cross-section had been selected, a series of slope stability and seepage analyses were carried out for the three main perimeter dewatering dikes. The results of the stability and seepage analyses are reported in detail in:

- Golder Associates Ltd., Report on Design of Dikes with Soil-Bentonite Cutoff Wall, Meadowbank Gold Project. 23 October 2003.

Slope stability analyses show that the dikes will be stable under static and earthquake load conditions. Seepage modelling indicates that the total seepage through all of the dikes will be in the range of approximately 2.4 to 48.3 L/s. This value varies depending on potential cracking in the soil-bentonite cutoff wall and/or a potential gap in the cutoff wall at the bedrock contact.


Slope stability analyses were carried out for three sections along the Goose Island dike. Section locations are shown on Figure 5.5; the sections are shown on Figures 5.6 and 5.7. Section A is located on a relatively flat foundation, section B is the deepest section with the foundation sloping away from the pit, and section C is the deepest section where the foundation is sloping toward the pit. Failure of section A could potentially occur on the inside of the dike towards the open pit. Section B has the deepest water and steepest lake bottom slope along the dike alignment. The lake bottom slopes away from the pit at section B, and failure of the dike at this location could potentially occur on the outside of the dike towards the lake. Section C is similar to section A.

The slope stability scenarios were modelled for each of sections A, B, and C only, as these represent the most critical dike sections. The dikes are high consequence structures, as they will be retaining water while personnel and equipment are working in the pits. The design life of the dikes is less than 20 years.


5.4.1 Results of Analyses for End-of-Construction Conditions

Slope stability analyses were carried out to evaluate the short-term, end-of-construction scenario. The soil foundation material was assumed to be undrained. Sections A, B, and C were analyzed to determine the values of the undrained shear strength (c_u), which would yield factors of safety of 1.0 and 1.3.


The analyses show that the minimum required undrained strength of the foundation must be in the range of 20 to 30 kPa, to achieve factors of safety of 1.0 and 1.3, respectively. The foundation soils that have been recovered during the geotechnical investigations carried out along the proposed dike alignments range from a silty till material containing significant proportions of gravel and cobbles to silty sand and gravel. Undrained strengths of this material are expected to be at least equal to, if not greater than, 20 to 30 kPa. Undrained shear strength testing will be required during the detailed engineering design stage for the dikes.



- NOTES**
- 1) Contour information on land supplied by Cumberland Resources Ltd.
 - 2) Contours below lake surface are based on bathymetric surveys by Golder Associates Ltd., 2002 and 2003.
 - 3) Lake contours are based on surveyed lake surface elevations:
2nd Portage Lake = 133.1 m
3rd Portage Lake = 134.1 m


PROJECT		CUMBERLAND RESOURCES LTD.	
TITLE		LOCATION OF STABILITY CROSS SECTIONS	
	PROJECT No.	05-1413-036A	FILE No.051413036A-1050-5.5
	DESIGN	DAH	01APR03
	CADD	WSL	10JUL03
	CHECK	CJC	13OCT05
REVIEW	CJC	17OCT05	SCALE: AS SHOWN
			FIGURE 5.5

REVISION DATE: 05/10/20 9:47am By: sreddy CADD FILE: N:\Bur-Graphics\Projects\2005\1413\05-1413-036A\1050\CAD\1300 Project Alternatives\051413036A-1050-5.6-5.7.dwg



NOTES

1. Sections are shown for 1.8H:1.0V sideslopes of rockfill. Actual slopes will vary, depending on water depth, rockfill grain size, and foundation conditions.
2. Overburden depth has been estimated based on results from the 2003 Golder geotechnical drilling investigations. Actual overburden depths will vary.
3. All dimensions are in metres unless noted otherwise.




PROJECT		CUMBERLAND RESOURCES LTD.			
TITLE		GOOSE ISLAND DIKE SECTIONS			
		PROJECT No.	05-1413-036A	FILE No.	051413036A-1050-5.6-5.7
DESIGN	CJC	13JUN03	SCALE	AS SHOWN	REV. 0
CADD	NV/WSL	19JUN03			
CHECK	CJC	13OCT05			
REVIEW	CJC	17OCT05			



FIGURE 5.6

REVISION DATE: 05/10/20 9:47am By: areddy CADD FILE: N:\Bur-Graphics\Projects\2005\1413\05-1413-036A\1050\5.6-5.7.dwg PROJECT Alternatives\051413036A-1050-5.6-5.7.dwg



NOTES

- 1) Sections are shown for 1.8H:1.0V sideslopes of rockfill. Actual slopes will vary, depending on water depth, rockfill grain size, and foundation conditions.
- 2) Overburden depth has been estimated based on results from the 2003 Golder geotechnical drilling investigations. Actual overburden depths will vary.
- 3) All dimensions are in metres unless noted otherwise.

PROJECT				
CUMBERLAND RESOURCES LTD.				
TITLE				
SECOND PORTAGE EAST DIKE AND CAUSEWAY SECTIONS				
PROJECT No.		05-1413-036A	FILE No.	
DESIGN		DAH 13JUN03	SCALE	
CADD		NV/WSL 19JUN03	AS SHOWN	
CHECK		CJC 13OCT05	REV.	
REVIEW		CJC 17OCT05	0	



FIGURE 5.7

5.4.2 Results of Analyses for Long-Term Static & Pseudostatic Conditions

Slope stability analyses were done to evaluate the stability of the dikes under long-term, steady-state seepage conditions. The results of the long-term analyses of the critical failure modes are summarized in Table 5.2. The results of all stability analyses are presented in Appendix D.

Table 5.2: Summary of Long-Term Slope Stability Analyses

Failure Mode	Minimum Calculated Factors of Safety		
	Section A	Section B	Section C
Failure through Cutoff Wall Static Conditions (Minimum = 1.5)	4.1	3.5	3.9
Failure through Cutoff Wall pseudostatic Conditions (Minimum = 1.2)	3.5	3.0	3.3
Failure through Rockfill only Static Conditions (Minimum = 1.5)	2.7	1.9	3.2
Failure through Rockfill only Pseudostatic Conditions (Minimum = 1.2)	2.5	1.7	2.4
Calculated Yield Acceleration (g)			
Failure through Cutoff Wall	0.41	0.27	0.37
Failure through Rockfill only	0.36	0.16	0.36

Notes: 1. FOS = 1.5 is minimum specified for long-term. 2. FOS = 1.2 is minimum specified for pseudo-static.

As seen in the table, the minimum calculated factor of safety for static conditions is 1.9, and the minimum calculated factor of safety for pseudo-static conditions is 1.5, both of which occur at Section B. These values exceed the minimum values indicated by the Dam Safety Guidelines (Canadian Dam Association, January 1999).

Based on the analyses, the dikes will be stable in the long-term for static and pseudostatic loading conditions.

5.5 SEEPAGE

Seepage analyses were carried out for sections A and B. The material parameters used in the analyses are presented in Table 5.3.

The cutoff wall was modelled for the following scenarios:

1. A cutoff wall with no gaps at the bedrock contact, and no cracking within the wall.
2. A gap through the soil-bentonite cutoff wall at the bedrock interface.
3. A crack through the soil-bentonite cutoff wall, in the overburden till material
4. A crack through the soil-bentonite cutoff wall, in the till core material.
5. Combinations of 2, 3, and 4.

Fluxes were computed through the soil-bentonite cutoff wall for each scenario. Table 5.4 shows the predicted fluxes for each of the scenarios modelled.

Table 5.3: Summary of Material Properties used in Seepage Analyses

Material	Hydraulic Conductivity (m/s)	Basis for Properties
Till Core	1×10^{-5}	Falling head tests from Dec 2002 geotechnical testing and; Experience with materials with similar genesis and grain size distribution
Rockfill	1×10^{-2}	Experience with similar materials
Overburden	1×10^{-5}	Falling head tests from Dec 2002 geotechnical testing and; Experience with materials with similar genesis and grain size distribution
Soil-Bentonite	1×10^{-9}	Published values
Backfill	1×10^{-8}	
Bedrock	4.7×10^{-7} (Section A) 2.2×10^{-7} (Section B)	BH 03GT-GI-6 packer tests BH 03GT-GI-3 packer tests previous geotechnical field investigations

Table 5.4: Seepage Fluxes through the Soil-Bentonite Cutoff Wall

Scenario Modelled	Predicted Flux (L/s/m of length of dike)	
	Section A	Section B
No gap at bedrock contact; no crack in soil-bentonite wall	5.8×10^{-4}	5.6×10^{-4}
No gap at bedrock contact; crack in soil-bentonite wall within overburden till	1.5×10^{-2}	7.5×10^{-3}
No gap at bedrock contact; crack in soil-bentonite wall within till core	5.9×10^{-4}	5.6×10^{-4}
0.5 m gap at bedrock contact; no crack in soil-bentonite wall	1.9×10^{-3}	6.7×10^{-3}
0.5 m gap at bedrock contact; crack in soil-bentonite wall within overburden till	1.5×10^{-2}	1.2×10^{-2}
0.5 m gap at bedrock contact; crack in soil-bentonite wall within till core	1.9×10^{-3}	5.9×10^{-3}

The predicted fluxes result in the following conclusions:

- Cracks through the cutoff wall in the section through the overburden would result in the largest increase in seepage. The increase is in the range of one to two orders of magnitude more than a wall with no cracks or defects in the overburden section. Cracks within the till core section have a negligible effect on seepage.
- A gap in the soil-bentonite cutoff wall at the bedrock contact results in an increase in seepage of approximately one order of magnitude.

Preliminary estimates of the range of seepage flows to be expected through the cutoff wall during operations are summarized on Table 5.5.

Table 5.5: Seepage Flows through Dikes

Dike	Predicted Flux (l/s/m of length of dike)		Length of Dike (m)	Predicted Flow through Dike and Overburden(see Note 1) (l/s)
	Section A	Section B		
No gap at bedrock contact, no crack within overburden				
Second Portage	6 x 10 ⁻⁴	n/a	950	0.6
Bay Zone	6 x 10 ⁻⁴	n/a	720	0.6
Goose Island	6 x 10 ⁻⁴	6 x 10 ⁻⁴	1724	1.2
0.5 m gap at bedrock contact, no crack within overburden (along complete length of dike)				
Second Portage	2 x 10 ⁻³	n/a	950	1.9
Bay Zone	2 x 10 ⁻³	n/a	720	1.4
Goose Island	2 x 10 ⁻³	2 x 10 ⁻³	1724	3.4
Crack in cutoff wall within overburden (along complete length of dike)				
Second Portage	1.5 x 10 ⁻²	n/a	950	14.2
Bay Zone	1.5 x 10 ⁻²	n/a	720	10.8
Goose Island	1.5 x 10 ⁻²	1 x 10 ⁻²	1724	23.3

Notes: 1. To calculate total flow at Second Portage and Bay Zone dikes, the seepage flux at Section A flux was applied over the total length of the dikes. To calculate total flow at the Goose Island dike, the Section A and B seepage fluxes were each applied over 70% and 30% of the dike length, respectively.

It is anticipated that the majority of the seepage flows would be captured in toe drains excavated near the downstream toe of the dikes and pumped, most likely to the water treatment plant. The seepage captured at the drains will likely be pumped to the water treatment plant. The remaining flow would report to the open pit dewatering systems.

SECTION 6 • STABILITY ASSESSMENT OF THE PORTAGE ROCK STORAGE FACILITY

An assessment of the physical and thermal stability of the Portage rock storage facility was carried out by BGC Engineering Inc., as detailed in the following report:

- BGC Engineering Inc., Preliminary Geothermal and Slope Stability Modelling of Rock Storage Facilities. 31 March 2004.

The assessment was based on the initial design of the Portage rock storage facility having a larger footprint area than the current design, and on the previous mine production schedule in which the mine was operated over a period of 10 years. The results of the assessment are summarized in the following sections.

Two sites to store the country rock have been selected based on an evaluation process that considered environmental impacts, costs, and operational constraints. Materials excavated from the Goose Island and Portage pits will be stored at the Portage rock storage facility (RSF), while materials excavated from the Vault pit will be stored at the Vault RSF (see Figure 3.1).

The foundation conditions at the Vault RSF primarily comprise thin deposits of ice-poor glacial till and weathered bedrock, and are expected to pose limited engineering challenges. At some locations, the foundation conditions at the Portage RSF comprise weaker ice-rich sediments and organic soils. Consequently, the Portage RSF was selected for further evaluation of slope stability considerations. This included an evaluation of the predicted ground thermal regime and its potential impacts on slope stability.

The construction, operation, and closure of the rock storage facilities will comply with NWT mine Health and Safety Regulations and Canadian Dam Association Dam Safety Guidelines, and design criteria such as the factors of safety required for construction and long-term conditions are similar to those developed for the tailings facilities.

6.1 CONSTRUCTION ALTERNATIVES

If construction of the RSF is initiated during the summer, the first lift of rockfill will be placed on an unfrozen or partially thawed foundation. Based on air photo interpretation, it appears that a portion of the RSF is underlain by ice-rich soil. These materials are expected to display relatively low shear strengths and thermal conductivities. Geothermal modelling, however, suggests that the foundation materials should freeze back within about 270 days of placement of the first lift of rockfill. Furthermore, slope stability analyses show that the bottom lift of rockfill should be stable despite the potential for thawed foundation materials, provided the lift height is limited to about 5 m and overall slope angles of about 3:1 (18.4°) are utilized.

If the first lift of rockfill is placed during the winter, geothermal analyses suggest this will help to “lock in” the cold foundation temperatures, and the foundation should remain frozen in perpetuity.

Geothermal analyses were undertaken to evaluate long-term foundation temperatures beneath as much as 70 m of rockfill placed in the RSF. A climate-warming trend of 5.5°C over the next 100 years was considered. The modelling suggests that foundation temperatures will remain below -4°C for at least the next 200 years in spite of this potential for climate warming.

If the RSF foundations remain frozen, long-term stability will, in part, be governed by creep deformation. Using estimates of creep strength developed for the Diavik project based on laboratory testing and case history review, slope stability modelling indicates creep strain rates less than 0.01 are attainable. If, for example, approximately 2.5 m of creep-susceptible materials are encountered in the foundation of the RSF, this implies deformations in the RSF should be less than 2.5 cm per year.

6.1.1 CONSTRUCTION GEOTHERMAL ANALYSIS

The geothermal modelling to evaluate conditions during construction of the RSF had two main objectives:

- to evaluate the potential for thawing the foundation during construction or operation of the facility
- to evaluate the impact of initiating construction in the summer versus the winter on predicted foundation temperatures.

6.1.1.1 Geothermal Model

The mine waste management plan calls for the filling of Second Portage Arm with tailings during mine operation. This will eliminate the nearby warming effect of the lake, resulting in cooler foundation temperatures near the toe of the facility starting about mid-way through the mine life.

Prior to placement of the first lift of rockfill for the summer placement alternative, the ground surface temperatures are about +6°C, and -8°C at approximately 5 m depth. The ground thermal regime prior to the winter placement scenario indicates a ground surface temperature of about -18°C and a temperature of -8°C at about 2.5 m depth.

As the excavated country rock has a low thermal conductivity and will be placed at temperatures below freezing, placement of the first lift is expected to present the greatest opportunity for thawing of the foundation. Once foundation materials freeze, the active layer is not expected to penetrate the full thickness of any of the additional lifts of rockfill. Therefore, construction of the facility was modelled in two steps: placement of a 5 m lift in Year 1; and placement of all remaining lifts in Year 3. This is expected to be highly conservative, as opportunities for cooling of the rockfill between placement of the intermediate lifts was not accounted for in the modelling.

Predicted temperatures in the foundation materials and the rockfill were monitored for eleven years, and the results are discussed below.

6.1.1.2 Summer Placement Results

The ground thermal regime was modelled for a period of two years following placement of lift no. 1. The ground temperatures in the summer of Year 2 (approximately 12 months after placement of the

first lift) are illustrated in Figure 6.1. By the summer of Year 2, the foundation materials beneath the rockfill are frozen, but at a temperature greater than -2°C . As a result of placing the lift of rockfill at -3°C , the -8°C isotherm below the base of the storage facility shifted downwards from a depth of 5 m to about a depth of 18 m below the original ground surface.

Figure 6.2 shows the ground thermal regime in the summer of Year 11. The foundation materials beneath the rockfill have cooled to between -4°C and -6°C . The majority of the rockfill is between -3°C and -6°C . Except at the toe of the facility, where temperatures remain below -6°C , the bedrock beneath the rockfill has warmed to between -4°C and -6°C .

6.1.1.3 Winter Placement Results

The ground temperatures in the summer of Year 2 are illustrated in Figure 6.3, and temperatures in Year 11 are illustrated in Figure 6.4. These figures illustrate the potential benefit of “locking in” the cold foundation temperatures by placement of the first lift during the winter. The predicted temperatures in the foundation are between -6°C and -9°C , which will result in a higher creep strength.

Temperatures in the rockfill are similar to those for the summer placement scenario with the majority of the rockfill residing between -3°C and -6°C .

6.1.1.4 Short-term Foundation Temperatures


A more detailed assessment of predicted foundation temperatures for each placement scenario was completed for the first two years following placement of the first lift of rockfill. The results indicate that, for summer placement of the rockfill, the soil 0.5 m below the original ground surface remains thawed for a period of about 270 days, then drops gradually towards -4°C . For winter placement, the soil 0.5 m below the original ground surface rapidly warms to about -8°C in the first 30 days, then gradually warms towards -7°C .

The modelling results suggest that frozen soil creep strength for temperatures less than -4°C can be relied upon from the time of rockfill placement in the winter placement scenario, but that only partially thawed strengths should be relied upon during the early stages of construction if the first lift of rockfill is placed during the summer.

6.1.2 LONG-TERM GEOTHERMAL ANALYSIS

Geothermal analyses were undertaken to evaluate long-term trends in the temperature of the RSF, both under current climatic conditions and under an assumed conservative estimate of climate warming. A time period of 100 years following mine closure was modelled for both the case of no climate warming, while a period of 200 years was modelled for the climate warming scenario. The initial temperature profile was based on the summer placement model data recorded in Year 11 (Figure 6.2).

Description: Meadowbank Rock Storage
Comments: Lift 1, Summer Placement
File Name: RSF lift 1a summer.tez
Last Saved Date: 26/03/2004
Last Saved Time: 2:03:35 PM
Analysis Type: Transient
Analysis View: 2-D



Reference: BGC Engineering Inc., Meadowbank Project, Geothermal and Stability Modelling,
Project No. 0374-001-08, Figure 7.




PROJECT	CUMBERLAND RESOURCES LTD.			
TITLE	PORTAGE ROCK STORAGE FACILITY GROUND THERMAL REGIME YEAR 2 (SUMMER), SUMMER PLACEMENT			
	PROJECT No.	05-1413-036A	FILE No.	THERMAL
	DESIGN	CJC	11OCT05	SCALE NTS
	CADD	SS	11OCT05	REV.
	CHECK	CJC	11OCT05	
	REVIEW	CJC	17OCT05	

FIGURE 6.1


DRAWING DATE: 11-Oct-05 COREL FILE: N:\Bur-Graphics\Projects\2005\141305-1413-036A\1050\Corel\1300 Project Alternatives\Thermal.cdr



Reference: BGC Engineering Inc., Meadowbank Project, Geothermal and Stability Modelling,
Project No. 0374-001-08, Figure 8.

PROJECT		CUMBERLAND RESOURCES LTD.	
TITLE		PORTAGE ROCK STORAGE FACILITY GROUND THERMAL REGIME YEAR 11 (SUMMER), SUMMER PLACEMENT	
	PROJECT No.	05-1413-036A	FILE No. THERMAL
	DESIGN	CJC 11OCT05	SCALE NTS
	CADD	SS 11OCT05	REV.
	CHECK	CJC 11OCT05	
REVIEW		CJC 17OCT05	
FIGURE 6.2			


Description: Meadowbank Rock Storage
Comments: Lift 1, Winter Placement
File Name: RSF lift 1a winter.tez
Last Saved Date: 17/03/2004
Last Saved Time: 5:07:52 PM
Analysis Type: Transient
Analysis View: 2-D



Reference: BGC Engineering Inc., Meadowbank Project, Geothermal and Stability Modelling,
Project No. 0374-001-08, Figure 9.

PROJECT		CUMBERLAND RESOURCES LTD.	
TITLE		PORTAGE ROCK STORAGE FACILITY GROUND THERMAL REGIME YEAR 2 (SUMMER), WINTER PLACEMENT	
	PROJECT No.	05-1413-036A	FILE No. THERMAL
	DESIGN	CJC 11OCT05	SCALE NTS REV.
	CADD	SS 11OCT05	
	CHECK	CJC 11OCT05	
	REVIEW	CJC 17OCT05	FIGURE 6.3

Description: Meadowbank Rock Storage
Comments: Lift 2, Winter Placement
File Name: RSF lift 2a winter.tez
Last Saved Date: 21/03/2004
Last Saved Time: 10:31:18 AM
Analysis Type: Transient
Analysis View: 2-D



Reference: BGC Engineering Inc., Meadowbank Project, Geothermal and Stability Modelling,
Project No. 0374-001-08, Figure 10.

PROJECT		CUMBERLAND RESOURCES LTD.	
TITLE		PORTAGE ROCK STORAGE FACILITY GROUND THERMAL REGIME YEAR 11 (SUMMER), WINTER PLACEMENT	
	PROJECT No.	05-1413-036A	FILE No. THERMAL
	DESIGN	CJC 11OCT05	SCALE NTS
	CADD	SS 11OCT05	REV.
	CHECK	CJC 11OCT05	
		REVIEW	CJC 17OCT05
FIGURE 6.4			

6.1.2.1 Climate Warming Assumptions

Climate warming assumptions conform with those presented by Golder (2003c) and included a 5.5°C increase in temperature over a period of 100 years. Each year, 0.055°C was added the mean monthly ground surface temperatures assumed for GST No. 3. The resulting mean annual ground surface temperature at the end of 100 years (Year 111) was approximately -3°C. The model was then run for an additional 100 years holding the Year 111 ground surface temperature function constant.

6.1.2.2 Results

In the case of no climate warming, the foundation temperatures remain between -6°C and -8°C, with slightly cooler temperatures predicted beneath the toe of the facility (Figure 6.5). The majority of the rockfill appears to have cooled towards a temperature of -7°C. Air convection cooling may, however, cause the rockfill to attain lower temperatures.

In the case of climate warming, the foundation temperatures are slightly warming at Year 111, but remain between -4°C and -7°C (Figure 6.6). The majority of the rockfill appears to be at temperatures of between -4°C and -6°C.

Maintaining the warmest set of ground temperature values for an additional 100 years, the foundation temperatures at Year 211 are between -3°C and -5°C, with cooler temperatures preserved beneath the highest portion of the RSF (Figure 6.7). While a warming trend for foundation temperatures is observed, the rate of warming is extremely slow because of the low thermal conductivity of the rockfill.


6.2 STABILITY ANALYSIS

Slope stability analyses were also undertaken to account for seismic loading conditions and the unlikely possibility of a thawing foundation beneath the completed RSF. The results indicate the long-term factors of safety against slope failure under static and seismic loading conditions are well in excess of those typically adopted for earth dams and other civil engineering structures.

The design assumptions used in the preliminary geothermal and slope stability modelling are considered to be conservative, but require verification through additional geotechnical investigation and laboratory testing. The results of this work should be used to optimize the design of the Portage RSF, likely resulting in a net cost savings to Cumberland during mine operation and closure. At the same time, verification of foundation conditions and design of the Vault RSF slopes should be undertaken, as should the design of temporary and/or permanent facilities to store overburden materials.

A process referred to as air convection cooling has been observed in highway embankments and waste rock piles constructed of coarse, poorly graded rockfill. The result is embankment and foundation temperatures that are considerably cooler than predicted by conventional geothermal modelling.


Description: Meadowbank Rock Storage
Comments: Summer Year 111, No Warming
File Name: RSF year 111 no warming.tez
Last Saved Date: 21/03/2004
Last Saved Time: 6:27:39 PM
Analysis Type: Transient
Analysis View: 2-D




Reference: BGC Engineering Inc., Meadowbank Project, Geothermal and Stability Modelling,
Project No. 0374-001-08, Figure 12.


PROJECT		CUMBERLAND RESOURCES LTD.	
TITLE		PORTAGE ROCK STORAGE FACILITY GROUND THERMAL REGIME YEAR 111 (SUMMER), SUMMER PLACEMENT	
	PROJECT No.	05-1413-036A	FILE No. THERMAL
	DESIGN	CJC 11OCT05	SCALE NTS
	CADD	SS 11OCT05	REV.
	CHECK	CJC 11OCT05	
		REVIEW	CJC 17OCT05
FIGURE 6.5			

Description: Meadowbank Rock Storage
Comments: Summer Year 111, w/ 5.5 deg. Warming
File Name: RSF year 111 warming.tez
Last Saved Date: 26/03/2004
Last Saved Time: 4:55:15 PM
Analysis Type: Transient
Analysis View: 2-D




Reference: BGC Engineering Inc., Meadowbank Project, Geothermal and Stability Modelling,
Project No. 0374-001-08, Figure 13.

PROJECT		CUMBERLAND RESOURCES LTD.			
TITLE		PORTAGE ROCK STORAGE FACILITY GROUND THERMAL REGIME YEAR 111 (SUMMER), WITH CLIMATE WARMING			
	PROJECT No.	05-1413-036A	FILE No.	THERMAL	
	DESIGN	CJC	11OCT05	SCALE	NTS
	CADD	SS	11OCT05	REV.	
	CHECK	CJC	11OCT05	FIGURE 6.6	
REVIEW	CJC	17OCT05			



Reference: BGC Engineering Inc., Meadowbank Project, Geothermal and Stability Modelling, Project No. 0374-001-08, Figure 14.

PROJECT		CUMBERLAND RESOURCES LTD.	
TITLE PORTAGE ROCK STORAGE FACILITY GROUND THERMAL REGIME YEAR 211 (SUMMER), AFTER CLIMATE WARMING			
	PROJECT No. 05-1413-036A		FILE No. THERMAL
	DESIGN	CJC	11OCT05
	CADD	SS	11OCT05
	CHECK	CJC	11OCT05
	REVIEW	CJC	17OCT05
		SCALE	NTS
		REV.	
		FIGURE 6.7	

6.2.1 CONSTRUCTION SLOPE STABILITY

6.2.1.1 Objectives

Slope stability analyses were undertaken to assess stability of the Portage RSF during its construction. The objective was to ensure that the factor of safety against failure of the overall slopes of the facility will not fall below a value of 1.3 during construction. A factor of safety of 1.3 for construction conditions is generally accepted for dams and mine tailings facilities.

6.2.1.2 Section for Analysis

The section for analysis was essentially that used for the geothermal modelling, although the thickness of the ice-rich sediments unit was increased from 1 m to 2.5 m, the stronger glacial till unit was removed, and instead of being level, a -1.1% gradient (4 m elevation in 350 m) was modelled along the base of the RSF. These modifications helped to ensure that the slip surfaces were properly constrained to the weaker ice-rich foundation materials, and that the effects of an outward dipping foundation were accurately accounted for. The water table was assumed to be located at the natural ground surface. Rockfill slope angles were modelled at 3:1 (18.4°) slopes.

Stability of the facility was modelled for two different stages of construction: following placement of the first lift, and following placement of all remaining lifts.

The limit-equilibrium software SLOPE/W, produced by Geo-Slope International Ltd., was used for the analyses. A search for slip surfaces passing through the crest of the RSF that gave the lowest factor of safety was conducted. Strength parameters were varied to account for partially thawed and fully thawed foundation conditions. Results of the analyses are reported below.

6.2.1.3 Partially Thawed Foundation

In the case that the first lift of rockfill will be placed during the summer, the ice-rich sediments may be thawed or partially frozen. If this occurs, the material is expected to consolidate rapidly under the load of the coarse rockfill, resulting in a gain in strength.

Using a friction angle of 20° for partially thawed ice-rich sediments, a factor of safety against slope failure of 1.3 is predicted for a five metre high lift of rockfill. A check on the required undrained shear strength of the ice-rich sediments was also carried out. Provided a shear strength in excess of 13 kPa can be relied upon, the factor of safety against undrained loading should also exceed 1.3. Higher undrained shear strengths will be required to maintain the stability of additional lifts. These should easily be achieved as foundation materials freeze.

Geothermal modelling showed that even if the first lift of rockfill was placed during the summer, the foundation materials would freeze within about 270 days and are expected to remain frozen in perpetuity. In the case of winter placement of the first lift, the foundation is never expected to experience thawed conditions. Regardless, a check on the stability of the completed RSF with a gradually thawing foundation was conducted. Using a friction angle of 20° for the ice-rich sediments, a factor of safety against slope failure of 1.8 is predicted. Since any thawing of the foundation underneath the completed RSF would occur very slowly, the potential for thaw-generated excess pore pressures was considered low and not analyzed.

6.2.1.4 Fully Thawed Foundation

If the foundation materials were fully thawed, they would consolidate and gain strength. Using a friction angle of 28° for the fully thawed and consolidated ice-rich sediments, factors of safety against slope failure of 1.7 for lift no. 1 and 2.1 for the full height of the RSF were determined.

6.2.2 LONG-TERM SLOPE STABILITY**6.2.2.1 Objectives**

The objectives of slope stability modelling for long-term conditions was to ensure that the factor of safety exceeds 1.5 under static conditions, and that under seismic loading the factor of safety is greater than 1.2. Additionally, a check was conducted to ensure that the stress condition in the foundation of the facility will not lead to creep rupture.

6.2.2.2 Static Conditions

As demonstrated previously, the factors of safety under static conditions exceed 1.5 under the full height of the proposed RSF, even when the unlikely scenario of thawing foundations is considered. Thus, the requirements for long-term stability under static loading conditions are satisfied.

6.2.2.3 Seismicity & Psuedo-Static Conditions

Golder (2004) reports that the peak ground acceleration (PGA) for the site has been estimated at 0.044 g for the 1:975-year event. This has been adopted for design in accordance with Canadian Dam Association safety guidelines. Common practice is to apply one-half of the expected PGA when carrying out a pseudo-static slope stability analysis. Consequently, the stability of the rock storage facility under a horizontal acceleration of 0.022 g was evaluated.

If the foundation is assumed to be partially thawed, the factor of safety under seismic loading is approximately 1.7, while if the foundation soils are fully thawed and consolidated, the factor of safety is approximately 2.0. These are well in excess of a factor of safety of 1.2 as recommended by the Canadian Dam Association and commonly adopted in engineering practice.

6.2.2.4 Frozen Foundation

If the ice-rich sediments in the foundation of the RSF remain frozen, the long-term stability of the facility may be governed by creep deformation. Using the creep strength assumptions for ice-rich materials at Diavik, a factor of safety of 1.6 was determined. The results imply that the specified creep rate (0.01) will not be exceeded, and the potential for creep rupture is low.

6.2.2.5 Air Convection Cooling

In cold climates, air convection can provide a cooling effect for embankments constructed of highly porous, poorly graded material such as gravel or crushed rock with a low fines and moisture content. Such a material allows convection of pore air to occur within the embankment. Saboundjian and Goering (2003) provide a description of the process.

During the winter, the surface of the embankment experiences very cold temperatures, while the lower portions of the embankment and its foundation are relatively warm. The result is an unstable air density gradient within the embankment, which can lead to circulation of the air and enhanced wintertime heat transfer.

In the summer, the surface of the embankment experiences relatively warm temperatures compared to the lower portions of the embankment and its foundation. In this case, the embankment air density gradients are stable and circulation will not occur. Thus, the embankment acts as a one-way heat transfer device that effectively removes heat from the embankment and foundation soil during the winter without re-injecting heat during the summer. This passive cooling effect can accelerate embankment freezing and prevent thaw of underlying permafrost.

Additional cooling may occur as a result of exposure to wind blowing air through the embankment, provided the mean annual air temperature is cooler than the average embankment temperature.

6.2.2.6 Observations from Test Highway Embankments

Saboundjian and Goering (2003) discuss the thermal performance of a highway test embankment constructed in Alaska.

The embankment was constructed to a thickness of about 3 m over ice-rich permafrost using granular material with approximately the following gradation:

Sieve Opening (mm)	% Passing
152.....	100
102.....	90
76.....	23
25.....	0.3

Temperatures were monitored throughout the embankment and embankment foundation between 1997 and 2001. The monitoring data confirmed that the process of air circulation during wintertime was occurring within the embankment, resulting in a depression of the mean annual temperature at the base of the embankment. The mean annual temperature at the base of the embankment was about 4°C cooler than at the surface. No such cooling effect was observed in an adjacent Control section that was constructed using minus 2" fill materials.

6.2.2.7 Observations from Ekati Mine

Anecdotal information suggests that rock piles placed at the Ekati mine are experiencing air convection cooling, resulting in temperatures at the base of the piles that are cooler than the mean annual air temperature. Interviews with Ekati personnel to learn more about the nature of the waste rock, rock placement schedule and techniques, and impacts of air convection cooling on ground thermal regime, should be conducted as part of final design of the Meadowbank rock storage facilities.

6.2.2.8 *Implications for Meadowbank Rock Storage Facilities*

The waste rock generated from the Meadowbank project may have a gradation similar to the materials used to construct the test embankment in Alaska and the waste rock pile at the Ekati mine, where air convection cooling has been observed. Consequently, air convection cooling could also occur within the Meadowbank rock storage facilities, resulting in cooler temperatures than predicted by the geothermal modelling completed to date. The results from Alaska suggest foundation temperatures beneath the Portage RSF could be as much as 4°C cooler than the mean annual air temperature. Faster rates of cooling and cooler temperatures within the RSF and its foundation will likely improve slope stability factors of safety over the values predicted from the slope stability modelling. Cooler temperatures should also reduce seepage quantities from the toe of the RSF, and possibly the rates of geochemical processes such as ARD and metals leaching.

SECTION 7 • TAILINGS DIKE DESIGN ALTERNATIVES

A site selection study was conducted to identify the preferred storage location and deposition method for tailings at the Meadowbank site. Details of the selection process have been described previously, and are presented in:

- Golder Associates Ltd., Report on Evaluation of Tailings Alternatives, Meadowbank Project, Nunavut. October, 2005.
- Golder Associates Ltd., Report on Evaluation of Waste Rock Management Alternatives, Meadowbank Project, Nunavut. October, 2005.
- Golder Associates Ltd., Report on Alternative Waste and Water Management Plan, Meadowbank Gold Project, Nunavut. 7 March 2005.
- Golder Associates Ltd., Report on Mine Waste and Water Management, Meadowbank Gold Project, Nunavut. 5 March 2004.

The key criteria used to select the preferred tailings storage area are as follows:

- the location should be within a catchment draining toward the open pits
- the facility must have the capacity to store the expected volume of tailings produced over the mine life
- the facility must have the potential to store increased volumes of tailings if mine is expanded
- the location must not preclude future mine expansion
- the facility must allow for collection and control of supernatant.


Based on the selection process, the preferred location for the tailings storage facility at the Meadowbank project is within the de-watered basin of the northwest arm of Second Portage Lake.

7.1 TAILINGS DIKE SITE CONDITIONS

The proposed tailings facility layout is shown on Figure 7.1 and the proposed tailings dike embankment is shown in plan on Figure 7.2 The site conditions along the proposed dike centreline are shown in Figure 7.3. This section was developed using the information obtained from geotechnical investigations conducted in 2002 and 2003, and presented in:

- Golder Associates Ltd., Report on 2003 Field Geotechnical Studies, Meadowbank Project, Nunavut. September, 2003.
- Golder Associates Ltd., Factual Report on Summer 2002, Geotechnical Drilling, Hydrogeological and Permafrost Investigations, Meadowbank Gold Project, Nunavut. 13 December 2002.
- Golder Associates Ltd., Report on Lake Bathymetry Survey, Meadowbank Project, Nunavut Territory. 15 November 2002.

CADD FILE: N:\Bur-Graphics\Projects\2005\1413\05-1413-036A\1050\1300 Project Alternatives\051413036A-1050-7.1-1.dwg
REVISION DATE: 05/10/19 11:45am By: sreddy




NOTES


- 1) Contour information on land supplied by Cumberland Resources Ltd.
- 2) Contours below lake surface are based on bathymetric surveys by Golder Associates Ltd., 2002 and 2003.
- 3) Lake contours are based on surveyed lake surface elevations:
2nd Portage Lake = 133.1 m
3rd Portage Lake = 134.1 m
- 4) All elevations are in metres above mean sea level.

LEGEND

- 02GT-05 Golder borehole, 2002
- 03GT-TD-2 Golder borehole, 2003
- Creek/Stream
- Powerline




PROJECT		CUMBERLAND RESOURCES LTD.	
TITLE		PROPOSED TAILINGS FACILITY LAYOUT	
PROJECT No.	05-1413036A	FILE No.	051413036A-1050-7.1-1
DESIGN	DAH 10NOV03	SCALE	AS SHOWN
CADD	RCR 10NOV03	REV.	0
CHECK	CJC 13OCT05	FIGURE 7.1	
REVIEW	CJC 17OCT05		

 **Golder Associates**

CADD FILE: N:\Bur-Graphics\Projects\2005\1413\05-1413-036A\1050\CAD\1300 Project Alternatives\051413036A-1050-7.2.dwg

REVISION DATE: 05/10/18 2:15pm By: WLI




NOTES

- 1) Contour information on land supplied by Cumberland Resources Ltd.
- 2) Contours below lake surface are based on bathymetric surveys by Golder Associates Ltd., 2002 and 2003.
- 3) Lake contours are based on surveyed lake surface elevations:
2nd Portage Lake = 133.1 m
3rd Portage Lake = 134.1 m
- 4) Basic Engineering Design includes 3 Alternatives for Typical Dike Section. See Figure 7.4.
- 5) All dimensions in metres.
- 6) All elevations in metres above sea level


LEGEND

- | | | |
|--|-----------|-----------------------|
| | 02GT-05 | Golder borehole, 2002 |
| | 03GT-TD-2 | Golder borehole, 2003 |
| | | Powerline |




PROJECT	CUMBERLAND RESOURCES LTD.			
TITLE	PROPOSED TAILINGS DIKE PLAN			
	PROJECT	No. 05-1413-036A	FILE	No 051413036A-1050-7.2
	DESIGN	DAH	10NOV03	SCALE AS SHOWN REV. 0
	CADD	RCR	10NOV03	
	CHECK	CJC	13OCT05	
	REVIEW	CJC	18OCT05	
FIGURE 7.2				

CADD FILE: N:\Bur-Graphics\Projects\2005\1413\05-1413-036A\1050\CAD\1300 Project Alternatives\051413036A-1050-7.3.dwg
REVISION DATE: 05/10/18 1:13pm By: WLI



A
7.2

SECTION ALONG DIKE CENTRELINE



NOTES

- 1) Geological contacts are inferred. Actual contact locations are valid only at borehole locations. Variation from the inferred geological is expected between boreholes.
- 2) Foundation material recovered during drilling indicated a dense gravel till with cobbles and boulders. Few fines were recovered during drilling and sampling.
- 3) All elevations in metres above mean sea level.

LEGEND

— ? —	Inferred Geological Contact
03GT-TD-1	Reverse Circulation Borehole Logged by Golder - 2003
LB	Lake Bottom Location in Borehole Log
B	Bedrock Contact in Borehole Log
EOH (80.2)	End of Borehole at Elevation 80.2masl as Recorded in Borehole Log

PROJECT		CUMBERLAND RESOURCES LTD.			
TITLE		PROPOSED TAILINGS DIKE SITE CONDITIONS			
		PROJECT No. 05-1413-036A		FILE No. 051413036A-1050-7.3	
		DESIGN	DAH	10NOV03	SCALE AS SHOWN
		CADD	RCR	10NOV03	REV. 0
		CHECK	GJC	13OCT05	
		REVIEW	GJC	18OCT05	
		FIGURE 7.3			

- Golder Associates Ltd., Factual Report on Geotechnical Drilling, Hydrogeological, and Geophysical Investigations, Meadowbank Project, Nunavut Territory. 12 July 2002.

The boreholes drilled along the proposed alignment of the dike indicate the following:

- The maximum depth of foundation soil is approximately 18 m.
- The foundation soil consists of glacial till and possibly glacial outwash deposits. The till contains significant amounts of gravel, and cobbles. Based on samples collected from surface around the Meadowbank project site, the material could also contain significant silt or clay. Since water was circulated during drilling, very few fines were recovered.
- At the bedrock contact, there is a zone of highly fractured bedrock. This zone extends along most of the proposed alignment of the tailings dike.
- The zone of fractured bedrock is at least 10 m thick. None of the boreholes reached a less-fractured zone. However, based on results from drilling at nearby locations, the fractured zone may be less than 20 m thick.

In addition to the fractured surficial bedrock, the Second Portage Lake fault will underlie the tailings dike, and will cross the proposed dike alignment approximately perpendicularly. The fault is expected to be a relatively discrete structural feature, based on geotechnical drilling investigations. The hydraulic conductivity of the fault was measured as 5.1×10^{-6} m/s.

7.2 DESIGN ALTERNATIVES

Due to the inability to recover the fine fraction of the foundation material during sampling, it is uncertain whether the in-situ till material along the alignment of the proposed tailings dike is of sufficiently low permeability and of sufficient extent to act as part of a seepage control blanket. This information might not be available until such time as the area has been dewatered. As such, three possible design cross-sections have been developed, as shown in Figure 7.4.


The first design alternative, the “full cutoff” design, includes a full cutoff through the foundation till materials to bedrock. In addition to the compacted till cutoff component, this design would include a pressure grouted curtain in the fractured bedrock.

The second design alternative, the “partial cutoff” design assumes that the foundation till material has sufficiently low permeability, and is of sufficient lateral extent, that a full foundation cutoff is unnecessary. In this case, only a shallow key-in has been included in the section.


Current mine planning indicates that the north portion of Portage pit, closest to the proposed tailings dike, will be mined beginning in Year 4. Therefore, it is possible that the deposited tailings could act as a low-permeability upstream seepage blanket. This scenario was also considered in the seepage analyses.

The third design alternative, “partial cutoff - alternative section,” is a modification of the partial cutoff design, with the seepage cutoff element (compacted till) being located on the upstream face of the embankment, overlying a full rockfill embankment structure.


CADD FILE: N:\Bur-Graphics\Projects\2005\1413\05-1413-036A\1050\CAD\1300 Project Alternatives\051413036A-1050-7.4.dwg
REVISION DATE: 05/10/18 1:22pm By: WLI




SECTION - FULL CUTOFF



SECTION - PARTIAL CUTOFF



SECTION - PARTIAL CUTOFF
ALTERNATIVE



NOTES

- 1) Full Cutoff Design assumes that existing till material is highly permeable and requires foundation cut off structures.
- 2) Partial Cutoff Design assumes the existing till material is of sufficient areal extent and of sufficiently low permeability that foundation cut off structures are not required.
- 3) All dimensions in metres. All elevations in metres above mean sea level.

PROJECT				
CUMBERLAND RESOURCES LTD.				
TITLE				
PROPOSED TAILINGS DIKE DESIGN ALTERNATIVES TYPICAL CROSS SECTIONS				
	PROJECT	No. 05-1413-036A	FILE	No. 051413036A-1050-7.4
	DESIGN	DAH 10NOV03	SCALE	AS SHOWN REV. 0
	CADD	RCR 10NOV03		
	CHECK	GJC 13OCT05		
	REVIEW	GJC 18OCT05		
FIGURE 7.4				

In this case, the cross-section is similar to the partial cutoff, with similar material properties, assumptions for the foundation till materials and the seepage cutoff element. As with the partial cutoff, a shallow key-in at the toe of the upstream face is included. This alternative is considered to be feasible because the current mine plan indicates that the north portion of Portage pit, adjacent to the proposed tailings dike, will not be mined until Year 4. At the time of mining the North Portage area adjacent to the tailings dike, the tailings reclaim pond is expected to be some 200 to 300 m to the west of the dike. Consequently the tailings will then be acting as a low permeability seepage control blanket for the dike, in collaboration with the seepage cutoff element on the upstream dike face. The physical stability of the third alternative is considered to be at least equal to that of the first two alternatives, as the seepage cutoff element is no longer an integral component forming the core of the dike section, and the full dike section is constructed with coarse rockfill. The slope stability, seepage, and thermal characteristics of the structure will be assessed further in detailed engineering.

7.2.1 Proposed Tailings Dike Sections

The proposed full and partial cutoff dike cross-sections consist of:

- a rockfill element, constructed from run-of-mine waste rock, with the upstream and downstream faces designed at a 2H:1V slope
- upstream and downstream filter zones
- a low-permeability compacted till cutoff element, either as a core to the dike, or as an element on the upstream face
- a minimum crest width of 30 m.

Additionally, for the full cutoff design, the cross-section includes:

- a low-permeability compacted till cutoff through the foundation soil
- a pressure-grouted grout curtain through the fractured bedrock zone (at this time it has been assumed that the fractured bedrock is up to 20 m deep, based on available geotechnical drilling information along the dike alignment)

Design details for the proposed cross-sections are presented in the following sections.


7.2.2 Tailings Facility Design Capacity and Required Crest Elevation

The elevation of the crest of the dike has been selected to provide storage capacity for the presently known ore reserves, plus 3 m to provide freeze-thaw and traffic protection for the core.


The required capacity for storage of tailings is calculated using the total mass of tailings (21.9 Mt), and the predicted settled dry density (1.45 t/m^3). This gives a total required volume of 15.1 Mm^3 .

Figure 7.5 shows the storage capacity and elevation curve for the proposed tailings facility.

Tailings Impoundment Area



— Attenuation Pond —◆— Tailings Basin —▲— Total Capacity

PROJECT				
CUMBERLAND RESOURCES LTD.				
TITLE				
TAILINGS STORAGE FACILITY STAGE STORAGE VOLUME CURVE				
		PROJECT No. 05-1413-036A		FILE No. FIGURE 7.5
		DESIGN	CJC	23SEP05
		CADD	SS	23SEP05
		CHECK	CJC	23SEP05
		REVIEW	CJC	17OCT05
				FIGURE 7.5

7.2.3 Proposed Construction Methodology

The tailings dike will be constructed under dry conditions after a portion of Second Portage Lake has been dewatered to elevation 105 m. The area will be dewatered once the East and Bay Zone dikes have been completed.

The tailings dike will be constructed to elevation 120 m in Years -2 and -1 of the mine life. Subsequently, by Year 2, the dike will be constructed to a crest elevation of 139.6 m, followed by a raise in Year 5 to a crest elevation of 144 m.

7.3 DESIGN BASIS & CRITERIA

Slope stability analyses were carried out for the full cutoff and partial cutoff design sections for the tailings dike. The section chosen for slope stability analyses was one that corresponds to the maximum height of the dike. The slope stability analyses were done for unfrozen conditions. If the dike and/or the foundation materials freeze, the strength of the materials would increase, and the slope stability of the dike would increase.

Stability analyses have been carried out for four stages, as follows:

- *End-of-Stage 1 Construction:* The first stage of the tailings dike would be constructed up to an elevation of 120 m. For the full cutoff design, it was assumed that the foundation soil is a permeable material. Strength of this material was assigned effective stress parameters. For the partial cutoff design, it was assumed that the foundation soil would be undrained, and the strength governed by the undrained shear strength of the material. A range of undrained strengths from 10 to 100 kPa was modelled for the foundation till to determine the minimum undrained shear strength required to achieve factor-of- safety design criteria. A potential upstream failure, through the foundation till layer, was modelled.
- *High Water Condition:* During the initial stages of mine life, water will be ponded against the upstream face of the tailings dike, at a maximum elevation of 120 masl. A potential downstream slope failure was modelled for this condition.
- *Potential Downstream Slope Failure:* This scenario was modelled for the completion of tailings deposition to an elevation of 136.6 m, consistent with the previous project objectives of a 10-year mine life and 13.7 Mm³ of tailings. This condition has not been modelled for the shorter life of mine and increased tailings final surface elevation.
- *Closure:* After closure, portions of the Goose Island dewatering dike will be removed, and water will be allowed to flood the Portage pit area, up to elevation 134.1 (the elevation of Third Portage Lake surface). A possible downstream failure was modelled for this condition.

Material properties used in the analyses are summarized in Table 7.1.

Table 7.1: Summary of Material Properties used in Slope Stability Analyses

Material	Unit Weight (kN/m ³)	Effective Stress Parameters		Undrained Strength Parameter, c_u (kPa)	Basis for Property Selection
		Cohesion, c (kPa)	Angle of Internal Friction (°)		
Till Core and Cutoff	15.7	0	28	n/a	Direct shear testing ¹
Rockfill	18.6	0	40	n/a	Previous experience with similar material
Overburden	17	0	28 to 32	10 to 100	Previous experience with material with similar grain size distribution

Notes: 1. Golder geotechnical investigations. 2. For till core material, assumed $c'=0$ for effective stress case.

For the Meadowbank site, the predicted PGA is 0.044 g for a seismic event with a return period of 975 years. The pseudo-static analyses have been done using a horizontal acceleration of 0.022 g. This value corresponds to one-half of the firm ground acceleration for the 1000-year return period event (USACE, 1984). The 1,000-year return period is considered appropriate, given that:

- the dike will be retaining water and tailings while personnel and equipment are working in the Portage pit
- the design life of the dike is less than 20 years.

7.4 SLOPE STABILITY

7.4.1 Results of Analyses for End-of-Construction Conditions

Slope stability analyses were carried out to evaluate the short-term, end of Stage 1 construction situation. For the full cutoff design, the foundation till material was assumed to be permeable. For the partial cutoff design, the foundation till was assumed to be undrained.

In both cases, the dike was modelled with a crest elevation of 120 m. This corresponds to the first stage of construction, to be completed in Year -1 of the mine life.

For the partial cutoff design case, the section was analyzed to determine the values of the undrained shear strength (c_u) which would yield factors of safety (FOS) of 1.0 and 1.3. A FOS of 1.3 is the minimum value required for the end of construction condition. A FOS of 1.0 is the value at which failure would begin to occur.

Table 7.2 presents the results of the end-of-construction conditions, and indicates that the Stage 1 dike will be stable for drained conditions with an associated FOS of 2.7.

Table 7.2: Summary of End of Stage 1 Construction Stability Analyses

Condition	Strength Parameters	Minimum Calculated FOS	Required Undrained Shear Strength of Foundation Till to Achieve a FOS of 1.3 (kPa)
Drained	c', ϕ	2.7	-
Undrained	cu	See Note 1	60 to 70

Notes: 1. A factor of safety of 1.3 has been assume in order to calculate the minimum undrained shear strength of the foundation till to meet design requirements.

The analyses also indicate that, for undrained end of construction conditions, the minimum undrained shear strength of the foundation materials required to achieve a EQS of 1.3 is about 60 to 70 kPa. The foundation soils that have been recovered during the geotechnical investigations carried out in other areas of the Meadowbank site indicate silty till material containing significant proportions of gravel and cobbles. Undrained shear strengths of this material are expected to be at least equal to or greater than 70 kPa, based on experience with similar materials at other sites. In the partial cutoff design case, undrained shear strength testing will be required during the detailed engineering design stage for the dike.

7.4.2 Results of Analyses for Long-Term, Steady-State Seepage Conditions

Slope stability analyses were done to evaluate the stability of the dike under long-term, steady-state seepage conditions, at three critical points in the life of the dike, and after closure. These were:

- In the early stages of mine life, free water ponded against the dike, with the water surface at approximately 120 masl. This situation was modelled under static and pseudostatic conditions.
- At the end of Year 10, deposition of tailings will be complete, and the tailings will be at their maximum elevation. This situation was modelled under static and pseudostatic conditions. This condition has not been modelled for the shorter life of mine and increased tailings final surface elevation.
- During closure of the facility, water will be allowed to flood the Portage pit side of the tailings dike. This situation was modelled under static and pseudostatic conditions.

The results of the long-term analyses are summarized in Table 7.3.

Table 7.3: Summary of Long-Term Slope Stability Analyses

Failure Mode	Minimum Calculated Factors of Safety		Yield Acceleration (g)
	Static (Minimum = 1.5)	Pseudostatic (Minimum = 1.2)	
High Water (Water at Elevation 120 m)	2.0	1.8	0.21
End of Deposition (Tailings at Elevation 136.6)	2.3	2.2	0.41
Closure	4.9	4.3	0.43

Notes: 1. FOS = 1.5 is minimum specified for long-term – see Ref. 7. 2. FOS = 1.2 is minimum specified for pseudostatic – see Ref. 7.

Based on the analyses, the dikes will be stable in the long term, for static and pseudostatic loading conditions.

7.5 SEEPAGE

Seepage analyses were carried out for the maximum section, for both the full and partial cutoff design cases. According to the current mining plan, the north portion of the Portage pit nearest the proposed tailings dike will not be mined until at least Year 4 of the mine life.

It is expected that seepage into the Portage pit for the “partial cutoff – alternative section” design will be similar to the partial cutoff design, with Year 3 tailings beach and reclaim pond 200 to 300 m back from the dike face. This situation was analysed considering the following:

- the foundation till is of higher permeability
- the dike cross-section includes a till core but no cutoff structures
- tailings have been deposited against the upstream face of the dike, and at a nominal slope into the impoundment
- the tailings pond is at a distance of 200 m from the face of the dike.

Material properties used in the analyses are presented in the Table 7.4.

Table 7.4: Summary of Material Properties used in Seepage Analyses

Material	Hydraulic Conductivity (X 10 ⁻⁶ m/s)	Comments/Basis for Properties
Till Core and Cutoff (Cutoff is for Full Cutoff Design only)	0.1	<ul style="list-style-type: none"> • falling head tests from Dec 2002 geotechnical testing • experience with materials with similar genesis and grain size distribution • if till core and/or cutoff material is thawed after initial freezing, it is possible that the hydraulic conductivity of this material could increase, unless the upstream portion of the till is maintained in a frozen state.
Rockfill	10,000	
Foundation Till – Full Cutoff Design	100	<ul style="list-style-type: none"> • assumes material is free-draining
Foundation Till – Partial Cutoff Design	0.1	<ul style="list-style-type: none"> • assumes material is relatively low permeability
Grout Curtain – Full Cutoff Design only	0.05	<ul style="list-style-type: none"> • previous experience
Fractured Bedrock	40	<ul style="list-style-type: none"> • BH O3GT-TD-4 falling head packer test
Deeper Bedrock	0.001	<ul style="list-style-type: none"> • report on Hydrogeology Baseline Studies.
Tailings	0.1	<ul style="list-style-type: none"> • conservative estimate for fine-grained tailings, based on experience with similar materials, and published values (Vick 1990)

Table 7.5 shows the seepage flux to the Portage pit west wall through the tailings dike.

Table 7.5: Seepage Fluxes at the Portage Pit West Wall

Design	Flux (m ³ /s/m)	Flow into Portage Pit (L/s)
Full Cutoff Design	3.3 X 10 ⁻⁵	26
Partial Cutoff Design	3.5 x 10 ⁻⁵	28
Partial Cutoff Design with Year 3 tailings beach (pond at 200 m from upstream dike face)	9.0 x 10 ⁻⁵	71
Partial Cutoff Design with Frozen Core and Cutoff	3.3 x 10 ⁻⁵	26
Full Cutoff Design with tailings beach at 100 m from upstream dike face	1.5 x 10 ⁻⁵	12

It is anticipated that the majority of the seepage flows will report to the pit dewatering system. This water would be returned to the tailings reclaim pond.

The seepage analyses show that the proposed designs are effective at controlling seepage through the tailings dike.

7.5.1 Tailings Dike Grout Curtain

As part of the evaluation of cutoff alternatives for the tailings dike, and to address some of the uncertainty associated with incomplete information relating to the foundation materials and the presence of the Second Portage Fault beneath the storage facility, estimates of quantities required for drilling and injection grouting and concrete cap for the full cutoff design were developed, and are presented in the following Table 7.6.

Table 7.6: Drilling & Injection Grouting Estimates for the Tailings Dike

Item	Quantity
Number of Grout Curtain Holes	800
Total Drilling Length – Grout Curtain	16,000 m
Volume of Grout – Grout Curtain	1,650,000 L
Number of Consolidation Grouting Holes	1,200
Total Drilling Length – Consolidation Grouting	6,000 m
Volume of grout – Grout curtain	250,000 L

The quantities are based on the following assumptions.

- Foundation rock is characterized as highly fractured. Average conductivity from field tests is around 3 to 4 x 10⁻⁵ m/s in the upper 5 to 10 m of bedrock, which is equivalent to the hydraulic conductivity measured within the Second Portage Lake fault.

- Assume a nominal depth of treatment to 20 m in bedrock across the foundation. Note that the geotechnical drilling did not penetrate through the fractured bedrock layer.
- Estimates assume a single row grout curtain.
- Slope length along centreline of core trench: 1,200 m.
- Average hole spacing in completed curtain: 1.5 m.
- One upstream and one downstream row of consolidation grout holes.
- Average hole spacing in consolidation rows: 2 m.
- Depth of consolidation grout holes: 5 m.
- Assume 75 l/m grout admission, with 15% waste.

7.6 POST-CLOSURE THERMAL ANALYSES

The potential for acid generation and metal leaching from the tailings via seepage to the deep groundwater regime will be reduced by the development of a horizontally-continuous layer of frozen tailings across the tailings mass. This will limit the infiltration of air and water into the tailings.

A cover of ultramafic rock will be placed over the tailings, such that the active layer does not develop within the tailings mass, thereby limiting cryoturbation within the frozen tailings.

After closure, the tailings dike will need to act as a thermal barrier to limit the heat transfer from the lake water toward the tailings. The current analyses of the overall tailings facility predict that the tailings and the existing talik below the tailings storage facility will freeze in the long term.

A thermal model of the tailings dike was developed for the tailings dike to investigate whether the 0°C isotherm would lie within the tailings dike, or would penetrate into the tailings. Both steady-state and transient analyses were run.

7.6.1 Steady-State Analysis

A steady-state analysis of the post-closure dike configuration was performed using the following boundary conditions:

- Ground surface temperature = -11°C.
- Water temperature = +4°C.
- Geothermal flux at base of model = 0.05 1 W/m².

The ground surface temperature was applied over the surface of the tailings, and on the exposed portion of the tailings dike. The water table in the east side of the dike was assumed to extend horizontally through the rockfill, to the till core. Material properties used in the thermal analyses are shown in the Table 7.7.

Table 7.7: Summary of Material Properties in Post-Closure Thermal Analyses

Material	Thermal Conductivity (kJ/day-m-°C)		Volumetric Heat Capacity (kJ/m ³)	Unfrozen	Volumetric Water Content (%)
	Frozen	Unfrozen	Frozen		
Compacted Till Seepage Cutoff Elements	3.3	2.4	1.9	2.5	0.28
Rockfill	3.3	2.8	2.4	2.6	0.12
Foundation Till	3.3	2.8	2.4	2.6	0.12
Fractured Bedrock	3.3	2.8	2.4	2.6	0.12
Deep Bedrock	3.5	3.4	2.39	2.4	0.02
Tailings	2.2	1.6	2.2	2.95	0.50

Figure 7.6 shows the results of the steady-state thermal analyses. The 0° isotherm is located within the tailings dike, indicating that the dike would be an effective thermal barrier between the lake and the tailings.

7.6.2 Transient Analysis


The tailings dike area was also analyzed for the transient thermal case, for:

- the case where no variation from the current climate patterns is anticipated
- the case where there will be a 5.5°C increase in average air temperature over the one- hundred years following closure of the mine.

The purpose of the transient model was to assess the potential for seasonal variations in temperature to affect the till core of the dike, particularly the top portion of the core. Given that the hydraulic conductivity of the till could increase if thawed after being frozen, it was also important to assess the potential for thawing due to climate change. The material thermal properties used in the transient analyses were the same as those used in the steady-state analysis.

Other parameters used in the analyses are shown in Table 7.8.

REVISION DATE: 05/10/20 9:26am By: sreddy CADD FILE: N:\Bur-Graphics\Projects\2005\1413\05-1413-036A\1050\CAD\1300 Project Alternatives\051413036A-1050-7.6.dwg



MATERIAL PROPERTIES

Material Type	Thermal Conductivity (J/sec-m-°C)		Volumetric Heat Capacity (J/m³-°C)(x 10 ⁶)		Volumetric Water Content
	Frozen	Unfrozen	Frozen	Unfrozen	
Till Core & Cutoff	3.3	2.4	1.9	2.5	0.28
Rockfill	3.3	2.8	2.4	2.6	0.12
Foundation Till	3.3	2.8	2.4	2.6	0.12
Fractured Bedrock	3.3	2.8	2.4	2.6	0.12
Deep Bedrock	3.5	3.4	2.4	2.4	0.02
Tailings	2.2	1.6	2.2	2.95	0.5

NOTES

- Analyses done using TEMP/WTM Software.


PROJECT								
CUMBERLAND RESOURCES LTD.								
TITLE								
POST-CLOSURE THERMAL MODELLING FULL CUTOFF TAILINGS DIKE - STEADY STATE ANALYSIS								
	PROJECT No.		05-1413-036A		FILE No.	051413036A-1050-7.6		
	DESIGN	DAH	23DEC03		SCALE	AS SHOWN	REV.	0
	CADD	RCR	23DEC03		FIGURE 7.6			
	CHECK	CJC	13OCT05					
	REVIEW	CJC	18OCT05					

Table 7.8: Summary of Modelling Parameters for Post-Closure Transient Thermal Modelling


Parameter	Conditions Used in Model
Initial Conditions	Post-Closure steady-state conditions assumed.
Boundary Condition Functions	<ul style="list-style-type: none"> • For tailings surface and exposed portion of tailings dike, a function assuming no snow cover was used. • For climate change, a linear warming trend of 5.5°C over 100 years was used. • A constant temperature of +4°C was used for water.
Time steps	Ten-day time steps used.
Total duration of modelling	<p>Ten years for transient modelling not including climate change. Duration chosen to be sufficient to allow stabilization of 0°C isotherm below active layer.</p> <p>For climate change, 100 years was used.</p>

Figure 7.7 summarizes the results of the transient thermal modelling without including for climate change, and shows the isotherms for January and August. Figure 7.8 shows the results for the transient thermal modelling including the effects of climate change.

The figures indicate that the active layer does not penetrate into the till core, and the till core will remain frozen.


CADD FILE: N:\Bur-Graphics\Projects\2005\1413\05-1413-036A\1050\CAD\1300 Project Alternatives\051413036A-1050-7.7.dwg
REVISION DATE: 05/10/13 12:40pm By: WL1

File Name: Small mesh transient.tez
Last Saved Date: 09-Jan-2004
Last Saved Time: 11:41:07 AM
Analysis Type: Transient



THERMAL REGIME IN JANUARY

File Name: Small mesh transient.tez
Last Saved Date: 09-Jan-2004
Last Saved Time: 11:46:26 AM
Analysis Type: Transient




THERMAL REGIME IN AUGUST


MATERIAL PROPERTIES

Material Type	Thermal Conductivity (J/sec-m-°C)		Volumetric Heat Capacity (J/m³-°C)(x 10 ⁶)		Volumetric Water Content
	Frozen	Unfrozen	Frozen	Unfrozen	
Till Core & Cutoff	3.3	2.4	1.9	2.5	0.28
Rockfill	3.3	2.8	2.4	2.6	0.12
Foundation Till	3.3	2.8	2.4	2.6	0.12
Fractured Bedrock	3.3	2.8	2.4	2.6	0.12
Deep Bedrock	3.5	3.4	2.4	2.4	0.02
Tailings	2.2	1.6	2.2	2.95	0.5

NOTES

- 1) Analyses done using TEMP/WTM Software.
- 2) All dimensions are in metres. All elevations in metres above sea level.




PROJECT	CUMBERLAND RESOURCES LTD.				
TITLE	POST-CLOSURE THERMAL MODELLING FULL CUTOFF TAILINGS DIKE - TRANSIENT ANALYSES				
	PROJECT	No. 05-1413-036A	FILE	No. 051413036A-1050-7.7	
	DESIGN	DAH	23DEC03	SCALE	AS SHOWN
	CADD	RCR	23DEC03	REV.	0
	CHECK	GJC	13OCT05	FIGURE 7.7	
REVIEW	GJC	18OCT05			


CADD FILE: N:\Bur-Graphics\Projects\2005\1413\05-1413-036A\1050\CAD\1300 Project Alternatives\051413036A-1050-7.7.dwg
REVISION DATE: 05/10/13 1:03pm By: WL1

File Name: Small mesh transient with climate change - large time steps for checking.tez
Last Saved Date: 12-Feb-2004
Last Saved Time: 8:10:56 AM
Analysis Type: Transient

File Name: Small mesh transient with climate change - large time steps for checking.tez
Last Saved Date: 12-Feb-2004
Last Saved Time: 8:10:56 AM
Analysis Type: Transient



CLIMATE CHANGE YEAR 100
JANUARY




CLIMATE CHANGE YEAR 100
AUGUST

MATERIAL PROPERTIES

Material Type	Thermal Conductivity (J/sec-m-°C)		Volumetric Heat Capacity (J/m³-°C)(x 10 ⁶)		Volumetric Water Content
	Frozen	Unfrozen	Frozen	Unfrozen	
Till Core & Cutoff	3.3	2.4	1.9	2.5	0.28
Rockfill	3.3	2.8	2.4	2.6	0.12
Foundation Till	3.3	2.8	2.4	2.6	0.12
Fractured Bedrock	3.3	2.8	2.4	2.6	0.12
Deep Bedrock	3.5	3.4	2.4	2.4	0.02
Tailings	2.2	1.6	2.2	2.95	0.5

NOTES

- 1) Analyses done using TEMP/WTM Software.
- 2) All dimensions are in metres. All elevations in metres above sea level.




PROJECT

CUMBERLAND
RESOURCES LTD.

TITLE

POST-CLOSURE THERMAL MODELLING
FULL CUTOFF TAILINGS DIKE - TRANSIENT ANALYSES
INCLUDING CLIMATE CHANGE EFFECTS

Golder
Associates

PROJECT	No. 05-1413-036A	FILE	No. 051413036A-1050-7.7
DESIGN	DAH	10FEB04	SCALE AS SHOWN
CADD	SRP	10FEB04	REV. 0
CHECK	CJC	13OCT05	
REVIEW	CJC	18OCT05	

FIGURE 7.8

SECTION 8 • PROCESS SELECTION

8.1 GOLD RECOVERY

Comparative scoping level capital cost estimates were developed for three process flowsheet options based on a plant throughput of 7,500 t/d:

- Base Case – whole ore leaching
- Option 1 – flotation concentrate leach
- Option 2 – flotation concentrate and tailings leach.

The trade-off study indicated that the Meadowbank deposits are more economically amenable to whole ore cyanidation than to the more-complex bulk sulphide flotation and concentrate cyanidation flowsheet used in the prefeasibility study. Subsequently, whole ore cyanidation was selected as the basis for the current feasibility study. A simplified flow diagram is shown in Figure 8.1.


The selected gold recovery process uses a traditional cyanide leach process, which generates a cyanide concentration of approximately 200 mg/L cyanide in solution, following the recovery of precious metals. The cyanide content of the process solutions will be reduced to approximately 2 to 5 mg/L using a patented INCO SO₂/air process. Because of the short- to mid-term residual reactivity resulting from the destruction process, solutions from cyanide destruction cannot be recycled immediately. The process solutions must be aged for complete cyanide destruction and to reduce chemical oxygen demand. The aging process is expected to require up to two months in a natural setting, a timeframe consistent with those at other gold processing operations that use this approach. The large inventory of solution will also provide a form of “chemical inertia” to the recirculating process water chemistry and reduce the impact of variable sulphide mineralogy within the mined ores. It has been shown that changes in solution chemistry can affect the overall extraction of gold from the ores, owing to the presence of oxidation products from the sulphide mineral phase when present in high concentrations.

8.2 TAILINGS PROCESSING

Three scenarios were considered for the deposition and storage of ground tailings from the gold recovery and cyanide recovery processes:

- filtering out the process tailings solids and stacking the resulting filter cake into tailings piles
- thickening/filtering the tailings slurry to a very high density, disposing of the resulting slurry without solution recovery, and recycling the filtrate solutions
- directly placing the tailings slurry either subaerially or subaqueously within an impoundment to permit solids to settle and process solutions to decant for re-use.

Figure 8.1: Simplified Flow Diagram for Proposed Meadowbank Process



In all three scenarios, a pond of process solution would need to be maintained to provide sufficient aging and volumes of stored process water. In the third option, process solids and process solutions would be stored within the same facility. In the first two options, the solids would be placed and stored separately from the process solutions; the impact on closure would be far greater than for the combined placement concept in option 3 because of the space required for the separate types of storage.


The option of combined tailings solution and solids placement has been selected for the feasibility study. The process would operate at a solids concentration of 45% to 55% (by weight), which corresponds to the product stream from the gold recovery plant. Recycling the solutions will allow for management of water quality within the process and minimize the impact of any process solution spillage on the surrounding surface and groundwater.

SECTION 9 • WATER MANAGEMENT & TREATMENT

A staged water management strategy has been designed for the Meadowbank project (central Portage mining area) based on the use of Second Portage Arm (see Figure 9.1) for the tailings storage facility. Initially, the eastern end of Second Portage Arm will be used for tailings discharge, the central area will serve as a reclaim pond, and the western end will be used as a stormwater attenuation pond until Year 5. After Year 5, mining of the Goose Island pit will be complete, and the pit will be operated as the attenuation storage facility. The former attenuation storage facility at the northwest end of Second Portage Arm will be used to manage reclaim water. At the end of mining, the process plant will be converted to water treatment, and the remaining water in the reclaim pond will be treated and released.

A site-wide water balance has been developed to evaluate the interaction between the various mine components as these relate to water consumption and use. The water balance allows the evaluation and prediction of water requirements for the mill process, tailings pond, re-watering of the open pits at closure, among other considerations. The model takes into account average annual climate data as well as predicted storm events to allow the appropriate sizing of water storage and conveyance structures. In the long term, the water balance model will be used to assess the predictions made for the mine during the feasibility studies against actual site conditions experienced during operations. This will allow appropriate mitigative measures to be identified at an early stage if it becomes apparent that alterations to the mine water management plan are required.

The type of treatment will depend on the quality of water to be discharged. Preliminary analysis indicates that levels of dissolved copper, zinc, and nickel may be elevated and need to be removed through a lime treatment process. Another possibility is to collect the storm runoff water separately and pump it to Third Portage Bay, west of the plant site, after Year 6 to serve as a settling pond. Having no contact with the tailings slurry or reclaim water, the runoff water may not need to be treated before discharge, reducing capital and operating costs. Further laboratory testing is required before design is finalized.



SECTION 10 • WORKFORCE CONSIDERATIONS

The Meadowbank project is being planned as a fly-in/fly-out mining operation, similar to other northern mines such as Lupin, Diavik, Ekati, and Polaris. On-site accommodations will be provided for approximately 250 people on bi-weekly rotations. Personnel will be transported to and from site by air service. The community of Thompson, Manitoba, is currently considered the point of origin for personnel based in the South and for air freight. Some smaller aircraft may be used to transport mine personnel residing in local northern communities where suitable commercial air service is not available.

Negotiations for the Inuit Impact and Benefit Agreement (IIBA) are ongoing and address some of the following opportunities:

- jobs
- training
- preferential hiring programs
- project financing
- new business and contract arrangements
- participation in monitoring activities and dispute resolution.

To the extent that workers can be hired from the local population, fly-in/fly-out arrangements could be scaled back. During the 2002 field season, Cumberland was one of the largest private employers in Baker Lake, with local residents comprising 54% of the project's workforce. Similar employment averages have been maintained since 1995, when exploration activities began.

SECTION 11 • ENERGY SOURCES

Typically and traditionally, remote northern mining projects use on-site, diesel-generated power for electrical supply unless they are close to a grid supply (within 100 km). This is usually based on considerations of proven technology, reliability, cost, and practicality. In the case of the Meadowbank project, the nearest grid is far to the south. Power for the community of Baker Lake itself is in fact supplied from diesel generators.

Other recent projects in northern Canada have considered wind, solar, and hydrogen fuel cell technologies but have found them to be lacking, even as supplemental sources to reduce diesel consumption and attendant air emissions. Alternative energy sources are briefly discussed below.

11.1 WIND POWER

This technology generally involves relatively high capital costs and is only effective under very specific wind conditions. The key parameter is sustained average wind speed: speeds above 8 m/s are deemed excellent and those below 4 m/s unacceptable. Wind speed at the Meadowbank site is variable and averages 4.8 m/s annually to a height of 10 m above the ground and slightly greater above 10 m (note that “average” is not necessarily “sustained”). At Baker Lake, the average wind speed is 5.9 m/s.

Wind power offers no significant economic advantages for the Meadowbank project because the variable wind speeds would not meet the steady demand of the process plant and related facilities. The only gains would be small reductions in air emissions associated with a limited wind power installation to supplement diesel-based power generation.

11.2 SOLAR

Conversion of solar radiation to electrical power or for use in direct heat exchange tends to be expensive and to have minimal benefit in winter months. Some limited use of solar heat exchange for building heating may be feasible in the spring and fall. This could be investigated during detailed design if the other anticipated sources of waste heat prove to be unavailable or inadequate.

11.3 HYDROGEN

Although hydrogen fuel cells are emission free, the technology is not yet proven and the costs are very high, particularly for remote sites. In addition, an economic source of hydrogen would need to be identified.

11.4 HYDROELECTRIC POWER

In spite of the potential advantages to the project of this type of power supply, no suitable site has been identified for the establishment of hydroelectric power-generating facilities.

11.5 OPTIONS TO REDUCE POWER CONSUMPTION

The project is designed to limit power use, diesel consumption, air emissions, and costs. Design concepts to further these objectives are listed below.

- use glycol heat exchangers to convert heat extracted from the diesel generating sets for heating buildings
- heat the process plant complex with excess heat generated by the process equipment
- minimize power losses and waste by using automated power plant management controls
- generally use high-efficiency electric motors
- use high-efficiency lighting such as metal halide lamps
- monitor and control building heating.

These and other refinements will be adopted as detail design proceeds.

SECTION 12 • TRANSPORTATION

Cumberland has considered various options for shipping project consumables to site. These materials will consist predominantly of diesel fuel and process supplies such as steel and reagents. Transport alternatives all generally consist of shipping during summer months from southern ports to a location in the vicinity of Baker Lake, as well as overland via an all-weather road to site (see Figure 12.1).

12.1 SUMMER SHIPPING OPTIONS

The prefeasibility study evaluated shipping options from eastern ports and also from southern railheads. Four options were considered and compared:


- *Deception Bay* – Use nickel ore carriers from the Raglan project to backhaul supplies, with transshipment at Deception Bay and onward shipment by tug and barge to Baker Lake. This option was not deemed suitable by the shipping companies that were approached for options and pricing.
- *Rankin Inlet* – Use a deep-sea shipping service from eastern ports to a future common user dock and storage facility at Melvin Bay, with tug and barge shipment to Baker Lake. This option was discounted because there is no firm indication that the required facility would be built in time to service the project.
- *Chesterfield Inlet (Schooner Harbour)* – Use deep-sea shipping to an anchorage in Schooner Harbour with lightering up Chesterfield Inlet by tug and barge. This would be less efficient and cost effective than direct barge shipment to Baker Lake because no trans-shipment facilities are available, and Chesterfield Inlet is distant (approximately 170 miles east) from Baker Lake.
- *Direct Tug & Barge Service* – Use a 6,000 to 8,000 DWT barge from Montreal or Halifax through Chesterfield Inlet to Baker Lake. At high water, a barge should be capable of carrying about 6,000 tonnes of cargo safely through the most constrained part of the inlet. Chesterfield Inlet is a 124 mile long, salt-water channel typically used by shallow draft barges and small vessels but not by deep-sea vessels. Depending on the type of vessel used and whether it is ice-strengthened, the shipping season ranges from about 2.5 months to 4 months.

Based on the pricing and equipment availability enquiries conducted for the prefeasibility study, direct shipping using adapted tug and barge equipment is considered the best option for the project.

12.2 ACCESS ROAD

Initial selection annual re-supply requirements at the mine site are estimated to be 20,000 to 30,000 tonnes, including 10,000 to 15,000 tonnes of process and mining consumables (reagents, tires, lubricants, mill steel, explosives). Options for haulage during winter from temporary storage at Baker Lake were investigated by soliciting budget quotes from experienced northern logistics companies. Two fundamental options are evident:

Figure 12.1: Marine & Overland Transportation Options



- use of tractor-trailer units on a maintained ice road or permanent all-weather road
- all-terrain tracked or low-pressure-tired equipment towing trailers or sleds.

The feasibility evaluation of the project considered the following alternative access options to the project:

- an ice road
- a seasonal land road
- a permanent all-weather road.

These are discussed in the following sections. Based on the feasibility evaluation of the alternatives, the preferred option is the permanent all-weather access road.

12.3 ICE ROAD

Tractor-trailers have been used to haul large volumes of freight and fuel over ice roads to service several large during construction projects and operations. For example, Robinson Enterprises Limited hauled more than 100 ML of fuel and 20,000 tonnes of dry goods over ice roads in 1997. Conventional trucks have been used for winter road haulage out of centres such as Yellowknife for several decades; these haulage fleets demobilize each season for southern use.

In 1993 and 1994 an experimental winter road was constructed between Rankin Inlet and Arviat. Maintaining driveable conditions was found to be very difficult because of snow drifting. Consequently, concern has been expressed that winter road construction and operation between Baker Lake and the Meadowbank site may not be feasible given the commonly inclement winter conditions. Balloon-tired, all-terrain articulated trucks have been used successfully in the vicinity of Baker Lake for the last 20 years or so, and have the advantage of not requiring a cleared roadway. While these vehicles are slower and considerably more expensive to purchase, minimal additional equipment and effort is needed to form and maintain a trafficable trail.

Two transportation contractors provided detailed plans and pricing for operating tractor-trailers or a fleet of all-terrain trucks over a conventional winter road, both following the same route from Baker Lake to Meadowbank. In both cases, the transportation fleet would remain captive at Baker Lake from year to year. The comparison is detailed in Table 12.1.

Table 12.1: Tractor-Trailer vs. All-Terrain Vehicle Operations – Winter Road

Aspect	Tractor-Trailer	All-Terrain Vehicle	Comment
Technical	28 day preparation and 75 day haulage	135 day haulage season	Tractor-trailer option requires support fleet, so shorter season is desirable to reduce operating costs
	Method well preceded at planned scale	Little precedent at planned scale	No fundamental reason for ATV not to succeed
	Experienced companies available and credible	Local operators need to build infrastructure and demonstrate management capability	2004 advanced exploration will test ATV and locally based operator further
Cost	Similar within 10%		Comparable to other projects/estimates
Environmental	Quote based on building snow/ice base over portages	Same approach	No permanent roadway construction across portages
	Risk of accidents and spills may be higher due to higher speed	Risk of mishaps/spills due to operation in poor visibility difficult to quantify but considered significant	Likely to be mitigated through good training and management for both options
	Shorter season may reduce effects on terrain	Longer period to mid-May may affect thaw and vegetation response	No reported effects of limited ATV operations in recent years
	Uses ½ the fuel of alternate	Uses 2 times the fuel of alternate	May be a significant difference in air pollution
	Wide roadway likely affects/influences fauna movements	Narrower, somewhat less distinct track may have less adverse impact on fauna	
Community	Fewer work-hours	More work-hours, longer period of winter operations	
	Smaller proportion of local labour hire	Relatively high use of local labour	Both depend on availability of trained staff
Regulatory	Likely more regulatory process required to permit	Local operator possesses permit for current level of ops; may be easier to scale up	Cumberland must verify PEL claim that sufficient permitting is in place for full scale operation
Overall Benefit	Less employment and less synergy with current methods of transport in region	Higher employment and more synergy	Assumed overall cost is similar for both quotes at current level of accuracy

Currently, an ice trail is used to service the project site from approximately January to May over a period of approximately 122 days. The practical period of use, accounting for white-out conditions, is estimated to be about 90 days. A seasonal ice road would have a limited and low environmental impact. However, there would be risks associated with the transport of fuel and other chemicals required for the mining project in the event of an accident on the ice. Based on the present project requirements, the shipment schedule will require the acquisition of at least 23 Foremost Delta 3 all-terrain transport units to complete the transport activities within the prescribed safe operating period

for the winter ice road. Due to the required fleet size, and associated risk, the ice road alternative is not considered to be a viable alternative.

12.4 SEASONAL LAND ROAD

As an alternative to the winter ice road, preliminary consideration was given to provide a seasonal land road to maximize the safe operating period up to the observed freezing period of 243 days from October 1 to May 31 each year. Although the observed freezing period is approximately 243 days, travel along the route would be unlikely before November of each year to allow sufficient frost penetration into the soils to carry the applied loads. Therefore, the operational period for this alternative would be on the order of about 213 days, not accounting for white-out conditions. A seasonal land road access will be limited to operate during extended seasonal frozen ground conditions and not operate during seasonal thaw conditions, spring freshet or summer stream flow periods.

It is envisaged that a seasonal land road would require some local ground improvement using materials available along the route, but water course crossing structures would not be constructed. A preferred seasonal land route would limit water course crossings to locations having less than 2 m of water, and would not require the construction of bridges or culverts as travel would only be during frozen conditions. Therefore, seasonal land road access will be limited to operate during extended seasonal frozen ground conditions and not operate during seasonal thaw conditions, spring freshet or summer stream flow periods.

Advantages of a seasonal road are:

- reduced fuel storage requirement at Meadowbank
- reduce number of haul units required
- use more economical conventional haul units instead of costly ATVs
- reduced transport costs Baker Lake to Meadowbank
- reduced construction equipment rental costs
- reduced environmental impact risks by not hauling fuel and reagents on ice surface
- unlimited load weight capability
- increased reliability for the delivery of supplies.

It is understood that the seasonal land route will not consider the use of thaw stable road embankments and water crossing structures. Thaw settlement should be expected for thin embankment fills constructed over soft subgrade soils or organic deposits. It is envisaged that a typical road structure for a capital cost-effective season land road will be less than a permanent all-weather road. However, the season land road will require more operational maintenance, particularly during the seasonal thermal transition periods.

12.5 ALL-WEATHER LAND ROUTE

As an alternative to the winter ice road and seasonal land road, consideration was given to a permanent all-weather access road. The all-weather access road would require the construction of bridge structures for water course crossings.

Construction of an all-weather land road will require the development of suitable borrow deposits and rock quarries along the route for the preparation of the sub-base and for surfacing materials. The travel surface would be 10 m in width and nominally 1.5 m in height above the original ground to preserve permafrost in the sub-grade. Surfacing would be crushed 3" minus rock. The bridges would be single-lane prefabricated logging road style structures supported on rock fill cribs.

Advantages of an all-weather road are:

- reduced laydown area required at Baker Lake
- reduced explosives and reagent storage at Baker Lake
- reduced fuel storage requirement at Meadowbank
- reduced transport fleet required
- reduced capital cost of transport fleet using conventional tractor trailer units instead of ATVs
- reduced freight costs Baker Lake to Meadowbank
- reduced equipment rental costs
- rapid delivery of critical spares (air freight to Baker Lake then overland transport)
- reduced risk of fuel and reagent spills on lake ice
- greater reliability of freight delivery schedules
- reduced airstrip length at Meadowbank
- enhanced alternate medivac capability
- reduced impact on permafrost in comparison to seasonal road effect.

12.6 PREFERRED ALTERNATIVE

Based on environmental, technical, and economic considerations, the all-weather land route is the preferred alternative.

Once the preferred alternative was defined, an additional evaluation of routing alternatives was undertaken.

12.7 PERMANANT LAND ROUTE ALTERNATIVES

Once the preferred access method was decided on, three alternative land routes were identified and evaluated for consideration within an access route corridor ranging between about 5 and 25 km wide.

Their general location relative to the winter ice road, estimated route length, and number of water crossings are summarized in Table 12.2 and are shown on Figure 12.2.

Table 12.2: Comparison of All-Weather Road Alternatives – Location, Length & Water Crossings

Route Name	Location Relative to Winter Ice Road	Estimated Length (km)	Estimated Number of Water Crossings
Green	Most westerly access route, up to 13 km west of the winter ice road and following high ground relief.	115	19
Red	West of ice road, within Green route alignment, up to 11 km west of the winter ice road and following low ground relief.	95	23
Yellow	East of ice road, up to 15 km west of the winter ice road and following low ground relief.	96	27


Initial field investigations involved preliminary route assessment from helicopter and air photo interpretation. The initial investigations also involved the collection of hydrology data during low and peak flow periods at stream crossings along the various routes. Based on the initial investigations, the Green route was selected as the preferred route alternative.


12.8 PREFERRED OPTION – GREEN ROUTE

Based on the assessment, the Green route was selected as the preferred option. The route length, as measured from the proposed Baker Lake marshalling area to the Meadowbank project site, is approximately 115 km. Detailed air photo interpretation was carried out for the Green route. Air photo coverage is shown on Figure 12.3 along with the proposed route alignment. Initially, 23 stream crossings were identified along the proposed Green route. This number was increased to 25 during the air photo interpretation study. The subsequent ground mapping program resulted in a reduction in the number of required stream crossings to approximately 19.


In general, the regional setting for the study area comprises poorly-drained low lying to moderate topographic relief resulting from post-glacial activities. The study area is surfaced with numerous water bodies and stream channels, organic filled depressions, glacial till sheets, limited granular deposits and exposed bedrock outcropping with coarse grained weathered block fields. The assessment indicated that surficial materials are potentially better drained along the Green route than for the other proposed routes. The Red and Yellow routes are shorter road lengths as they are located in lower ground relief and require a number water course crossings.


N:\Bur-Graphics\Projects\2005\141305-1413-036A\GIS\aprs\10501300 Project Alternatives\figure-12-02_route-alternative_map-01.mxd





N:\Bur-Graphics\Projects\2005\1413\036A\GIS\aprs\1050\1300 Project Alternatives\figure-12-03_route-alignment_map-01.mxd





Occurrences of geomorphic and periglacial processes and surficial materials along the access road route were mapped to identify site conditions, natural hazards, and possible aggregate sources to be considered during engineering design and construction. The results of the office-based assessment were field verified by eight walking traverses along selected sections of the route, observations at eleven locations associated with potential bedrock quarry sites and, terrain observations along the road route from a helicopter. In addition, bedrock sampling for geochemical analysis was carried out at a series of possible rock quarry sites. Selected soil samples were collected for geochemical and geotechnical characterisation. Samples of potential borrow and quarry material was collected for initial assessment of acid rock drainage (ARD) potential.

The results of the air photo interpretation, mapping, and sampling program were presented in a report:

- Golder Associates Ltd., Report on Air Photo Interpretation, Site Reconnaissance, Mapping, and Sampling: Tehek Lake Access Road, Meadowbank Gold Project, Nunavut. October 2005.

12.8.1 Test Pitting & Soil Sampling

To assess ground conditions and permafrost depths, 44 hand-dug soil pits were excavated along the proposed route and locations are shown on Figure 12.3. Samples of overburden material were collected from all 44 test pits. A selected number of samples were submitted for additional laboratory testing. Table 12.3 describes the samples collected, and the conditions observed in the field.

The area has low relief, and is generally gently- to moderately- sloping with short, steep slopes occurring locally on some bedrock surfaces. The terrain is dominated by undulating and irregular bedrock surfaces, veneers and blankets of till and/or weathered (frost-shattered) bedrock (felsenmeer), and discontinuous organic veneers. Occasional marine (beach) deposits and very small glaciofluvial deposits are present locally. Periglacial processes present in the area are typical of areas underlain by continuous permafrost, although their surface expression is subdued due to the relatively thin cover of overburden and locally well-drained site conditions. Terrain features and geomorphic processes associated with excess ground ice are limited. Previous field studies in the Baker Lake area and the Meadowbank project site, which included the installation of thermistor cables, indicated that the depth of annual thaw is on the order of 1.5 to 2 m. Shallow, hand-dug soil pits excavated in late July 2005 indicate thaw to depths of 1 m or less on imperfectly- to poorly-drained upland till surfaces at this time of year.

Physical weathering (frost wedging and frost shattering) will occur on exposed bedrock surfaces and in areas of rubbly, weathered bedrock. Freezing induced displacement of soil (frost creep, frost heave, frost jacking, and frost sorting) is expected to occur along the road alignment, although the displacements are likely restricted to poorly-drained surficial materials such as fine-grained glacial tills. Thaw induced displacement of soils (possible solifluction and thaw consolidation/settlement) are expected to occur locally, but are expected to be restricted to the finer, grained soils and to steeper slopes. Thaw settlement and consolidation of finer, grained tills following road construction or surface disturbance should be expected to occur along portions of the road underlain by native till materials.

Table 12.3: Characteristics of Soil Sample Test Pits

Site	Depth (m)	Soil Type	Comments
Soil-1	0-0.4	Brown silt, some clay, gravel and sand	Wet
Soil-2	0-0.3	Light brown silty Sand and Gravel	Dry
Soil-3		Sand, some gravel	No sample
Soil-4		Till	No sample
Soil-5	0-0.3	Grey brown Silt, some clay, fine gravel and sand	No GPS point
Soil-6	0-0.3	Till	
Soil-7	0-0.3	Light brown Silt, some sand, clay and gravel	
Soil-8	0.4-0.6	Grey sandy Silt with gravel	No GPS point
Soil-9	0-0.3	Till	Very stiff and hard to dig
Soil-10	0-0.3	Till	Small holes showing trace of melted ice, soil around the hole is swelling, not able to dig deeper
Soil-11		Till	Dry, no sample
Soil-12		Till	Dry, no sample
Soil-13		Till	Dry, no sample
Soil-14	0-0.5	Light brown sandy Silt, some clay and gravel	Softer in the bottom than Soil-8
Soil-15		Plastic Till	Wet, no sample
Soil-16		Till	Wet, no sample
Soil-17	0-0.35	Till	Drier than others places, no trace of permafrost
Soil-18	0-0.3	Brown silty Sand mixed with weathered rock	Very difficult to dig deeper, too much rocks
Soil-19	0-0.4	Till	Very stiff at the bottom, no trace of permafrost
Soil-20		Dark brown clayey Silt, some sand and gravel	
Soil-21		Till	Permafrost at 0.6-0.7 m
Soil-22	0-0.5	Dark brown clayey Silt, some sand and gravel	Soft at the base of pit, sandier at the surface
Soil-23	0-0.3	Brown Silt, some gravel, trace of sand and clay	No sample, rock at 0.3 m
Soil-24	0-0.7	Wet till	
Soil-25		Sand and Gravel	No sample
Soil-26	0-0.05	Weathered reddish rock	
Soil-27	0.4-0.5	Silty gravel	
Soil-28	0-0.4	Silty sandy Gravel	
Soil-29	0-0.5	Sand and Gravel	
Soil-30	0-0.6	Sand and Gravel	
Soil-31		Sand and Gravel	No sample
Soil-32	0-0.05	Till	Poorly-drained (type 4)
Soil-33	0-0.45	Ablation till	Sand and Gravel, well drained (type 2)
Soil-34	0-0.5	Grey clayey Silt, some sand and gravel	Permafrost at 0.5m
Soil-35	0-0.5	Grey brown Silt, some gravel, clay and sand	
Soil-36	0-0.5	Till	Poorly-drained
Soil-37		Dark brown clayey Silt, some sand and gravel	
Soil-38	0-0.3	Sand, some gravel	Nbn (permafrost classification), below 0.3 cm
Soil-39		Peat	Soft and wet peat over frozen peat, Vx (permafrost), no sample
Soil-40		Sandy till	Seems to have lost the sample
Soil-41		Sand	
Soil-42		Grey clayey Silt, some sand and gravel	
Soil-43	0-0.3	Grey sandy Silt, some gravel	Permafrost at 0.7 m, visible ice, inclusion of ice
Soil-44	0-0.5	Sand and Gravel	Collapsing hole, could not excavate deeper than 0.7 m deep

A geophysical ground penetration radar (GPR) survey has recently been completed along the proposed route by Golder Associates, to evaluate areas of potential snow drifting, snow pack, and to refine the proposed route alignment based on actual site conditions. In addition to the GPR survey, electromagnetic terrain conductivity (EM31) surveys were carried out at specific locations, in particular at potential bridge abutments, to evaluate the potential for massive ice formation.

12.8.2 Summary of Rock Sampling

Sources of granular aggregate are relatively small in spatial extent, and are scarce along the proposed road alignment. It is expected that rock quarries will be developed along the road to provide a source of material for processed aggregates. An initial assessment of some proposed quarry sites has been undertaken to assess the potential for environmental effects associated with the aggregate sources proposed for road construction.

The local bedrock consists of rocks of igneous, metamorphic, volcanic, and sedimentary origin. Individual bedrock types tend to extend over large distances along the road route. Samples were collected from 20 potential quarry sites located along the proposed route. The criteria for selecting potential rock quarry sites were:

1. areas of exposed bedrock ideally 200 x 200 m in extent
2. moderate relief (i.e., 5 m to 10 m or more from bottom to top of outcrop)
3. sites located away from surface waters
4. avoidance of areas that are heavily mineralised
5. avoidance of outcrops with deep, extensive, and open fractures/joints
6. avoidance, if possible, of areas with deeper overburden (>0.5 m)
7. avoidance of lee slopes (S, SSE, and SE) when possible
8. well-spaced sites (5 km to 10 km apart), supplementary and closer site if only small outcrops are available.

Three composite rock samples weighing 3 to 5 kg each were collected at each potential quarry site situated within 1 km on either side of the proposed access road. Quarry sites and sample locations are shown on Figure 12.3. A total of 53 samples were collected from 18 possible quarry sites. Most quarry site outcrops consisted of one relatively homogeneous rock type.

The suite of chemical analyses performed by CEMI includes whole rock and elemental solid phase chemistry, acid-base accounting (ABA) and analysis of metal leaching potential (shake flask extraction). Acid base accounting results were compared to guidelines presented by INAC (1992) for Northern mine sites.

12.8.3 Geology

Table 12.4 summarizes the lithology, sulphides, and iron staining of samples collected from each of the eighteen sample locations.

Table 12.4: Rock Sample Location & Lithology

Station ID	Primary Lithology	Visible Sulphides	Iron Staining	Notes on Texture, Fabric, Weathering
2	Granite	None	None	Medium-grained, fresh to slightly weathered
3	Granite	None	traces on fracture surfaces	Medium-grained, fresh to slightly weathered
4	Granite-Granodiorite	None	None to trace	Fine- to medium-grained, fresh locally up to 0.5 cm weathering rind
5	Granite	None	None to trace on some fractures	Fresh, weakly foliated
7	Granite	None	Traces of iron staining, mostly on fractures	Fresh, fine- to medium-grained, weakly foliated
8	Quartzite	None to very minor	Iron staining on some surfaces	Fresh, fine- to medium-grained, weakly foliated
10	Granite/ Gneiss/ Quartzite	None	None to trace	Fresh, medium-grained
11	Felsite	None	None to trace	Fresh to slightly weathered, fine grained
11B	Andesite	-	-	Moderately weathered, fine-grained
13	Metawacke	None	None to trace	Fresh to slightly weathered, fine-grained
15	Metawacke	None	None to trace	Fresh to slightly weathered
16	Metawacke	Trace	Trace	Slightly weathered
17	Mafic wacke/granite gneiss	None	Trace	Slightly weathered
18	Mafic Volcanic	None	Minor to trace	Slightly weathered
19	Granite	None to trace	None to trace	Fresh to slightly weathered
20	Granite	None	Traces on fracture surfaces	Fresh
21	Granite	None	Trace	Fresh
22	Granite	None	Trace	Fresh, weakly foliated

None of the samples exhibited visible sulphides in greater than trace amounts, and iron staining was generally minor.

Results of whole rock and elemental analyses confirm an abundance of aluminosilicate minerals within the majority of the rock types. Aluminosilicates, such as feldspar and mica, which are typically present in the rock types being studied, provide some amount of acid neutralization potential, although they are less reactive (slower reaction kinetics and lower buffering pH) than carbonate minerals such as calcite or dolomite.

As shown in Table 12.5, ABA results indicate that all samples are non-acid-generating, based on their neutralization potential ratio (NPR above 2 as per INAC (1992) guidelines), or based on their very low sulphide sulphur content.

Rock leachate pH values range from acidic to alkaline. Six of 24 samples are outside of the freshwater CEQG range for pH. The following metals exceed the freshwater CEQG for at least two

samples: aluminum, arsenic, chromium, copper, and selenium. These exceedances do not necessarily imply non-compliance of actual on-site drainage water quality. Concentrations of these constituents are expected to decrease with time, as soluble salts are flushed from the excavated rock.

Table 12.5: Summary of Analytical Results

Station	Sample ID	Rock Type	CCME Exceedances	ARD Potential (INAC, 1992)
2	P2-2	Granite	Al, Cu	NPAG
3	P3-2	Granite	Al, Cu, Se	NPAG
4	P4-2	Granodiorite	Cu, Se	NPAG
5	P5-2	Granite	Al, Cu, Se	NPAG
7	P7-2	Granite	Al, Cu, Se	NPAG
8	P8-2	Quartzite	pH, Cu, Se	NPAG
	P8-3		pH, Al, Cu, Se	NPAG
10	P10-2	Granite / Gneiss / Quartzite	pH, Al, Cu, Se	NPAG
	P10-3		pH, Al, Cu, Se	NPAG
11	P11-2	Felsite	Al, As, Cu, Se	NPAG
	P11-3		Al, Cu, Se	NPAG
11B	P11b-2	Andesite	Al, Cu, Se	NPAG
	P11b-3		Al, As, Cu, Se	NPAG
13	P13-2	Metawacke	Al, Cu, Se	NPAG
15	P15-2	Metawacke	Al, Cu, Se	NPAG
	P15-3		Al, Cu, Se	NPAG
16	P16-2	Metawacke	Cu, Se	NPAG
17	P17-2	Mafic wacke/ Granite gneiss	Cr, Cu, Se	NPAG
	P17-3		Cr, Cu, Se	NPAG
18	P18-2	Mafic Volcanic	Cu, Se	NPAG
19	P19-2	Granite	Se	NPAG
20	P20-2	Granite	pH, Al, Cu, Se	NPAG
21	P21-2	Granite	pH, Al, Cu, Se	NPAG
22	P27-2	Granite	pH, Al, Cu, Se	NPAG

Although quarry sites 8, 10, 21, and 22 have a sulphide content that is expected to be too low to generate ARD, consideration should be given to avoiding these quarry sites as a precautionary measure. The quality of runoff contacting the open quarry sites and the excavated rock should be monitored during construction to document the effect of exposure of the quarry rock on receiving water quality.

12.9 STREAM CROSSINGS

The terrain conditions at the stream crossing locations, as best as can be determined from the air photo interpretation and through field verification, are listed below. The kilometer distances indicated are measured from the Baker Lake marshalling area at Km 0 (see Table 12.6).

Initially 23 stream crossings were estimated, but this number was increased to 25 during the air photo interpretation. However, on further inspection of the air photos, the route alignment was adjusted where possible to reduce the number of stream crossings required to approximately 19.

Table 12.6: Terrain Conditions at Stream Crossings

Stream Crossing			
Number	Terrain Conditions	Notes	km
R01	Unconsolidated materials form both sides of the crossing. Bedrock is exposed a short distance south and north of the crossing. Road construction on the approaches could provide ample rock for crossing construction. Organic veneers and poorly-drained tills are present along the stream edge. The crossing may move closer to the lake if road location to south changes.	Crossing conditions are better closer to the lake as some bedrock is exposed on the north side of the crossing.	3.5
R02/B01	No air photo coverage. Ground photos indicate blocky-rubbly frost shattered bedrock at the crossing.	Bedrock near surface; check grades.	10
R03	Crossing appears to be on poorly-drained till. There is a possibility that the crossing could be located on bedrock a short distance to the west, or this rock could be exploited for crossing materials.	Field verify conditions.	12
R04	Crossing appears to be on poorly-drained till. There is a possibility of locating the crossing on bedrock a short distance to the west. Ground photos indicate organic soils at the crossing location.	Field verify bedrock.	13
R05	There are two possible crossings at this location (east and west of a small lake). Both crossings are on till or weathered bedrock. The east crossing appears better drained, there is a very slight chance there is exposed bedrock on the north side of the east crossing. Rounded/sub-rounded boulders visible in the stream channel in the ground photos suggest that till may underlie the stream/crossing. Poorly-drained tills are present on the approaches to the crossing.	Original (west) crossing location okay – broad and low flows after freshet; no change.	17 to 19
R06/B02	The stream on the eastern side of this crossing location is narrower but the western side appears to have exposed bedrock on both sides of the stream. Frost shattered bedrock is present at the east end of the stream so bedrock may be near surface. Ground photos indicate areas of blocky, rubbly frost shattered bedrock, and possibly gently dipping bedrock locally in the stream channel.	Current location is near west end of stream.	24
R07A	There is bedrock exposed along most of the north side of this crossing but the south side is dominated by till or weathered bedrock. Moving the crossing location west may provide some bedrock for the south approach as well as a narrower crossing.	Check alternative route.	27.5
R07	This is the alternative route location described above.		28

Table 12.6 – Continued

Stream Crossing			
Number	Terrain Conditions	Notes	km
R08	Till or weathered bedrock. The south side of the crossing appears better drained than the north side. Exposed bedrock is available to the south of the crossing. There may areas of frost shattered bedrock on the south side of the crossing that may provide reasonable foundation opportunities.	Not part of the current road route, which uses an alternate high ground alignment to the west of R08.	34
R09	There appear to be bedrock outcrops at this location on the stream that may provide favourable foundation conditions.		54
R10/B03	Primarily unconsolidated materials (till) – poorly-drained till likely dominates. Could exploit exposed bedrock by moving towards west or on green route or to the east.	Crossing excluded from revised route alignment.	63.5
R11	Bedrock is present on the south side of crossing. Mainly unconsolidated materials (till) on north side but may be bedrock locally.	Crossing excluded from revised route alignment.	64
R12	Unconsolidated materials (till) dominate this crossing.	Crossing excluded from revised route alignment.	66
R13	Unconsolidated materials (till) dominate this crossing.		68
R14	Poorly- to imperfectly-drained tills dominate the approaches to this crossing. Rubbly, frost-shattered bedrock is present along the stream.		74
R15/B04	Bedrock and frost shattered bedrock dominate on both sides of this crossing.	Check rock at abutments.	75
R16	Unconsolidated materials (till) dominate both sides of this crossing. Some exposed bedrock may be present a short distance west.	Shift route slightly west.	80
R17	Unknown conditions, no air photo coverage. Ground photo suggests there may be exposed bedrock or frost shattered bedrock to west.	Field verification required, no air photos.	83.5
R18	Unknown conditions – no air photos or ground photos.	Field verification required, no air photos. Two route options available (R18A).	86

Table 12.6 – Continued

Stream Crossing			
Number	Terrain Conditions	Notes	km
R19/B05	Ground photos indicate areas of frost shattered bedrock (angular rock fragments) that would provide a more favourable crossing location. Avoid areas possibly underlain by till (i.e., rounded/sub-rounded boulders in stream). Approaches are dominated by poorly-drained till deposits. Gradients are quite gentle in this area so there may be an opportunity to shorten the route between kilometre 89 and kilometre 87 to reduce road construction across poorly-drained till deposits.	Two route options available (R19A/B05A).	89
R20	Poorly-drained tills (terrain types 4 and 6) dominate this crossing (see photos D-c-1 to D-c-4 on the traverse photos CD). Rock quarry site 19 is about 0.5 kilometres southeast.	Two route options available (R20A).	91.5
R21	Poorly-drained tills are present at the immediate crossing (terrain type 6), areas of blocky to rubbly frost-shattered bedrock and small bedrock outcrops are present on the approaches to the crossing (see photo D-a-1 on the traverse photos CD, the crossing area is on the right hand side of this photo).	Field verification required; shift to green route between R21 and R22.	93.5
R22	Ground photos indicate unconsolidated materials but there may be localised areas of frost shattered bedrock (upstream areas) that could provide more favourable ground conditions for the approaches and the crossing. The air photos indicate opportunities for bedrock approaches on at least one side of the crossing depending on exact route selection.	Crossing excluded from revised route alignment.	98
R23	Rubbly, frost-shattered bedrock is present at the crossing. Areas of poorly- to imperfectly-drained tills are present on the approaches to the crossing.		100
R24	The crossing site is dominated by blocky to rubbly, frost-shattered bedrock limited areas of till may be present in meadow area upstream of crossing (see photos C2-1 and C2-2 on accompanying traverse photos CD).		105
R25	Air photo review indicates that the crossing site is dominated by bedrock outcrops, areas of frost-shattered bedrock and till veneers may be present locally.		109

12.9.1 Stability Discussion

The terrain along the proposed road route does not show any obvious features or processes that preclude the development of the access road, provided appropriate permafrost engineering design methods that account for specific site conditions are used. However, where possible the road should be located on well-drained (dry), granular soils. Sites underlain by fine-grained, poorly-drained, ice-rich, frost-susceptible tills should be avoided where possible, as these soils may require significant ground treatment. There are one or two possible landslides adjacent to the northern portion of the route, but none were observed on the route itself.

Table 12.7 summarizes the susceptibility of various terrain types identified in the mapping to periglacial processes.

Table 12.7: Evaluation of Terrain Susceptibility to Periglacial Processes

Active Layer Process	Description	Susceptibility		
		Low	Moderate	High
Physical weathering of <i>in situ</i> materials	Rockfall or Minor Rock Displacement	Non-bedrock areas	Bedrock areas with slope gradients typically > 60%	Observed rockfall areas
	Frost Shattering	Bedrock areas with slope gradients typically < 60%		
	Frost Wedging	Rubbly gravely beach ridges and veneers (gWrv)		
Freezing-induced displacements of soils	Frost Creep	Felsenmeer (rD _b)	Similar terrain as “High” but no sign of lateral movement	Thick till or organics (M _w , M _b , O _w , O _b)
	Frost Jacking	Bedrock (R)		Terrain showing signs of lateral movement (e.g. solifluction lobes)
	Cryoturbation	Flat, thin till veneers or organic veneers		Patterned ground
Thaw-induced displacements of soils		Rubbly gravely beach ridges and veneers (gWrv)		
	Thaw Settlement	Felsenmeer (rD _b)	Thin till or organics (M _x , M _v , O _x , O _v)	Thick till or organics (M _w , M _b , O _w , O _b)
	Thaw Slumping	Bedrock (R)		Polygons including obvious patterned ground
		Flat, thin till veneers or organic veneers		Settlement, slopes typically <10% gradient
		Rubbly-gravely beach ridges and veneers (gWrv)		Slumping, slopes typically >10% gradient

Some of the identified ground conditions will require conventional cold climate, or permafrost, engineering practices to be used.

Table 12.8 summarizes general engineering and construction methods to consider during the detailed design phase and to be used during the construction phase to manage ground stability in permafrost terrain.

Additional field inspection may be necessary to assess specific, poorly-drained areas (i.e., till deposits), and to assess local variations in permafrost conditions.

Table 12.8: Engineering & Construction Methods Based on Sensitivity to Freeze/Thaw Induced Displacements

Sensitivity to Ground Disturbance	Facility Type	Engineering/Construction Methods Based on Sensitivity to Ground Disturbance
Sensitive to Settlement or Heave	Bridge abutments, heated structures, water retaining structures, fuel storage tanks, machine foundations, and cut slopes. Structures will likely include modular units on grade supported foundations or skids.	<p><i>Appropriate engineering design:</i></p> <ul style="list-style-type: none"> - Excavate ice rich soils - Excavate to bedrock - Use thaw stable fills - Manage drainage - Fill to preserve permafrost - Insulate/Ventilate/Refrigerate - Realign/Relocate if necessary - Flatten cut slopes.
Moderately Sensitive to Settlement or Heave	Ditches, cut slopes, building pads, explosives, and storage pads.	<p><i>Appropriate engineering design:</i></p> <ul style="list-style-type: none"> - Excavate ice rich soils as required, or accept slight increase in annual maintenance associated with controlled subsidence - Use thaw stable fills - Manage drainage - Fill to preserve permafrost - Insulate - Realign/Relocate if necessary.
Insensitive to Settlement or Heave	Site roads, soil stockpiles, and dry freight storage areas.	<p><i>Appropriate engineering design:</i></p> <ul style="list-style-type: none"> - Fill to preserve permafrost - Use thaw stable fills where possible - Annual maintenance - Control drainage - Insulate where possible.

SECTION 13 • REFERENCES

- Golder Associates Ltd., Report on Air photo Interpretation, Site Reconnaissance, Mapping, and Sampling: Tehek Lake Access Road, Meadowbank Gold Project, Nunavut. October, 2005.
- AMEC Mining and Metals Ltd., 2005. Cumberland Resources Ltd. Meadowbank Project Feasibility Study Report, dated 27 June 2005.
- Golder Associates Ltd., Report on Alternative Waste and Water Management Plan, Meadowbank Gold Project, Nunavut 7 March 2005.
- Cumberland Resources Ltd. 2004a. Mine Waste and Water Management, Meadowbank Gold Project, Nunavut. February 2004.
- Golder Associates Ltd., Technical Memorandum on Tailings Dike Cost Reduction Options.26 April 2004.
- Golder Associates Ltd., Report on Field Geotechnical Investigations Baker Lake Site, Meadowbank Project Baker Lake, Nunavut.8 January 2003.
- Golder Associates Ltd., Report on Design of Dikes with Soil-Bentonite Cutoff Wall, Meadowbank Gold Project.23 October 2003.
- Golder Associates Ltd., Report on Meadowbank Gold Project Tailings Dike Basic Engineering Design.13 February 2004.
- Golder Associates Ltd., Report on Thermal Modelling of the Tailings Deposit in the Second Portage Lake, Meadowbank Gold Project.16 February 2004.
- Golder Associates Ltd., Letter on Revised Tailings and Country Rock Management Concept – Meadowbank Project.11 May 1999.
- Golder Associates Ltd., Report on Frozen Tailings Practices Applicability for Meadowbank Gold Project, Near Baker Lake, NWT. October 1997.
- Golder Associates Ltd., Report on Tailings and Waste Management Options, Meadowbank Gold Project, Northwest Territories. March 1999.
- Golder Associates Ltd., Letter on Revised Tailings and Country Rock Management Concept – Meadowbank Project.11 May 1999.
- Golder Associates Ltd., Report on Review of Seepage Cut Off Alternatives Open Pit De-Watering Dikes, Meadowbank Gold Project, Nunavut Territory.9 March 2000.
- Golder Associates Ltd., Letter on Preliminary Geotechnical Scoping Study in Support of Tailings Site Selection – Meadowbank Gold Project.4 September 1998.
- Cumberland Resources Ltd., 2003. Project Description Report, Meadowbank Gold Project, Nunavut, dated March 2003.

APPENDIX A

Tailings Site Selection

I

Golder Associates Ltd.

500 – 4260 Still Creek Drive
Burnaby, British Columbia, Canada V5C 6C6
Telephone (604) 296-4200
Fax (604) 298-5253



REPORT ON

**EVALUATION OF TAILINGS MANAGEMENT
ALTERNATIVES
MEADOWBANK GOLD PROJECT
NUNAVUT**

Submitted to:

Cumberland Resources Ltd.
Suite 950, One Bentall Centre
505 Burrard Street
Vancouver, BC
V7X 1M4

DISTRIBUTION:

- 3 Copies - Cumberland Resources Ltd., Vancouver, BC
- 2 Copies - Golder Associates Ltd., Burnaby, BC

October 6, 2005

05-1413-036A/3000



EXECUTIVE SUMMARY

A series of Technical Meetings were held in Baker Lake on June 2 and 3, 2005 to review the Draft Environmental Impact Statement (DEIS) for Cumberland Resources Limited (CRL), Meadowbank Gold Project. Following the technical meeting, a list of commitments by CRL was prepared, which would either be addressed as soon as possible or appear in the Final Environmental Impact Statement. This report responds to Items #5 and #26 from this list which requested additional information relating to the decision matrix used to evaluate tailings disposal options.

Items #5 and #26 from this list specifically requested that:

- 1) Revised wording for the elimination of options be provided;
- 2) Clarification be provided regarding the decision matrices for the Portage Waste Rock pile and Tailings Impoundment Area (as it relates to the possible effects on all affected fish-bearing lakes) – to be provided to parties as soon as possible;
 - a) The rationale for selecting the various factors, sub-indicators, relative weightings and the ranking of the various options needs to be supported with scientific evidence. The various options need to be clearly described with supporting rationale for each component.

Two reports have been issued previously describing the evaluation process used to select the most appropriate tailings facility:

- Golder Associates Ltd., Report on *Alternative Waste and Water Management Plan, Meadowbank Gold Project, Nunavut*, March 7, 2005.
- Golder Associates Ltd., Report on *Mine Waste and Water Management, Meadowbank Gold Project, Nunavut*, March 5, 2004.

The objectives of those reports was to identify the most appropriate method for disposal of tailings for the Meadowbank Project based on an evaluation of technical, environmental and economic considerations. The requirements are that the facility have minimal net adverse effects on the environment, now and in the future, be technically sound with the minimal potential for failure and economic. Further clarification of the methodology used to select the tailings facility has been requested, and the objective of this document is to provide this clarification.

The process used to select the tailings management system involved:

- Identifying potential tailings storage locations and technologies;
- Developing a list of key site selection criteria that all facilities needed to meet; and
- Developing a site specific, decision matrix model to evaluate, rank, and select the best overall tailings management facility.

This approach, known as a Multiple Accounts Analysis (MAA), is commonly used as a decision making tool for the selection of tailings and waste management facilities. An important aspect of the decision matrix methodology is that it requires all factors be weighed in the final outcome, rather than allowing a single factor to dictate the overall outcome.

The decision matrix model considered factors in three primary categories:

- Environmental;
- Operational; and
- Economic.

Each category was subdivided to consider other sub-indicators. Weighting factors were assigned to each sub-indicator and to the overall factors.

Initially, seven potential tailings management areas were identified. Three of these were excluded from further consideration based on a series of pre-screening criteria. Four potential tailings management areas were carried further for analysis using a decision matrix approach.

Location	Disposal Type
Second Portage Arm	Sub-aerial Paste or Dry Stack
Second Portage Arm	Sub-aerial Slurry
North of Second Portage Arm	Sub-aerial Slurry
North of Second Portage Arm	Sub-aerial Paste or Dry Stack

The sites were evaluated using the decision matrix model.

The results of the decision matrix analysis indicate that the most appropriate tailings management option for the Meadowbank Project, based on environmental, operational, and economic considerations, is the disposal of tailings into the natural rock basin of the northwest arm of Second Portage Lake.

Three sensitivity analyses were carried out. Firstly, each of the individual weighting factors was set to 1, assigning equal weighting to each individual sub-indicator. Secondly, only environmental factors and long term (post-closure) impacts were considered, at the exclusion of operating and economic indicators. Finally, environmental factors specifically relating to impacted lakes and fish habitat were weighted as highly as possible within the decision matrix so that the contribution of these sub-indicators towards on-land disposal options ranged between 31% and 35% of the total environmental score, while the contribution to disposal options in Second Portage Lake were reduced to between 13% and 17% of the overall total score.

The sensitivity analyses showed that when economic factors were removed from consideration, and operational factors reduced in terms of relative importance leaving environmental factors as having the greatest contribution to the overall decision analysis, the preferred option continues to be disposal in the northwest arm of Second Portage Lake, using permafrost encapsulation as the control strategy for acid mine drainage and metal leaching.

A case study of the oxidation of exposed, sub-aerial mine tailings from Rankin Inlet, Nunavut, at sub-zero temperatures is presented. The tailings are acid generating and metal leaching, with saline pore waters. A remediation program begun in 1991 consisted of depositing the tailings into a drained rock basin, with the expectation that permafrost would aggrade into the facility. This is similar to the recommended option for tailings management at the Meadowbank project. A series of thermistors installed in the Rankin Inlet test area indicated that freeze-back of the tailings was occurring more rapidly than predicted. There was no indication of heating by tailings oxidation, despite the reactive nature of the pyrrhotite rich tailings. The results of the laboratory and field investigations indicated that prospective sites for permafrost encapsulation of tailings should have a mean annual air temperature colder than about -6°C. The mean annual air temperature at the Meadowbank Project is -11.3°C. Based on the results presented in the case study, permafrost encapsulation of tailings disposed in a drained rock basin, such as the northwest arm of Second Portage Lake, is a preferred method of disposal in permafrost regions.

TABLE OF CONTENTS

<u>SECTION</u>	<u>PAGE</u>
1.0 INTRODUCTION.....	1
1.1 Physical Setting	2
1.2 Planned Mining Operations	3
1.3 Decision Matrix Models	3
1.4 Meadowbank Tailings Selection Process	3
2.0 MEADOWBANK DECISION MATRIX METHOD OF ANALYSIS.....	6
2.1 Environmental Factors.....	6
2.2 Operational Factors	12
2.3 Economic Factors	16
2.4 Weighting Factors and Scoring	16
3.0 ANALYSIS OF POTENTIAL TAILINGS STORAGE SYSTEMS	20
3.1 Alternative Control Strategies For Mine Waste Disposal At The Meadowbank Project	20
3.2 Tailings Disposal Systems Considered	25
3.3 Description of Tailings Deposition Methods	27
3.4 Description of the Meadowbank Site Potential Tailings Storage Areas.....	30
4.0 RESULTS.....	37
4.1 Base Line Analysis	37
4.2 Sensitivity Analyses	37
4.3 Discussion	46
5.0 CASE STUDY – NORTH RANKIN INLET NICKEL MINE	47
5.1 Summary of Rankin Inlet Remediation Project.....	47
5.2 Thermal Regime in the Tailings at Rankin Inlet.....	48
5.3 Key Conclusions of the Rankin Inlet Studies and Implications for the Meadowbank Project Site	48
6.0 SUMMARY AND CONCLUSIONS	50
7.0 CLOSURE	52
REFERENCES.....	53

LIST OF TABLES

Table 1.1	Peak Horizontal Ground Accelerations for Meadowbank Site
Table 2.1	Environmental Sub-Indicators
Table 2.2	Operational Sub-Indicators
Table 2.3	Tailings Deposition Methods in Arctic or Cold Climates
Table 2.4	Economic Sub-Indicators
Table 2.5	Contribution of the Primary Categories to Weighting Factors Used in the Decision Matrix

Table 2.6	Example of Scoring System used in the Decision Matrix
Table 2.7	Weighting Factors for Sub-Indicators
Table 3.1	Reports Relating to Disposal of Mine Waste in Arctic
Table 3.2	Acid Mine Drainage Control Strategies of the Arctic
Table 3.3	Summary of Potential Tailing Storage Options
Table 3.4	Options Evaluated using the Decision Matrix
Table 3.5	Tailings Site Selection Pre-Screening
Table 4.1	Summary of Baseline Analysis Decision Matrix Results
Table 4.2	Tailings Storage Options – Decision Matrix Results
Table 4.3	Summary of Decision Matrix Results – Sensitivity Analysis (Part 1)
Table 4.4	Sensitivity Analysis Results (Part 1)
Table 4.5	Summary of Decision Matrix Results – Sensitivity Analysis (Part 2)
Table 4.6	Sensitivity Analysis Results (Part 2)
Table 4.7	Summary of Decision Matrix Results – Sensitivity Analysis (Part 3)
Table 4.8	Sensitivity Analysis Results (Part 3)

LIST OF FIGURES

Figure 1	Location Plan Meadowbank Project
Figure 2	General Site Plan
Figure 3	Tailings Storage Options
Figure 4	Geochemical and Physical Processes Potentially Resulting in ARD and ML
Figure 5	Waste Rock Storage Facility Construction Methods
Figure 6	Tailings Thin Layered Freezing Design Concept
Figure 7	Tailings Dam Construction Methods
Figure 8	Tailings Dam and Water Cycle
Figure 9	Above Ground Paste Tailings Deposition Methods
Figure 10	Rankin Inlet Tailings Study Thermal Monitoring
Figure 11	Rankin Inlet Tailings Study Predicted Freeze-Back Time

1.0 INTRODUCTION

Golder Associates Ltd. (Golder) was retained by Cumberland Resources Ltd. (CRL) to identify and select an appropriate tailings storage facility for the Meadowbank Gold Project in Nunavut. The project is located approximately 70 km north of Baker Lake, Nunavut (see Figure 1).

Two reports have been issued previously describing the evaluation process used to select the most appropriate tailings facility:

- Golder Associates Ltd., *Report on Alternative Waste and Water Management Plan, Meadowbank Gold Project, Nunavut*, March 7, 2005.
- Golder Associates Ltd., *Report on Mine Waste and Water Management, Meadowbank Gold Project, Nunavut*, March 5, 2004.

The objectives of those reports was to identify the most appropriate method for disposal of tailings for the Meadowbank Project based on technical, environmental and economic considerations. The requirements are that the facility have minimal net adverse effects on the environment, now and in the future, be technically sound with the minimal potential for failure and economic. Further clarification of the methodology used to select the tailings facility has been requested, and the objective of this document is to provide this clarification.

A Multiple Accounts Analysis (MAA), or decision matrix method of analysis, was used to evaluate tailings disposal alternatives and to select the best tailings storage facility for the Meadowbank Project.

A series of Technical Meetings were held in Baker Lake on June 2 and 3, 2005 to review the Draft Environmental Impact Statement (DEIS) for Cumberland Resources Limited (CRL), Meadowbank Gold Project. During these sessions, the Department of Fisheries and Oceans (DFO) and other stakeholders requested additional clarification regarding the decision matrix method used to select the Tailings Impoundment Area for the project. The following report has been prepared to explain in more detail the evaluation process used to select the tailings storage facility for the proposed Meadowbank Gold Project. The decision matrix used to identify the most appropriate tailings management site based on environmental, engineering, and economic considerations is presented and explained in greater detail. In some cases the weightings and scoring of sub-indicators used to arrive at the final site selection have been modified to reflect on-going refinements to the mine model.

The primary objectives for a tailings storage facility were that the facility would:

- have a low long-term environmental impact;
- provide reliable containment; and
- be operational on a year round basis, during mining operation.

1.1 Physical Setting

The site area consists of low, rolling hills with numerous small lakes. Laterally extensive deposits of glacial till cover the area, with thicknesses typically of 2 m to 4 m. Bedrock consists of a sequence of Archean greenstone (ultramafic and mafic flow sequences) and metasedimentary rocks.

The Meadowbank project is located in an area of low seismicity.

Table 1-1: Peak Horizontal Ground Accelerations for Meadowbank Site

Return Period of Seismic Event (years)	Peak Horizontal Ground Acceleration (g)
100	0.018
200	0.025
475	0.034
975	0.044

Source: Seismic Risk Calculation for Meadowbank Project Site, Geological Survey of Canada, Natural Resources Canada, Sidney, B.C., July, 2003.

The site has vegetation cover interspersed with bedrock outcrops and continuously aggrading surfaces. The vegetation includes; lichens, mosses, shrubs, heaths, grasses and sedges (CRL 2003).

No vital caribou areas or protected wildlife areas have been identified in close proximity to the site (CRL 2003). The area is not regularly used for hunting due to its remoteness from Baker Lake and relatively low abundance of wildlife (CRL 2003).

Water quality in the lakes is excellent. However, the lakes are nutrient poor and are classified as ultra-oligotrophic and hence have low fish productivity (CRL 2003).

The annual average temperature is about -11.3°C, based on site data collected between 1997 and 2004 and an annual precipitation of less than 200 mm (AMEC, 2005). Long-term temperature trends collected over 50 years at Baker lake, when applied to the Meadowbank Project site, suggest a mean annual air temperature of -12.8°C. The depth of permafrost is estimated to range from about 450 m to about 550 m, but varies based on

proximity to lakes. Taliks typically are located beneath bodies of water that exceed 2 m to 2.5 m depth of water. The depth of the active layer ranges from about 1.3 m in areas of shallow overburden, up to 4 m adjacent to lakes.

1.2 Planned Mining Operations

The project consists of several gold bearing deposits within reasonable proximity to one another. Mining of the deposits will primarily be performed as a truck and shovel, open pit operation. Ore is to be transported to a central plant site for processing.

A site plan is shown in Figure 2. The mine plan estimates that 22 million tonnes of ore will be processed over the mine life of approximately 8.4 years. The total volume of settled tailings is estimated to be 15 million cubic metres.

1.3 Decision Matrix Models

Decision matrix types of analyses are also sometimes referred to as Multiple Accounts Analyses (MAA) or alternatives analyses. These types of analyses have been used as site selection tools for tailings facilities and other mining related decision processes including at: Zortman and Landusky Mine Sites, Montana (Shaw *et.al.*, 2001), Red Dog Mine, Alaska (Northern Liner, 2005), and Questa Molybdenum Mine, New Mexico (Molycorp Watch Project). Numerous papers have been published on the subject of Multiple Accounts Analyses such as: Robertson and Shaw (1998 and 1999); Caldwell and Robertson (1983); Vick (1990); Brown (2002); and the Decision Makers Field Guide (2005).

Similar types of analyses are also used in the fields of risk assessment, risk management, selection of the best available technologies or options for environmental remediation projects, resource planning, and sustainable development (Canter, 1985; International Atomic Energy Agency, 2000; CH2MHill, 2004, Robson Valley Land and Resource Management Plan, 1999).

1.4 Meadowbank Tailings Selection Process

The tailings selection process for the Meadowbank project involved three main steps:

- developing a list of key site selection criterion;
- identifying potential tailing storage facilities and deposition methods; and
- developing a decision matrix model to evaluate potential storage facilities.

The site selection process was based on a decision matrix model to assess alternatives.

1.4.1 Initial Site Selection Criterion

A list of initial site selection criterion that any tailings storage facility for the Meadowbank mine site must meet was developed. This list was used as an initial screening tool, and any locations that did not meet these criteria were eliminated from further analysis. The following key site selection criteria were utilized:

- The site was required to have sufficient volume to store planned volume of tailings;
- The site required the potential to provide additional capacity for tailings storage;
- The location would accommodate mine expansion;
- The location is within catchments of the open pits; and
- The site allows control and collection of the tailings supernatant.
- Low potential for failure of the containment facility

1.4.2 Potential Tailing Storage Facilities

Potential tailings storage facilities were identified in the area of the proposed mine site (Figure 3), along with appropriate deposition methods for each location. The tailings facility locations and deposition methods are intimately linked throughout the analyses; in some cases the deposition method can alter the responses to each of the sub-indicators.

All locations and methods that met the initial criterion proceeded to the next phase of analyses which involved the use of the decision matrix.

1.4.3 Meadowbank Decision Matrix Model

The development of the decision matrix model for the Meadowbank Project first involved developing a site specific list of criteria that would be utilized to evaluate and rank the facilities. The criteria covered three main areas:

- environmental factors;
- operational factors; and
- economic factors.

Each of the factors was further subdivided into sub-indicators, in order to evaluate specific aspects. Weightings were assigned to each factor and sub-indicator.

Each tailings facility option was then evaluated based on the sub-indicator and a relative score was assigned. These scores were then multiplied by the weighting factors and summed to give the overall score. The options were then ranked according to the overall score, with the highest score indicating the preferred option.

Quantitative methods were utilized to assign the relative scores where possible, however some sub-indicators necessitated the use of qualitative assessment. Judgement and

perception of the individual conducting the analyses is inevitably a part of any such decision making system, both in the assignment of qualitative scores and of weighting factors.

The weighting factors were specifically designed to place a higher significance on the environmental factors, and less on the operational and economic factors.

Some sub-indicators, such as the potential for the tailings facility to generate acid rock drainage (ARD), were divided into two components: the potential for impact during mine construction and operation, and the potential for long-term impact, after mine closure. In these cases the long-term sub-indicator was generally assigned a higher weighting than the short term operation sub-indicator.

2.0 MEADOWBANK DECISION MATRIX METHOD OF ANALYSIS

This section will explain in greater detail the decision matrix component of the site selection analyses, and each of the sub-indicators used in the selection process, under the three primary categories of environmental, operational, and economic factors. Sub-indicators were chosen to evaluate a wide spectrum of potential impacts, without double counting impacts.

2.1 Environmental Factors

The European Commission published a Report on Best Available Techniques (BAT) reference document for Management of Tailings and Waste-Rock in Mining Activities (2004). This document was developed in response to a Communication from the European Commission COM(2000) 664 [COM(2003) 319 final, 2.6.2003] on the 'Safe Operation of Mining Activities' that was a follow-up action to tailings dam bursts that occurred in Aznalcollar and Baia Mare. The follow-up measures included an elaboration of the BAT Reference Document based on an exchange of information between European Union's Member States and the mining industry. The document was developed in response to the Commission's initiative and in anticipation of the proposed Directive on the management of waste from extractive industries (European Commission, 2004). The following key environmental issues or impacts associated with tailings facilities were listed in this document:

- Site specific issues relating to facility location and relative land take;
- Potential emissions of dust and effluents during operation (to air, land and water) and their impact;
- Potential emissions of dust and effluents after closure (to air, land and water) and their impact;
- ARD and metal leaching generation, release and impact;
- Potential releases due to failures of facilities (i.e., burst or collapses of tailing management facilities); and
- Site rehabilitation and aftercare to minimize environmental impacts.

In accordance with the intention to utilize Best Available Techniques to respect environmental considerations, a list of sub-indicators was developed and used to evaluate the various tailings options. These sub-indicators are presented in the following table and are described briefly in subsequent sections.

Table 2.1: Environmental Sub-Indicators

	Sub-Indicators
Environmental Factors	Sub-catchment area
	Footprint area
	Potential for generating dust during operation
	Potential for generating dust after closure
	Potential for Acid Rock Drainage (ARD) generation during operation
	Potential for ARD generation after closure
	Potential for metal leaching (ML) during operation
	Potential for ML after closure
	Potential for seepage to impact groundwater during operation
	Potential for seepage to impact groundwater after closure
	Potential for geotechnical hazards ¹
	Lake area impacted
	Number of lakes impacted
	Visual impact
	Impact on fish and fish habitat

Note:

¹ Includes consideration of foundation conditions, impact of seismicity, and height of structure.

2.1.1 Sub-Catchment Area

A catchment is an area of land bounded by natural high points (hills, ridges and mountains). Surface water (rainfall and runoff) flows down through the catchment area and into one low point (a creek, river or bay). Catchment areas may be further divided into sub-catchments; typically each sub-catchment area will have homogeneous physical characteristics.

Sub-catchment area for the purpose of this evaluation was defined as the primary portion of the watershed that would be impacted by the deposited tailings. The total sub-catchment area (hectares) was used to assign the relative scores and determine the impact of each option. Options having lower sub-catchment areas are preferable to those with greater areas, and hence were assigned a relatively higher score.

2.1.2 Footprint Area

The footprint area of the tailings storage facility is defined as the area covered by the deposited tailings both on land and in water. The total footprint area, in hectares, was used to assign the relative scores and judge the impact of each facility location. The site having the smallest footprint area was given the highest relative score, and the other options were assigned a lower score, relative to their footprint area.

2.1.3 Potential for Generating Dust During Operations

The relative potential for each facility and tailings deposition method to generate dust during mine operation was qualitatively judged and a value of low, moderate, or high was assigned. This factor is dependent on the method of tailings deposition selected and the relative exposure of the site to wind. In assessing this indicator, a tailings site having the lowest topographic profile, or within an area of low topographic relief, would have a high relative value assigned representing a more desirable site. A site having high topographic profile, and located in an area exposed to wind, would be assigned a low relative value, representing a less desirable site.

At the Meadowbank Project site, the prevailing wind direction is from the northwest, averaging about 20 km/h to 30 km/h. The maximum daily wind gust recorded at the Meadowbank climate station was 83 km/h. A tailings facility located on-land and substantially exposed above ground would have the potential for on-going dust generation during operations and during closure. The dispersion of dust could potentially result in deposition in lakes and on land down wind of the source. A facility located topographically as low as possible would be preferable in that the potential for on-going dust generation and down-wind dispersion over water and land would be reduced.

2.1.4 Potential for Generating Dust After Closure

The relative potential for each facility to generate dust after closure was qualitatively judged and a value of low, moderate, or high was assigned. This factor is dependent on the planned method for closure, grain size of cover material, including methods of erosion protection, topographic profile, and exposure of the site to wind. A facility that as part of the closure plan is to be covered, thus reducing or eliminating the potential for dust, either by a rock, soil or vegetative cap, or underwater, would have a high relative value assigned. A facility that remained exposed after mine closure would have a low value assigned.

2.1.5 Potential for Acid Rock Drainage (ARD) Generation During Operation

Geochemical testing has shown that tailings at Meadowbank contain metal sulphides and will have the potential to generate ARD. The relative potential for each facility to generate ARD during mine operation was qualitatively judged and a value of low, moderate, or high was assigned. This factor is primarily dependent on the method of tailings deposition and the planned method of operation that may minimize the generation of ARD.

Sulphides oxidize when exposed to oxygen and air, which in turn creates an acidic metal-laden leachate and can be generated over a prolonged period of time if acid buffering minerals are not present. The rate of generation of ARD is accelerated with fine particles as the surface area potentially exposed to oxygen is much greater, which is typically the case when dealing with tailings and processed mine waste. Other factors that may increase the rate of ARD generation are: high oxygen concentration, high temperature, low pH, and bacterial activity (European Commission, 2004).

Tailings deposition methods that reduce or prevent the generation of ARD would receive a higher score. For example, methods that reduce or eliminate exposure to oxygen, such as through the use of submerged tailings facilities, or permafrost encapsulation would receive a higher relative score, in comparison to facilities where tailings are exposed to oxygen (i.e., aerial). Alternatively, facilities that mix acid generating tailings with buffering agents would receive a higher score in comparison to the same facility with insufficient buffering agents. Facilities that maintain tailings at low temperatures and in a frozen state through permafrost encapsulation would receive a high score.

2.1.6 Potential for ARD Generation After Closure

The relative potential for each facility to generate ARD after closure was qualitatively judged and a value of low, moderate, or high was assigned. This factor is primarily dependent on the method of tailings deposition, and the planned method for closure which may reduce or control generation of ARD. As discussed in the previous subsection, facilities that in the long term control factors that lead to acid generation, would receive a relatively higher score in comparison to facilities that do not control these factors. Deposition and maintenance of a submerged facility, a lined and dry facility, or a permafrost encapsulated facility would receive higher scores, in comparison to above ground facilities exposed to air and precipitation.

2.1.7 Potential for Metal Leaching (ML) Generation During Operation

Geochemical testing has shown that tailings generated at Meadowbank will have the potential to generate ML. The impact of metals released into the environment may be toxic, but depends on many factors including: concentration, pH, temperature, and water hardness (European Commission, 2004). Figure 4 schematically shows some of the primary geochemical and physical processes and their interaction that may lead to the generation of ARD and the potential release of metals (ML).

The relative potential for each facility to generate ML during mine operation was qualitatively judged and a value of low, moderate, or high was assigned. This factor is primarily dependent on the method of tailings deposition and the planned method of operation that may minimize the generation of ML. Facilities that reduce or eliminate the generation and/or transmission of soluble metals to the environment (i.e., hydraulic containment) would receive a high relative score, in comparison to facilities that do not control metal leaching.

Metals may leach from tailings irrespective of the pH, therefore controlling the flux of water through and out of the tailings facility may have the most significant impact on reducing the release of constituents. Consequently, management strategies that limit infiltration of water into the tailings facility, and limit the ability for tailings to come into contact with natural water sources such as groundwater, surface water, and precipitation, through the use of permafrost encapsulation, low permeability cover systems, containment berms and diversion ditches, are preferable.

2.1.8 Potential for ML Generation After Closure

The relative potential for each facility to generate ML after closure was qualitatively judged and a value of low, moderate, or high was assigned. This factor is primarily dependent on the method of tailings deposition, and the planned method for closure which may reduce or control generation and migration of ML. The evaluation of this sub-indicator is the same as discussed in the previous subsection.

2.1.9 Potential for Seepage to Impact Groundwater During Operation

The relative potential for seepage from each facility to impact groundwater resources during operation was qualitatively judged and a value of low, moderate, or high was assigned. This factor is primarily dependent on the method of tailings deposition, the planned method of operation, including any steps that will be taken to control groundwater discharges, and groundwater flow paths and flow rates of the site (i.e., groundwater discharge or recharge area). Facilities that produce low rates of seepage and seepage with low levels of contamination would receive a high relative score in comparison to facilities that are expected to generate high quantities of seepage with a high concentration of contaminants (including metals and low pH).

One method of reducing the potential for groundwater impact may be achieved by controlling the flux of water through the facility. During operation flow through the facility may be controlled by the surrounding berms and liner or low permeability boundary. Facility liners may be man-made or natural, such as low permeability rock, till, clay, permafrost, or synthetic materials (i.e., high density polyethylene). Materials such as sands and gravels, or highly fractured rock are highly conductive and would not reduce the flux through the facility.

At the Meadowbank Project site, the hydraulic conductivity of the bedrock is on the order of 10^{-8} m/s, while that of the overburden materials is on the order of 10^{-6} to 10^{-5} m/s. Consequently, a naturally contained basin facility underlain by bedrock would be preferable to an engineered facility underlain by till.

2.1.10 Potential for Seepage to Impact Groundwater After Closure

The relative potential for seepage from each facility to impact groundwater resources after closure was qualitatively judged and a value of low, moderate, or high was assigned. This factor is primarily dependent on the method of tailings deposition, planned methods to control groundwater discharges, and the planned closure method, as discussed in the previous section. Facilities that generate low rates of seepage and seepage with low levels of contamination would receive a high relative score in comparison to facilities that are expected to generate high quantities of seepage with higher concentration of contaminants.

2.1.11 Potential for Geotechnical Hazards

The relative potential for geotechnical hazards to exist at each facility was qualitatively judged and a value of low, moderate or high was assigned. The assessment considered foundation conditions, seismic activity, and height and type of structure. Tailings facilities may be constructed using very high dams, and very long perimeter dykes. These may contain large quantities of mobile tailings that can be released to the environment if the retaining structures fail either through the man-made perimeter dikes and dams, or failure through the foundation materials due to low strength.

If the tailings are deposited on-land, within a storage facility, the facility will require the construction of several kilometers of dikes. The dikes will be engineered structures constructed with processed materials. The performance and stability of these structures will depend on the foundation conditions, foundation preparation, fill materials, and quality of the construction. Experience at the site have shown that the till materials can be problematic to construct with, having high moisture content and low strength. Consequently, there is a higher inherent risk associated with failure of an engineered structure constructed on weak soils. This risk increases with the length of the structure.

It is desirable from an environmental perspective to minimize the reliance on engineered structures.

Facilities constructed at higher relative elevations will have a greater relative potential energy compared with facilities constructed at lower elevations. Consequently, there is a greater risk associated with facilities at higher elevations as a breach and release of tailings from these facilities will move to an elevation having a lower potential energy. Such a failure could result in the release of tailings to the environment. If the site was located directly upslope of a fish bearing lake then there is the potential for damage to fish stocks not only in that lake but also to downstream habitat and fish stocks. The use of natural depressions at lower relative elevations considerably reduces the reliance on engineered structures, and hence the geotechnical and environmental risks associated with these structures.

2.1.12 Lake Area and Habitat Quality Impacted

The expected quality (i.e., low, medium, high) of lake area impacted by each of the tailings facilities (tailings deposition and reclaim water) was determined and was used to assign the relative scores and judge the impact of each facility location. The facility with the lowest relative quantity of high quality habitat area impacted would receive a higher score, relative to a facility that impacts a greater amount of high value habitat area. Because of the greater relative importance of this metric, a weighting factor was applied.

2.1.13 Number of Lakes Impacted

The number of lakes that each option would impact was tallied and used to assign the relative scores for this sub-indicator. A facility that impacted only one lake would receive a higher score in comparison to a facility that impacted three lakes.

2.1.14 Visual Impact

The relative visual impact for each facility was qualitatively judged and a value of low, moderate, or high was assigned. This factor considered such items as height, shape, and contrast with the surrounding terrain. A facility with a low profile and that would blend in with the surrounding area would receive a higher relative score than a facility with a high topographic relief, that did not blend into the surrounding terrain.

2.2 Operational Factors

Table 2.2 presents a list of the sub-indicators that were used to evaluate the operational factors for the tailings options under consideration. The following subsections briefly describe each of these sub-indicators and how they were evaluated.

Table 2.2: Operational Sub-Indicators

	Sub-Indicators
Operational Factors	Ease of operation
	Distance from mill
	Potential for delays due to freezing
	Construction risk
	Disposal system has precedent in arctic environment

2.2.1 Ease of Operation

The relative ease of operation of each facility was qualitatively judged and a value of low, moderate, or high was assigned. Various factors were considered including such items as: number of personnel, energy requirements, and mechanical components. For example, a gravity drain system may be judged as being easier to operate than a system that required three pumping stations. In this case the gravity system would receive a relatively higher score than the alternative system. Another example would be a facility that requires multiple tailings discharge locations may be less desirable than a facility with a single discharge point, especially considering the Arctic climate.

2.2.2 Distance from Mill

The nominal distance from the mill to the proposed tailings discharge location was determined. This value was used to assign a relative score for each tailings facility based on the proximity to the mill. The facility closest to the mill would receive the highest relative score, and the facility located furthest from the mill would receive the lowest relative score. Increased distance results in higher pumping power requirements, higher risk of pipe blockage either due to freezing or sanding, and increased pipe maintenance. It is also recognized that reduced distance from the mill allows more frequent inspections and facilitates maintenance.

2.2.3 Potential for Delays due to Freezing

The relative potential for delays to be caused due to freezing that would impact mining processing operations was qualitatively judged and a value of low, moderate, or high was assigned. This considered various factors including; deposition method, tailings transport method, and ability to operate a reclaim pond. Facilities that were judged as being more susceptible to freezing that could then cause delays within other portions of the plant received a relatively low score, whereas facilities that were less subject to freezing received a relatively high score.

For example a facility that required multiple pumping stations or a longer pipeline for transport of tailings and reclaim water would likely be more susceptible to freezing and therefore cause delays than a system that required only one pump, and transport length was shorter.

2.2.4 Construction Risk

The relative potential for delays or problems to occur during construction was qualitatively judged and a value of low, moderate, or high was assigned. Various factors including: type of construction, likely construction schedule, and site conditions, were taken into account. Facilities that utilized local materials that can be placed on a year round basis received a higher score. In comparison, facilities that required a large number of components to be imported, and that could only be delivered by ship and during summer months when the port is open and free of ice, received a lower score.

2.2.5 Disposal System has Precedent in Arctic Environment

The relative precedent for use of each of the proposed tailings deposition methods was qualitatively judged based on the evaluators' experience and published literature, and a value of low, moderate, or high was assigned. Facilities that have been successfully built and operated in arctic climates received relatively higher scores than facilities that have not been built or rarely built in arctic climates. A list of various tailings management systems used in Arctic or cold climate regions are shown in Table 2.3. The list is not comprehensive but is intended to provide the reader with additional background as to which management strategies are commonly used in the north.

Table 2-3
Tailings Deposition Methods in Arctic or Cold Climates

Mine Name	Owner	Location	Tailings Disposal Method	Notes
Ruttan Mine	Hudson's Bay Mine & Smelting	Northern Manitoba	Sub-aqueous slurry	- initial deposition in lake until filled - under construction, to be completed in late 2005 - into a lake with dams - planned - initially in on land containment facility now in mined out flooded pit - in open pit with a drainage layer surrounding tailings (wall and base)
Thompson Mine	Inco	Manitoba	Sub-aqueous slurry	
Nanisivik Mine	Breakwater Resources Ltd	Nunavut	Sub-aqueous slurry	
Red Dog Mine	Teck Cominco	Alaska	Sub-aqueous slurry	
Voisey's Bay	Inco	Newfoundland (Labrador)	Sub-aqueous slurry	
Colomac Mine	Comaplex Minerals Corp.	Northwest Territories	Sub-aqueous slurry and sub-aerial slurry	
Doris North Project	Miramar Hope Bay Ltd.	Nunavut	Sub-aqueous slurry	
Key Lake	Cameco	Northern Saskatchewan	Sub-aqueous slurry	
Rabitt Lake	Cameco	Northern Saskatchewan	Sub-aerial slurry, will be sub-aqueous at closure	
Copper Cliff Mine	Inco	Sudbury	Sub-aerial slurry	- Thickened to 60-65% deposited from center in a cone - later stage deposition in cells above lake - permafrost encapsulation - in dammed valley, closure will be: sub-aqueous using engineered wetlands as remediation, permafrost encapsulation - deposited in cells, saturated final cover, and paste for underground backfill, permafrost encapsulation
FlinFlon	Hudson's Bay Mine & Smelting	Northern Manitoba	Sub-aerial slurry	
Kidd Creek Mine	Falconbridge (Falconbridge-Noranda)	Timmins	Sub-aerial slurry	
Nanisivik Mine	Breakwater Resources Ltd.	Nunavut	Sub-aerial slurry	
Fort Knox and True North	Kinross Gold Corporation	Alaska	Sub-aerial slurry	
Rankin Inlet	Asamera Minerals Inc.	Nunavut	Sub-aerial slurry in pit	
Lupin Mine	Echo Bay Mines Ltd.	Nunavut	Sub-aerial slurry	
Ekati Mine	BHP	Northwest Territories	Thickened tailings (50%) - sub aerial and sub-aqueous	- in dammed lake with lake level raised - non acidic generating
Polaris Mine	Teck Cominco (formerly Cominco)	Cornwallis Island, Nunavut	Thickened tailings	- deposition in lake
Greens Creek Mine	Hecla Mining Company	Alaska	Sub-aerial dry stack	- permafrost encapsulation - Tailings are filtered to recover excess water as well as residual cyanide and metal credits - final permitting and construction - in the planning stages
Raglan Mine	Falconbridge (Falconbridge-Noranda)	Quebec	Sub-aerial dry stack	
La Coipa	Mantos de Oro (Placer Dome)	Chile	Sub-aerial dry stack	
Pogo Gold Mine	Teck Cominco and Sumitomo Metal Mining	Alaska	Sub-aerial dry stack in valley impoundment and underground paste backfill	
Mineral Hill Mine	Triako Resources Limited	Montana	Sub-aerial dry stack	
Met Site, Kidd Creek Mine	Falconbridge (Falconbridge-Noranda)	Timmins	Sub-aerial paste (thickened)	- radius of the conical pile is 1.2km and the height of the cone is 25m. The height of the cone increases by 0.2m/y and by closure the height is expected to be 29m
Colstrip power plant	LLC, Portland General Electric Company, Puget Sound Energy, PacifiCorp, AVISTA Corporation and NorthWestern Energy LLC	Montana	Sub-aerial paste	- for fly ash disposal
Snap Lake	De Beers Canada	Northwest Territories	Sub-aerial paste and paste backfill underground	- non acidic generating are placed on land
Kubaka Mine	Omolon Mining Company (operators facility is a joint venture)	Russia	Tailings facility as consisting of two levels; Partially dry tailings in the upper level, and lower level holding the liquid tailings	- permafrost as containment
Colomac Mine	N.W.T.	Northwest Territories	Sub-aqueous slurry	final closure final closure inactive
Illinois Creek	Quest Capital Corp.	Alaska	Tailings slurry	
Ryan Lode	Bartholome	Alaska	Lined earthen Dam with reclaimed water system	
Nixon Fork	St. Andrews Goldfields LTD	Alaska	Lined earthen Dam with reclaimed water system	
Julietta	Bema	Russia Far east	Paste tailings 85-90% soilds in to surface facility	
Kumtor	Cameco, Kyrgyz Govt	Kyrgyzstan	Sub- aerial	- under constrction
Con	Miramar	Yellowkife	Sub aerial	
Giant	Diand (formerly Royal Oak)	Yellowkife	Sub aerial	
Pogo	Teck Cominco (formerly Cominco)	Alaska	Dry Stack	
Kemess	Northgate	BC	De-watered slurry	
Huckleberry	Imperial Metals Corporation	BC	De-watered slurry	
Mount Polley	Imperial Metals Corp.	BC	Tailings slurry	
Diavik	DDMI, Rio Tino	NWT	Fine Pk as sub-aerial slurry into HDPE and coletanche bitumenous lined containment, coarse pk trucked moist and dumped (stacked) in till lined containment	
Snap lake	Debeers	NWT	Paste tailings on surface into cells	

2.3 Economic Factors

The economic factors influencing each of the tailings options were considered. The following table presents the sub-indicators that were used to evaluate the economic factors for the tailings options under consideration based on an assessment of the present value of costs.

Table 2.4: Economic Sub-Indicators

Economic Factors	Sub-Indicator
	Total present value of costs (initial costs + delayed costs)

Previously, (Golder, 2004) two sub-indicators, overall present value cost and initial capital costs, were considered in the evaluation of the economic factors. This has been revised to consider only the total present value cost as a sub-indicator of economic factors. This reduces the influence of economic factors on the results of the decision making process.

The total present value costs for each facility were estimated and used to rank the facilities. This value includes initial construction costs, facility operational costs over the ten-year mine life, and closure costs. An 8% interest rate was used for these calculations. The resulting total costs were then ranked and scored, with the lowest cost allocated the highest score.

2.4 Weighting Factors and Scoring

The contributions of the three primary categories were assigned weightings so that the overall contribution of the primary categories to the outcome of the decision matrix was as follows.

Table 2.5: Contribution of the Primary Categories to Weighting Factors Used in the Decision Matrix

Primary Category	Contribution to Overall Weighting ¹
Environmental	55%
Operational	33%
Economic	12%

2.4.1 Scale Factor

In order to separate the best alternatives from the worst, a scaling, or scoring factor was applied (S_{IND}). Each sub-indicator was assigned a score between 1 and 9 points, similar to the system described by Robertson and Shaw (1999). The scores provide a relative ranking between the options with the 'best' option receiving a score of 9, and the 'worst' a score of 1. All subsequent options were then compared to the 'best' option and assigned a lower relative score.

An example of the scoring method is presented in Table 2.6.

Table 2.6: Example of Scoring System used in the Decision Matrix

Option	Distance to Mill	Points	Notes
A	1 km	9	9 points awarded for the facility located closest to the mill (BEST)
		8	
		7	
		6	
C	2 km	5	9 points x 1 km (BEST)/2 km = 5 points
		4	
B	3 km	3	9 points x 1 km (BEST)/3 km = 3 points
		2	
		1	

2.4.2 Relative Weighting Factor

Each sub-indicator of the primary categories was assigned a relative weighting factor (W_{IND}) to introduce a value bias between the individual sub-indicators, based on the relative subjective importance of one indicator versus another. A higher weighting factor indicates a perceived greater relative value or importance between sub-indicators. For example, the relative importance of the impact of a disposal on fish and fish habitat is considered greater than the visual impact of the facility. Consequently, the sub-indicator of fish and fish habitat has been given a relative weighting factor that is four-and-a-half times greater than the weighting factor for visual impact. The weighting factors are shown below in Table 2.7.

Calculations

The cumulative score for each of the primary categories was determined as the sum of the products of the sub-indicator weightings and relative scores.

$$OptionScore = \sum (W_{IND} \times S_{IND})_{Environment} + \sum (W_{IND} \times S_{IND})_{Operations+} + \sum (W_{IND} \times S_{IND})_{Economic}$$

The resulting option score based on qualitative and quantitative inputs provides a means to evaluate the relative ranking of the various options considered. The method is transparent, and allows stakeholders the opportunity to assess the relative weightings and scaling factors based on personal preference. A significant aspect of the decision matrix methodology is that it requires all factors be weighed in the final decision, rather than allowing a single factor to dictate the overall outcome.

The following table presents the weighting factors for the sub-indicators in each of the primary categories as well as the maximum possible value and maximum possible score that could potentially be achieved.

Table 2.7: Weighting Factors for Sub-Indicators

Factor	Sub-Indicator	Relative Weighting	Max, Possible Score	Max. Possible Weighted Score¹	Max. Possible Category Score¹
Environmental	Sub-catchment area	1	9	9	603
	Footprint area	1	9	9	
	Potential for generating dust during operation	6	9	54	
	Potential for generating dust after closure	4	9	36	
	Potential for Acid Rock Drainage (ARD) generation during operation	5	9	45	
	Potential for ARD generation after closure	7	9	63	
	Potential for metal leaching (ML) during operation	2	9	18	
	Potential for ML after closure	5	9	45	
	Potential for seepage to impact groundwater during operation	5	9	45	
	Potential for seepage to impact groundwater after closure	6	9	54	
	Potential for geotechnical hazards ²	5	9	45	
	Lake area impacted	5	9	45	
	Number of lakes impacted	4	9	36	
	Visual impact	2	9	18	
	Relative loss of high value fish habitat	9	9	81	
Operational	Ease of operation	9	9	81	351
	Distance from mill	8	9	72	
	Potential for delays due to freezing	10	9	90	
	Construction risk	4	9	36	
	Disposal system has precedent in arctic	8	9	72	
Economic	Total present value of costs (initial cost + delayed costs)	15	9	135	135
TOTAL					1089

Notes:

¹ Values represent the maximum score, if each sub-indicator assigned a maximum scoring factor of 9 points.

² Includes consideration of foundation conditions, impact of seismicity, and height of structure.

3.0 ANALYSIS OF POTENTIAL TAILINGS STORAGE SYSTEMS

3.1 Alternative Control Strategies For Mine Waste Disposal At The Meadowbank Project

The generation of metal leachate in acidic drainage is a concern for mining projects. In evaluating the potential control strategies for the disposal of the mine waste at the Meadowbank Project, consideration was given to control strategies that are effective in cold regions. Many reports have been prepared that relate to the disposal of mine waste in cold regions. Under the Mine Environment Neutral Drainage (MEND) program some relevant reports are:

Table 3.1: Reports Relating to Disposal of Mine Waste in Arctic

MEND Project	Title	Year
6.1	Preventing AMD by Disposing of Reactive Tailings in Permafrost	1993
1.61.1	Roles of Ice, in the Water Cover Option, and Permafrost in Controlling Acid Generation from Sulphide Tailings	1996
1.61.2	Acid Mine Drainage in Permafrost Regions: Issues, Control Strategies and Research Requirements	1996
1.61.3	Column Leaching Characteristics of Cullaton Lake B and Shear (S) – Zones Tailings Phase 2: Cold Temperature Leaching	1997
1.62.2	Acid Mine Drainage Behaviour in Low Temperature Regimes – Thermal Properties of Tailings	1998
W.014	Managing Mine Wastes in Permafrost Zones, Summary Notes MEND Workshop	1997
5.4.2d	MEND Manual, Volume 4 – Prevention and Control, Chapter 4.8 Permafrost and Freezing	2001
1.61.4	Covers for Reactive Tailings Located in Permafrost	2004

Common control strategies for the prevention or reduction of acid mine drainage are:

1. Control of acid generating reactions;
2. Control of migration of contaminants; and,
3. Collection and treatment.

In assessing the overall control strategies for the Meadowbank Project, an emphasis has been placed on methods that satisfy items 1 and 2 in the above list, which then has an impact on item 3, collection and treatment, by potentially reducing the requirements for these activities.

Dawson and Morin (MEND 1.61.2, 1996) list various acid mine drainage control strategies.

Table 3.2: Acid Mine Drainage Control Strategies of the Arctic

Strategy	Tailings	Waste Rock
Freeze Controlled	<ul style="list-style-type: none"> • Total or perimeter freezing options can be considered • Can freeze up to greater than 15 m annually if freezing in thin layers • Process chemicals could cause high unfrozen water contents 	<ul style="list-style-type: none"> • Requires considerable volumes of non-acid waste rock for insulation protection • Better understanding of air and water transport through waste rock required for reliable design
Climate Controlled	<ul style="list-style-type: none"> • May not be a reliable strategy for saturated tailings 	<ul style="list-style-type: none"> • Requires control of convective air flow through waste rock, infiltration control with modest measures and temperature controls • Better understanding of waste rock air, water, and heat transport for reliable design
Engineered Cover	<ul style="list-style-type: none"> • Special consideration for freeze-thaw effects • Availability and cost of cover materials are major impediments 	
Subaqueous Disposal	<ul style="list-style-type: none"> • Special considerations for winter ice conditions and pipeline freeze-up 	<ul style="list-style-type: none"> • Very difficult to dispose of waste rock beneath winter ice
Collection and Treatment	<ul style="list-style-type: none"> • Costly to maintain at remote locations • Long term maintenance cost 	
Segregation and Blending	<ul style="list-style-type: none"> • Tailings are normally geochemically homogeneous 	<ul style="list-style-type: none"> • May be very effective • Research and development on-going

Reference: (MEND 1.61.2, 1996)

The Meadowbank Project is located within the zone of continuous permafrost, and has a mean annual air temperature of about -11.3 degrees C. The project area is underlain by permafrost to depths between 450 m and 550 m based on thermal data collected from the site since 1996.

Freeze Control Strategies: Freeze control strategies rely on the immobilization of pore fluids to control acid mine drainage reactions, and the potential migration of contaminated porewater outside of the impoundment area. The climate conditions at the Meadowbank Project site are amenable to freeze control strategies, and hence should be taken advantage of. In addition to immobilization of pore fluids, permafrost can reduce the hydraulic conductivity of materials by several orders of magnitude. Consequently, freeze control strategies are effective methods for preventing the migration of

contaminants through materials. At the Meadowbank Project, the hydraulic conductivity of the bedrock is already low, on the order of 10^{-8} m/s. The implementation of a freeze control strategy would result in even lower hydraulic conductivities if tailings were disposed of within a bedrock basin. According to Dawson and Morin, above, freeze control strategies for waste rock dumps can only be effective if sufficient quantities of non-acid generating waste rock are available for use as a cover and insulation protection. Based on the production forecast schedule for the Meadowbank Project, there will be sufficient ultramafic rock, which is not only non-acid generating, but also acid neutralizing with a buffering capacity up to 5 times greater than the other rock types at the project. Consequently, a freeze control strategy for the waste rock dumps in the Portage area, using ultramafic rock as a cover and insulating layer, is a preferred alternative.

Climate Control Strategies: Cold temperatures reduce the rate at which oxidation occurs. The low net precipitation in permafrost regions limits infiltration of water into waste rock and tailings disposal areas. Consequently, the climate of the Meadowbank Project area will act as a natural buffer to the production of acid mine drainage and metal leachate. According to Dawson and Morin (1996) these strategies are best applied to materials placed at a low moisture content to reduce the need for additional controls on seepage and infiltration. Consequently, this strategy is considered to be effective for waste rock, but not tailings. The arid climate at the Meadowbank Project is therefore ideally suited for climate control strategies for use with the waste rock piles.

Engineered Covers: In general, the objectives of engineered covers are to minimize infiltration of water into the disposal facility, and to create a physical barrier to the diffusion of oxygen into the facility, either waste rock or tailings. In temperate climates, dry covers consist of a layer of fine grained material between two coarse grained layers. In permafrost regions, freeze-thaw cracking due to annual freeze-thaw processes is a concern, resulting in damage to the cover layers and a reduction in the effectiveness of the barrier system. Consequently, materials having a low susceptibility to freeze-thaw damage are desirable. At the Meadowbank Project there is a substantial shortage of thaw-stable soils. Consequently, the development of an appropriate cover design using natural materials available at the site would require significant processing to achieve the requirements for the cover materials. Alternatives to natural materials are manufactured materials, such as geosynthetics or geomembranes. However the costs associated with transporting these materials to site, and the construction of the man-made cover system, are prohibitive.

Subaqueous Disposal Strategies: In temperate regions, the disposal of waste rock and tailings beneath a water cover is a suitable method for disposal as this inhibits the ability of sulphides within the waste materials, either tailings or waste rock, to oxidize. In permafrost regions, additional considerations include the ability to dispose of tailings and waste rock under ice during the ice covered water period of the project. At the Meadowbank Project, ice on the lakes can continue in to July. Consequently, the free-ice

period for subaqueous disposal strategies would be limited to a time period of about 3 months. It is notable however, that mines such as Polaris have successfully operated underwater tailings disposal.

Blending and Segregation: Blending and segregation of waste materials consists of combining acidic and alkaline materials to achieve a net neutral waste product producing non-acidic leachate. This approach requires substantial quantities of non-acid generating waste rock to blend with the acid generating rock. At the Meadowbank Project, there are sufficient quantities of non-acid generating waste rock such that this strategy appears desirable. However, in comparison with a total freeze control strategy, there does not appear to be any significant advantage to this method. Furthermore, this type of approach would likely require substantial planning, stockpiling, and re-handling of material; more so than for the freeze control alternative.

3.1.1 Summary

A review of control strategies for mine waste disposal, both waste rock and tailings, in cold regions has been presented. The following lists aspects of the project that must be considered in selecting an overall waste management philosophy:

- The Meadowbank Project site is located in the zone of continuous ‘dry’ permafrost;
- The permafrost is classified as ‘dry’, having ice content of less than 10% based on regional permafrost classification maps;
- The permafrost is continuous, with permafrost up to 450 m to 550 m deep based on thermal data collected from the site;
- The mean annual air temperature at the site is about -11.3 degrees C;
- The project site is considered to be arid and dry, with mean annual precipitation on the order of about 290 mm (rainfall and estimated snowfall);
- There is a shortage of naturally occurring thaw-stable materials at the site;
- Most of the waste rock that will be produced during mining is potentially acid generating;
- However, there are sufficient quantities of acid-neutralizing ultramafic waste rock material at the site for use as a cover of waste rock piles and tailings; and
- All of the tailings are acid generating and metal leaching.

Based on the summary of conditions at the site, the following strategies for waste management are appropriate from a technical perspective.

Waste Rock Disposal Alternatives

Waste rock should be disposed of on-land using a total freezing control strategy, followed by a convective insulating cover of acid-neutralizing waste rock. The waste rock will freeze with time, encapsulating the potentially acid generating waste material within

permafrost. The waste rock could be placed in a heaped dump construction in lifts of about 2 to 3 m to allow freezing during placement. The cover material would be coarse to allow the development of convective cooling during winter, and insulation through trapped air within voids during the summer. Given the high evaporation rate and low annual average precipitation at the site, the average annual infiltration into the pile is expected to be low. Freeze and climate control strategies for potentially acid generating rock are shown on Figure 5.

Tailings Disposal Alternatives

Due to the arid climate and permafrost environment, tailings should be disposed of in a manner that encourages total freezing as a control strategy. Subaerial disposal is preferred, given the length of time that water at the site is ice covered, allowing the tailings to be frozen in thin layers rather than one thick layer in order to maximize the total frozen thickness. This can be accomplished through the use of slurry pipelines. The tailings will eventually become encapsulated by permafrost, thus limiting oxygen diffusion and water infiltration into the pile, thereby limiting the generation of acid mine drainage. This is shown conceptually on Figure 6.

If disposed of on-land a system of containment dikes would need to be constructed. The dike system would contribute to perimeter freezing of the tailings pile. However, there are insufficient quantities of natural materials available to construct such a dike system. Ideally, disposal of the tailings into a rock basin within permafrost would be the most suitable control strategy. Freezing of the tailings pile would then occur during deposition of the thin layers into the basin, and from the perimeter of the basin which would already be frozen. The hydraulic conductivity of the thawed bedrock at the site is on the order of 10^{-8} m/s. Permafrost can reduce the hydraulic conductivity of a material by as much as several orders of magnitude. Consequently, an additional advantage to disposal within a naturally occurring bedrock basin followed by total freezing is that the ability for constituents to migrate out of the facility is substantially restricted. The use of the naturally occurring bedrock and permafrost as the control mechanism to inhibit the onset of acid mine drainage, to restrict the potential release of constituents to the environment, and to restrict infiltration into the pile is preferred over other alternatives that rely on the construction of kilometres of engineered dikes constructed with man made and processed materials, such as clay liner systems, which have hydraulic conductivities that are higher than the bedrock in the Meadowbank Project area. Furthermore, the use of engineered structures carries with it an inherent risk of failure. It is therefore desirable to minimize the reliance on engineered structures.

Capping of the tailings storage facility would consist of the placement of a coarse convective insulating layer of ultramafic rock over the facility to a minimum depth of about 2 m. This thickness is consistent with other cover designs over reactive tailings in the north. During winter convective heat transfer developed within the coarse cover

material will transfer heat out of the tailings pile; during the summer trapped air within the voids will act as insulation. This will limit the depth of annual thaw penetration to within the acid-neutralizing ultramafic waste rock. During detailed design, a detailed cover design will be developed that will consider the addition of a fine grained layer of soil material as a base layer to the coarse rock cover. This layer would retain moisture within it resulting in a reduction in the thickness of the active layer. It is possible that this layer could consist of till material dozed in a thin layer over the tailings facility. There are sufficient quantities of till material that will be produced during pre-mining and pre-stripping that could be stockpiled and used for this purpose.

3.2 Tailings Disposal Systems Considered

Initially seven potential tailings storage sites were identified. These are listed in Table 3.3 along with the disposal methodology for each site, and are shown on Figure 3.

Table 3.3: Summary of Potential Tailing Storage Options

Option	Location	Disposal Type
A	Second Portage Arm and North Portage Pit	Sub-aqueous Slurry
B	Second Portage Arm	Sub-aerial Paste or Dry Stack
C	Second Portage Arm	Sub-aerial Slurry
D	Third Portage Lake	Sub-aqueous Slurry
E	East from Vault Haul Road	Sub-aerial Slurry
F	North of Second Portage Arm	Sub-aerial Slurry
G	North of Second Portage Arm	Sub-aerial Paste or Dry Stack

These options were then compared to the site selection criteria (described in Section 1.4), as a pre-screening process, prior to conducting the overall decision matrix analysis. Based on the pre-screening assessment, only four of the initial seven options met the site selection criteria. These are shown in Table 3.4. Options B and C require draining of the northwest arm of Second Portage Lake. Options F and G are on land. Note that all options require that the northwest arm of Second Portage Lake be diked and nearly completely drained. The full pre-screening matrix is shown in Table 3.5.

Table 3.4: Options Evaluated Using the Decision Matrix

Option	Location	Disposal Type
B	Second Portage Arm	Sub-aerial Paste or Dry Stack
C	Second Portage Arm	Sub-aerial Slurry
F	North of Second Portage Arm	Sub-aerial Slurry
G	North of Second Portage Arm	Sub-aerial Paste or Dry Stack

Table 3.5: Tailings Site Selection Pre-Screening

		Option A	Option B	Option C	Option D	Option E	Option F	Option G
		2nd Portage Arm and North Portage Pit	Second Portage Arm	Second Portage Arm	Third Portage Lake	East of Second Portage Arm	North of Second Portage Arm	North of Second Portage Arm
		Sub-aqueous slurry	Sub-aerial Paste or Dry Stack	Sub-aerial Slurry	Sub-aerial Slurry	Sub-aerial Slurry	Sub-aerial Slurry	Sub-aerial Paste or Dry Stack
		Construction – Dewater Second Portage Arm by 28 m (El. 105m ASL) to allow construction of dike. Construct and maintain pipeline.	Construction - Dewater Second Portage Arm by 38 m (El. 95m ASL) and allow base to freeze. Build water management pond near mill or in 3rd Portage Arm. Construct and maintain pipeline.	Construction - Dewater Second Portage Arm by 28 m (El. 105m ASL) to allow construction of dike. Construct and maintain pipeline.	Construction – Place silt curtain to control sediment dispersion or other sediment control and install and maintain pipeline.	Construction – build conventional tailings containment berms on frozen ground; install and maintain pipeline.	Construction – build conventional tailings containment berms on frozen ground; install and maintain pipeline.	Construction – build minor containment berms on frozen ground; install and maintain pipeline.
		Operation - Place tailings in Second Portage Arm until Year 6, then North Portage Pit. Use water above tailings for reclaim. Transport tailings by pipeline.	Operation - Place thickened/paste tailings to 4 to 7 m above current lake level such that tailings freeze each year. Transport tailings by pipeline for paste, or by truck for thickened.	Operation - Place slurry to 7 m above current lake level. Maintain water management and reclaim pond at west end of lake. Transport tailings by pipeline.	Operation – deposit tailings into 3rd Portage Lake. Reclaim from Second Portage Arm (water management pond) and 3rd Portage Lake. Transport tailings by pipeline.	Operation - Place tailings slurry on surface. Use Second Portage Arm for water management, plus reclaim from tailings area. Allow tailings to freeze each year. Transport tailings by pipeline.	Operation - Place tailings slurry on surface. Use Second Portage Arm for water management and reclaim water, plus reclaim from tailings area. Allow tailings to freeze each year. Transport tailings by pipeline.	Operation - Place thickened/paste tailings on surface. Use Second Portage Arm or Third Portage Arm for water management and reclaim water. Allow tailings to freeze each year. Transport paste tailings by pipeline, or truck thickened tailings.
Key Indicators	Sub-Indicators	Closure – Submerged tailings: Tailings remain submerged and thawed. Long term metal leaching potential.	Closure – Permafrost encapsulation: Place ultramafic capping layer to maintain tailings frozen below active layer and to shed water.	Closure – Permafrost encapsulation: Place ultramafic capping layer to maintain tailings frozen below active layer and to shed water.	Closure – Submerged tailings: Tailings remain submerged and thawed. Long term metal leaching potential.	Closure – Permafrost encapsulation: Place ultramafic capping layer to maintain tailings frozen below active layer and to shed water.	Closure – Permafrost encapsulation: Place ultramafic capping layer to maintain tailings frozen below active layer and to shed water.	Closure – Permafrost encapsulation: Place ultramafic capping layer to maintain tailings frozen below active layer and to shed water.
Site Selection Criteria	Sufficient volume to store planned volume of tailings	Yes	Yes	Yes	Yes	Yes	Yes	Yes
	Potential for increased capacity	No	Yes	Yes	Yes	Yes	Yes	Yes
	Location enables mine expansion	No	Yes	Yes	Yes	Yes	Yes	Yes
	Impoundment is within catchment of open pits	Yes	Yes	Yes	No	No	Yes	Yes
	Allows control/collection of supernatant	Yes	Yes	Yes	No	Yes	Yes	Yes
	Potential candidate for tailings storage facility	No	Yes	Yes	No	No	Yes	Yes

3.3 Description of Tailings Deposition Methods

The tailings deposition methods considered for use at the Meadowbank Project are:

- Sub-aqueous Slurry;
- Sub-aerial Slurry;
- Sub-aerial Dry Stack; and
- Sub-aerial Paste.

The following subsections provide a brief summary of each of these technologies.

3.3.1 Sub-Aqueous Slurry

This method of tailings deposition, involves the direct placement of tailings slurry into a body of water. The water body may consist of a natural lake, river, or other body of water, within an on-land flooded containment facility, or within a flooded pit. This type of tailings deposition method is commonly used in combination with wet ore mineral processing techniques. Slurries typically have solids contents between 20% and 40%, but may range between 5% and 50%. Tailings slurries are typically transported in pipelines or open channels to the containment area. Slurries may be deposited from a single point or multiple locations.

Sub-aqueous deposition implies that all tailings are deposited under water. This is primarily used when tailings have a high potential to produce ARD or severe dust problems. After slurry deposition, solids settle out and the supernatant water can then be decanted and recycled for use within the plant.

Engineered containment structures are built to control the area over which tailings are placed. These structures may consist of dykes or dams, and may be constructed using upstream, downstream or center line construction methods (Figure 7). Figure 8 shows a typical tailings dam structure and the associated water cycle (European Commission, 2004).

As part of this type of tailings management facility, diversion structures are commonly constructed to redirect natural surface water away from the tailings storage facility.

The following are examples of mines that use this type of tailings deposition: Hudson's Bay Ruttan Mine, Manitoba; Inco's Thompson Mine, Manitoba; Nanisivik Mine (initial deposition), Nunavut; Polaris Mine Nunavut ; and the Red Dog Mine, Alaska.

3.3.2 Sub-Aerial Slurry

Sub-aerial slurry deposition is generally the same as the sub-aqueous method of tailings deposition, but in this case the tailings are not all deposited under water. In general, the resulting density of the tailings when a sub-aerial method of deposition is used is greater than when sub-aqueous methods are used as settlement of the deposit is promoted through drainage and evaporation from the tailings beach.

Additional thickening techniques, often using chemical additives, may be employed to increase the solids content above 50% (typically 50% – 60%), thus improving storage efficiency.

Water within this type of facility may also be decanted and recycled for use within the plant.

As part of this type of tailings management facility, diversion structures are commonly constructed to redirect natural surface water away from the tailings storage facility.

The following are examples of mines that use this type of tailings deposition: Inco's Copper Cliff Mine, Ontario; Hudson's Bay Flin Flon, Manitoba; Kidd Creek Mine, Ontario; and Nanisivik Mine (later stage), Nunavut.

3.3.3 Sub-Aerial Dry Stack

An alternative to slurry type tailings deposition systems is called "dry stack". This method uses mechanical devices, such as high capacity vacuum and pressure belt filters, to dewater the tailings. The resulting tailings have about 50% to 70% solids, and are not able to be pumped. Instead they are transported by truck or conveyor system. It is important to note that these tailings are not truly "dry", but rather have moisture contents several percentage points below saturation.

Typically, these tailings are then placed, spread, and compacted to form an unsaturated, dense and stable mound. No additional containment structures are required such as dykes or dams.

This type of facility may be advantageous if the mine is:

- Located in an arid regions, where water conservation is a driving factor, and where subsequent saturation by precipitation is not an issue;
- Located in a high seismic area;
- In a region where water handling is difficult; and
- Limited by available space for disposal of tailings.

These facilities may result in a smaller footprint area due to their increased density; however, a secondary facility for re-circulation of water may still be required.

The nature of the tailings produced, both the grain size and mineralogy, can play an important role in determining the effectiveness of filter processing. Tailings with a high percentage of clay-sized particles and also clay mineralogy may negate the effectiveness of a filtering system.

These facilities still may require surface water runoff and seepage management systems. Ditches to redirect non-contact water away from the facility and ditches to collect runoff from the stack are utilized. Additionally, methods to collect seepage and prevent groundwater contamination may be required. A series of under drains, groundwater cut-off walls, or liners may be used. A closure cover is required to prevent erosion, prevent dust generation, and to provide an appropriate media for re-vegetation. Potentially acid generating tailings may require an infiltration barrier to reduce ARD generation.

Examples of dry stack tailings facilities are: Greens Creek Mine, Alaska; Raglan, Quebec; and La Coipa, Chile (Davies and Rice, 2001; Brown, 2002). Additional facilities are being considered or planned at: Pogo Gold Mine, Alaska; Las Cruces, Spain; and Mineral Hill, Montana.

3.3.4 Sub-Aerial Paste

Paste tailings have to be thickened using chemical additives, or a combination of mechanical devices and chemical additives, such as hydrating agents (i.e., Portland cement, fly ash), creating a slurry that will not separate. Pastes typically consist of approximately 60% solids for fine grained tailings and up to 80% solids for coarse tailings.

Paste tailings are frequently used for backfilling underground mines; however, surface disposal of paste tailings is also possible. Above ground use of paste technology, still requires the use of containment facilities, although due to the increased density of the tailings and lower moisture content, the size and/or height of the facilities may be reduced compared to other slurry type methods of disposal. Paste tailings can be transported using high pressure pipelines to the storage area. Two methods for deposition of paste tailings are shown in Figure 9.

These facilities require surface water runoff and seepage management systems. Ditches to redirect non-contact water way from the facility and ditches to collect runoff from the stack are utilized.

A secondary facility for re-circulation of water may still be required.

The following are examples of mines that use the paste method technology for tailings deposition: Bulyanhulu, Tanzania; Myra Falls, on Vancouver Island; and Kidd Creek Mine, Timmons, Ontario. The Colstrip power plant in Montana also utilizes this technology for fly ash disposal.

3.4 Description of the Meadowbank Site Potential Tailings Storage Areas

Based on the initial screening criteria, two potential tailings storage areas were identified:

- Storage within Second Portage Arm (Option B and Option C); and
- On land storage north of Second Portage Arm (Option F and Option G).

The locations of these two areas are shown on Figure 3. The following sections briefly describe these two areas and the ancillary components and structures for each of the Options that were evaluated.

3.4.1 Storage Within Second Portage Arm (Option B and Option C)

Option B

Option B is to dispose of the tailings as a Sub-aerial Paste or Dry Stack in the natural rock basin of the northwest arm of Second Portage Lake. This will require dewatering of this portion of the lake. As part of mine construction, a dike and haul road will be constructed across the east end of this portion of the lake to facilitate dewatering and mining of the Portage Deposit. The dike will isolate the northwest arm of Second Portage Lake from the remaining portion. The water level within the arm of Second Portage Lake would be lowered by 38 m (elevation 95 m asl). Once de-watered, the rock basin would freeze. Once the base was frozen, then thickened tailings (“dry stack”) or paste tailings would be transported, by truck (if dry stack method was selected) or by pipeline (if paste technology was utilized), and placed in lifts, such that each lift would freeze. The tailings stack at closure would be frozen and permafrost would eventually penetrate further into the base of the storage facility.

A separate water reclaim pond would be required, and would likely be constructed just to the west of the proposed plant site in a small basin of Third Portage Lake (sometimes referred to as Third Portage Arm). This small basin of Third Portage Lake would be isolated from the remaining portion of the lake by constructing small dikes. At the end of the mine life, the water quality within this basin would be monitored, and if it met water quality guidelines, the basin would be re-connected to the remainder of Third Portage Lake by removal of the dike system.

The tailings facility within the northwest arm of Second Portage Lake would be progressively reclaimed during operations by covering with a layer of relatively inert capping material. The cover would be designed to contain the depth of annual thaw within the relatively benign capping material so that the entire tailings mass would remain encapsulated by permafrost. Advantages to the Option B method of tailings storage include the following:

- The option is inherently more stable than the other alternatives that place tailings on land, or at a higher 'potential energy'. Option B utilizes a natural depression with the tailings placed in a "dry" form.
- Regardless of where tailings are stored, the northwest arm of Second Portage Lake will be impacted by mine activities due to the construction of a series of de-watering dikes to allow mining of the ore. Consequently, this option takes advantage of a necessary requirement for the mining process to proceed, avoiding the need to construct a specific on-land disposal area which would result in a greater area of impact by the mine.
- The option is located immediately downstream from the proposed Portage Waste Rock Storage Facility. Runoff from the waste rock can be collected and managed within the facility if necessary.
- Freezing of the tailings and the talik beneath Second Portage Lake will limit the potential for ARD and ML generation and migration of contaminants into the surrounding environment (groundwater and surface water).
- Second Portage Lake is currently a regional discharge point for deep groundwater flow. The hydraulic gradient will continue to be towards the lake once the lake level has been drawn down to allow mining. This will reduce the potential for contaminant migration into the surrounding environment. The potential for contaminant release is further reduced by the low hydraulic conductivity of the surrounding bedrock.
- The surface of the facility is low relative to the surrounding topography, and relative to an equivalent facility that might be constructed on land. Consequently, the potential for the generation of dust from the tailings during operations and closure is less than for an equivalent on-land facility. Furthermore, capping of the tailings will reduce the potential for post-closure dust generation and also help ensure that tailings remain in a frozen state, year round.
- The facility will be located close to the plant site and other mine facilities which will make it easier to operate and will reduce the risk of operational problems.

Disadvantages to Option B method of tailings storage include the following:

- There is a greater potential for ARD generation during operation as tailings will be exposed to oxygen and therefore have the potential for sulfide oxidation.
- The northwest arm of Second Portage Lake will permanently contain tailings.

Option C

Option C is to dispose of tailings by sub-aerial deposition in the natural rock basin of the northwest arm of Second Portage Lake, and would involve partial dewatering. The East Dike and haul road that will be constructed across the east end of this portion of the lake to permit dewatering and mining of the Portage Deposit and to provide road access to the plant site, as previously discussed, will isolate the northwest arm from the remaining portion of the lake. For Option C, the water level upstream will be lowered by 28 m (elevation 105 m asl) to permit tailings dike construction. Once the tailings dike has been constructed, slurried tailings would be transported by a pipeline and deposited within the tailings facility. The tailings and talik beneath the northwest arm of the lake will eventually freeze. The facility would be progressively reclaimed during operations by covering with a layer of relatively inert capping material. The cover would be designed to contain the depth of annual thaw within the relatively benign capping material so that the entire tailings mass would remain encapsulated by permafrost. Advantages to the Option C method of tailings storage include:

- The option is inherently more stable than other alternatives that place tailings on land, or at a higher 'potential energy' as it utilizes the natural depression of Second Portage Lake.
- Regardless of where tailings are stored, the northwest arm of Second Portage Lake will be impacted by mine activities due to the construction of a series of de-watering dikes to allow mining of the ore. Consequently, this option takes advantage of a necessary requirement for the mining process to proceed, avoiding the need to construct a specific on-land disposal area which would result in a greater area of impact by the mine.
- The option is located immediately downstream from the proposed Portage Waste Rock Storage Facility. Runoff from the waste rock can be collected and managed within the facility.
- Freezing of the tailings and the talik beneath Second Portage Lake will reduce the potential for ARD and ML generation and migration of contaminants into the surrounding environment (groundwater and surface water).
- Second Portage Lake is currently a regional discharge point for deep groundwater flow. The hydraulic gradient will continue to be towards the lake once the lake level has been drawn down to allow mining. This will reduce the potential for contaminant migration into the surrounding environment.
- The surface of the facility is low relative to the surrounding topography, and relative to an equivalent facility that might be constructed on land. Consequently, the potential for the generation of dust from the tailings during operations and closure is less than for an equivalent on-land facility. Furthermore, capping of the tailings will reduce the potential for post-closure dust generation and also help ensure that tailings remain in a frozen state, year round.

- The facility will be located close to the plant site and other mine facilities which will make it easier to operate and will reduce the risk of operational problems.
- This method of tailings management has been used at numerous locations both in temperate and cold climates.

Disadvantages to the Option C method of tailings storage include:

- Higher potential for ML during operation as tailings will be submerged and therefore have the potential for leaching and release of metals. However, leaching and release of metals will be contained within the storage facility.
- The northwest arm of Second Portage Lake will permanently contain tailings.

3.4.2 Storage North of Second Portage Arm (Option F and Option G)

Option F

Option F is to dispose of tailings slurry sub-aerially on land, north of Second Portage Lake. There are several small ponds and drainage channels in this area. However, the aquatic habitat studies (CRL 2005a, and CRL 2005b) have indicated that these ponds do not contain fish and are not considered suitable fish habitat due to their shallow depth and the typical thickness of ice that forms on the lakes during the winter months.

Option F would require the construction of conventional tailings containment berms on frozen ground in a permafrost region that contains soft compressible soils including peat and an active layer that is variable, all of which provide challenges to designing and constructing a geotechnically stable containment system. A geomembrane liner system would likely need to be installed on the tailings (upstream) side of the containment berms, and keyed into the permafrost. There are insufficient natural materials suitable for use as a liner. The berms would require additional quarrying of rock material which would create greater land disturbance. It is likely that the additional rock material for construction of the embankment berms would require the development of a separate quarry from the mining activities. Material from mining operations has been identified as potentially acid generating, and the current mine plan takes this into consideration when defining where the material will be stored in specific waste storage facilities, and how the waste will be managed in the long term to minimize impacts on environment. Furthermore, the current plan optimizes the use of waste from pre-mining activities in the construction of the de-watering dikes, and specifically places potentially acid generating material under water where possible. There would be insufficient quantities of material produced during pre-mining activities to be used for the construction of the extensive embankment system that would be required for on-land storage. In addition to this, based on the current understanding of the geochemistry of the materials produced from pre-mining activities, these would not be suitable for construction of the berms as they would

be continually exposed to an oxidizing environment in the thaw layer, and would be flushed annually during spring freshet, and during rain storm events. The run-off from the embankment system would need to be collected, managed, and treated unless an alternative quarry site of geochemically benign material could be identified and exploited for the construction of the berms.

Once the embankments were constructed slurried tailings would be transported in a pipeline and deposited within the berms. Eventually, the tailings would freeze and the tailings would be encapsulated by permafrost. A capping system consisting of geochemically benign materials would need to be designed to limit infiltration of water into the tailings, and to restrict the annual thaw depth within this layer.

The dike and haul road that will be constructed across the east end of the northwest arm of Second Portage Lake to permit dewatering and mining of the Portage Deposit, will isolate the northwest arm from the remaining portion of the lake. For Option F, the northwest arm of Second Portage Lake would be used for water management and tailings reclaim water and this basin would likely be permanently be lost for fish habitat. A dike would need to be constructed in the area of the currently proposed tailings dike for water management purposes. Tailings reclaim water would also be stored and re-circulated from the tailings facility. Once mine operations were finished, the water contained within the northwest arm of Second Portage Lake would need to be treated. Once the treated water meets guideline requirements, the dike would be removed, reconnecting the northwest arm of Second Portage Lake with the rest of the lake.

Advantages to Option F method of tailings storage include:

- The northwest arm of Second Portage Lake may only be isolated from the remaining portion of the lake during the operational phase of the mine. Depending on the water quality at the completion of mine operation, it may be possible for the northwest arm to be re-connected with the remainder of the lake.
- Freezing of the tailings and the underlying soil layer will reduce the potential for ARD and ML generation and migration of contaminants into the surrounding environment.
- Capping of the tailings will reduce the potential for post-closure dust generation and will shed water, thus limiting infiltration into the facility.
- This method of tailings management has been used in both temperate and cold climates.

Disadvantages to Option F method of tailings storage include:

- A substantial system of containment berms will need to be constructed on poor soil foundation conditions. Consequently, there is an elevated risk of failure of the

foundations, and hence the containment berms. The containment facility would be constructed immediately up-slope of the northwest arm of Second Portage Lake. A failure of the containment berms could potentially result in the introduction of tailings into Second Portage Lake. The introduction of tailings into the lake could result in the development of a silt plume which could conceivably impact on the entire lake, although this would be a relatively short term impact.

- There is a higher potential for dust generation during operation and closure, due to the higher relief. Wind erosion of the tailings surface during operations and during closure could result in the transportation and deposition of tailings over considerable distances down-wind of the facility.
- It is likely that a separate quarry source of non-PAG rock will need to be developed to produce the materials required to construct the embankment berms. There are insufficient quantities of rock available from pre-mining activities to construct the perimeter de-watering dikes as well as embankment berms. The rock from the pre-mining activities is unsuitable for use as construction material for the scale of facility that would be required to enclose the tailings due to its potential for acid generation. If there were sufficient material available from pre-mining activities for this use then a substantial water collection and treatment system would need to be constructed to collect run-off from the embankment berms.
- There is a higher potential for generating acidic drainage and leaching metals during operation as the tailings will be in a partially saturated state, and exposed to oxygen.
- The tailings facility will have greater visibility.
- The system would require a geomembrane liner or similar seepage cutoff system on the upstream face of the embankment berms, keyed into the permafrost.
- The mine footprint (area of disturbance) would be increased substantially.
- Native sediments in the northwest basin of Second Portage Lake may become metals contaminated due to prolonged contact with mine tailings reclaim water, which could pose a source of metals to the receiving environment for a prolonged period after re-flooding.

Option G

Option G is to dispose of thickened (“dry”) or paste tailings sub-aerially on land, north of Second Portage Lake. There are several small lakes or ponds and streams in this area. However, the aquatic habitat studies (CRL 2005a, and CRL 2005b) have indicated that these ponds do not contain fish and are not considered suitable fish habitat due to their shallow depth and the typical thickness of ice that forms on the lakes during the winter months.

The development of the site would involve constructing minor embankment berms and diversion ditches on frozen ground. Once the berms were constructed, tailings would be transported by truck (if dry stack method was selected) or by pipeline (if paste technology was utilized), and placed or deposited in lifts within the berms. Tailings would

eventually freeze. A capping system consisting of geochemically benign materials would need to be designed to limit infiltration of water into the tailings, and to restrict the annual thaw depth within this layer.

As with Option F, the northwest arm of Second Portage Lake would be de-watered, and a water containment dike would be constructed along the western edge of the proposed Portage Pit. The purpose of the dike would be to allow the management of site water and tailings reclaim water within the arm of Second Portage Lake. As an alternative to the use of the arm of Second Portage Lake for water management, the arm of Third Portage Lake, immediately to the west of the mill and mine site process plant, could be isolated by the construction of dikes, and then used to manage site and tailings reclaim water.

Advantages to Option G method of tailings storage include:

- The northwest arm of Second Portage Lake may only be isolated from the remaining portion of the lake during the operational phase of the mine. Depending on the water quality at the completion of mine operation, it may be possible for the northwest arm to be re-connected with the remainder of the lake.
- The height of containment dikes will be less than for Option F.
- Freezing of the tailings and the underlying soil layer will reduce the potential for ARD and ML generation and migration of contaminants into the surrounding environment.
- Capping of the tailings will reduce the potential for post-closure dust generation and will shed water, thus limiting infiltration into the facility.

Disadvantages to Option G method of tailings storage include:

- There is a higher potential for dust generation during operation and closure, due to the higher relief. Wind erosion of the tailings surface during operations and during closure could result in the transportation and deposition of tailings over considerable distances down-wind of the facility.
- There is a high potential for the generation of acidic run-off during operation as tailings will be only partially saturated state, thus exposed to oxygen enabling sulfide oxidation to occur.
- The tailings facility will be more readily visible.
- Long containment berms will need to be constructed on poor soil foundation conditions. These berms will be less than those required for Option F, however an inherent risk of failure remains and therefore the risk of releasing tailings to the environment.
- Native sediments in the northwest basin of Second Portage Lake may become metals contaminated due to prolonged contact with mine tailings reclaim water, which could pose a source of metals to the receiving environment for a prolonged period after re-flooding.

4.0 RESULTS

4.1 Base Line Analysis

Tailings facility Options B, C, F, and G for the proposed Meadowbank Project were analyzed using the decision matrix method of analysis described above. The following table summarizes the results.

Table 4.1: Summary of Baseline Analysis Decision Matrix Results

Factor	Options			
	B	C	F	G
	Second Portage Arm	Second Portage Arm	West of Waste Rock Storage	West of Waste Rock Storage
	Sub-aerial Paste	Sub-aqueous/ Sub-aerial Slurry	Sub-aerial Slurry	Sub-aerial Paste
Environmental	438	475	372	432
Operational	263	216	160	256
Economic	60	135	75	60
TOTAL	761	826	607	748

Table 4.2 presents the full results of the decision matrix for the tailings storage options. The individual scores for each sub-indicator are shown along with the summed scores for environmental factors, operational factors, and economic factors.

Based on the decision matrix method Option C, tailings slurry disposal in the northwest arm of Second Portage Arm, is the best tailings management strategy for the Meadowbank Project site based on an evaluation that included environmental, operational, and economic considerations.

4.2 Sensitivity Analyses

The relative sensitivity of the decision matrix system and resulting selection to changes in the weighting factors was evaluated. Firstly, each of the individual weighting factors was set to 1. This assigns an equal weighting to each individual sub-indicator. The results of this analysis are presented and described in the following section. Secondly, only environmental factors and long term (post-closure) impacts were considered. This analysis excluded the influence of operating and economic impacts from the decision matrix. Finally, environmental factors specifically relating to lake and fish habitat impacts were weighted as highly as possible within the decision matrix so that the contribution of these sub-indicators towards on-land disposal options ranged between 31% and 35% of the total score, while the contribution to disposal options in Second Portage Lake were reduced to between 13% and 17% of the overall total.

TABLE 4.2: TAILINGS STORAGE OPTIONS DECISION MATRIX RESULTS				Option B	Option C	Option F	Option G	Scale Factor				Sub-Indicator Weighted Scores			
				Second Portage Arm	Second Portage Arm	North of Second Portage Arm	North of Second Portage Arm	B	C	F	G	B	C	F	G
				Sub-aerial Paste or Dry Stack	Sub-aerial Slurry	Sub-aerial Slurry	Sub-aerial Paste or Dry Stack								
				Construction - Dewater Second Portage Arm by 38 m (El. 95m ASL) and allow base to freeze. Build water management pond near mill or in 3rd Portage Arm. Construct and maintain pipeline.	Construction - Dewater Second Portage Arm by 28 m (El. 105m ASL) to allow construction of dike. Construct and maintain pipeline.	Construction - build conventional tailings containment berms on frozen ground; install and maintain pipeline.	Construction - build minor containment berms on frozen ground; install and maintain pipeline.								
				Operation - Place thickened/paste tailings to 4 to 7 m above current lake level such that tailings freeze each year. Transport tailings by pipeline for paste, or by truck for thickened.	Operation - Place slurry to 7 m above current lake level. Maintain water management and reclaim pond at west end of lake. Transport tailings by pipeline.	Operation - Place tailings slurry on surface. Use Second Portage Arm for water management and reclaim water, plus reclaim from tailings area. Allow tailings to freeze each year. Transport tailings by pipeline.	Operation - Place thickened/paste tailings on surface. Use Second Portage Arm or Third Portage Arm for water management and reclaim water. Allow tailings to freeze each year. Transport paste tailings by pipeline, or truck thickened tailings.								
Key Indicators	Sub-Indicators	Relative Weighting Factor	Maximum Possible Score	Closure - Permafrost encapsulation. Place ultramafic capping layer to maintain tailings frozen below active layer and to shed water.	Closure - Permafrost encapsulation. Place ultramafic capping layer to maintain tailings frozen below active layer and to shed water.	Closure - Permafrost encapsulation. Place ultramafic capping layer to maintain tailings frozen below active layer and to shed water.	Closure - Permafrost encapsulation. Place ultramafic capping layer to maintain tailings frozen below active layer and to shed water.								
Key Details	Dike construction volumes required (m³)			1,140,000	1,140,000	1,250,000	250,000								
	Capping volume, assuming 2 m thickness (m3)			3,000,000	3,000,000	2,280,000	2,280,000								
	Length of tailings pipeline (m)			2,600	2,800	4,100	4,100								
	Length of reclaim pipeline (m)			800	2,800	1,200	1,000								
	Location of water pond			Near mill or 3rd Portage Arm	2nd Portage Arm	2nd Portage Arm and tailings	2nd or 3rd Portage Arm								
Environmental Factors (55% of Weighted Total)	Sub-catchment area (ha)	1	9	200	200	180	180	8	8	9	9	8	8	9	9
	Footprint area (ha)	1	9	150	150	114	114	7	7	9	9	7	7	9	9
	Potential for dust generation during operation	6	9	Moderate	Moderate	High	High	7	9	1	4	42	54	6	24
	Potential for dust generation after closure	4	9	Low	Low	Moderate	Moderate	9	9	6	6	36	36	24	24
	Potential for ARD generation during operation	5	9	Moderate	Low	High - Moderate	Moderate	7	9	3	5	35	45	15	25
	Potential for ARD generation after closure	7	9	Low	Low	Moderate	Moderate	7	7	5	5	49	49	35	35
	Potential for ML during operation	2	9	Low	Moderate	Moderate	Low	8	7	7	9	16	14	14	18
	Potential for ML after closure	5	9	Moderate	Moderate	Low	Low	7	7	9	9	35	35	45	45
	Potential for seepage to groundwater during operation	5	9	Low	Low	Low	Low	9	9	9	9	45	45	45	45
	Potential for geotechnical hazards¹	6	9	Low	Low	High	Moderate	9	9	1	5	54	54	6	30
	Potential for seepage to groundwater after closure	5	9	Low - Moderate	Low - Moderate	Low	Low	7	7	9	9	35	35	45	45
	Area of lakes impacted (ha)	5	9	100 - 140	100	40 - 100	40 - 100	5	6	9	9	25	30	45	45
	Number of lakes impacted	4	9	1 - 2	1	1	1	6	9	9	9	24	36	36	36
	Visual Impact	2	9	Low	Low	High	Moderate	9	9	1	3	18	18	2	6
	Impact on Fish and Fish Habitat	9	9	High	High	Moderate	Moderate	1	1	4	4	9	9	36	36
	Sum of Environmental Weightings	67	603									438	475	372	432
Operational Factors (33% of Weighted Total)	Ease of operation	9	9	High	Moderate	Low	Moderate	9	4	2	6	81	36	18	54
	Distance from mill	8	9	1200 m	1200 m	2800 m	2800 m	9	9	4	4	72	72	32	32
	Potential for delays due to freezing	10	9	Low	Moderate	High	Moderate	9	6	1	7	90	60	10	70
	Construction Risk	4	9	Moderate	Moderate	Low	Low	3	2	7	9	12	8	28	36
	Disposal system has precedent in arctic environment	8	9	No	Yes	Yes	Yes	1	5	9	8	8	40	72	64
	Sum of Operational Weightings	39	351									263	216	160	256
Economic Factors² (assumes i = 8%) (12% of Weighted Total)	Initial Capital Cost (\$CDN) (Approximate)³			\$11,800,000	\$2,860,000	\$5,955,000	\$14,675,000					0	0	0	0
	Net Present Value of Delayed Costs³			\$2,986,613	\$3,428,432	\$5,955,892	\$528,041					0	0	0	0
	Total Present Value of costs	15	9	\$14,786,613	\$6,288,432	\$11,910,892	\$15,203,041	4	9	5	4	60	135	75	60
	Sum of Economic Weightings	15	135									60	135	75	60
TOTAL SCORE			1089	761	826	607	748					761	826	607	748

Notes
1. Includes consideration of foundation conditions, impact of seismicity, and height of structure
2. Relative capital cost for comparison only. Interest rate assumed as 8%.
3. Value not used in scoring. Value is presented to allow calculation of total cost for comparison purposes.

4.2.1 Sensitivity Analysis – Part 1

To consider the impact of the weighting factors used in the decision matrix, a sensitivity analysis was conducted with all sub-indicator weightings set equal to one. This results in each of the sub-indicators having equal importance in the decision process and removes any value bias between the sub-indicators that might be imposed by personal preferences. The greatest numbers of sub-indicators were associated with the environmental category, while the lowest numbers of sub-indicators were associated with the economic category. Consequently, the relative importance of each category is determined by the number of sub-indicators representing that category. Based on the revisions to the weightings, the relative distribution of influence on the weighted total is:

- Environment 71%
- Operational 24 %
- Economic 5%

The results of this analysis are summarized in Table 4.3.

Table 4.3: Summary of Decision Matrix Results – Sensitivity Analysis (Part 1)

Factor	Options			
	B	C	F	G
	Second Portage Arm	Second Portage Arm	West of Waste Rock Storage	West of Waste Rock Storage
	Sub-aerial Paste	Sub-aqueous/ Sub-aerial Slurry	Sub-aerial Slurry	Sub-aerial Paste
Environmental	106	113	91	104
Operational	31	26	23	34
Economic	4	9	5	4
TOTAL	141	148	119	142

The detailed analysis is shown in Table 4.4.

As with the baseline case, Option C received the highest overall score although only marginally greater than Options B and G.

TABLE 4.4: SENSITIVITY ANALYSIS RESULTS (PART 1)				Option B	Option C	Option F	Option G	Scale Factor				Sub-Indicator Weighted Scores			
				Second Portage Arm	Second Portage Arm	North of Second Portage Arm	North of Second Portage Arm	B	C	F	G	B	C	F	G
				Sub-aerial Paste or Dry Stack	Sub-aerial Slurry	Sub-aerial Slurry	Sub-aerial Paste or Dry Stack								
				Construction - Dewater Second Portage Arm by 38 m (El. 95m ASL) and allow base to freeze. Build water management pond near mill or in 3rd Portage Arm. Construct and maintain pipeline.	Construction - Dewater Second Portage Arm by 28 m (El. 105m ASL) to allow construction of dike. Construct and maintain pipeline.	Construction - build conventional tailings containment berms on frozen ground; install and maintain pipeline.	Construction - build minor containment berms on frozen ground; install and maintain pipeline.								
				Operation - Place thickened/paste tailings to 4 to 7 m above current lake level. Maintain water level such that tailings freeze each year. Transport tailings by pipeline for paste, or by truck for thickened.	Operation - Place slurry to 7 m above current lake level. Maintain water management and reclaim pond at west end of lake. Transport tailings by pipeline.	Operation - Place tailings slurry on surface. Use Second Portage Arm for water management and reclaim water, plus reclaim from tailings area. Allow tailings to freeze each year. Transport tailings by pipeline.	Operation - Place thickened/paste tailings on surface. Use Second Portage Arm or Third Portage Arm for water management and reclaim water. Allow tailings to freeze each year. Transport paste tailings by pipeline, or truck thickened tailings.								
Key Indicators	Sub-Indicators	Relative Weighting Factor	Maximum Possible Score	Closure - Permafrost encapsulation: Place ultramafic capping layer to maintain tailings frozen below active layer and to shed water.	Closure - Permafrost encapsulation: Place ultramafic capping layer to maintain tailings frozen below active layer and to shed water.	Closure - Permafrost encapsulation: Place ultramafic capping layer to maintain tailings frozen below active layer and to shed water.	Closure - Permafrost encapsulation: Place ultramafic capping layer to maintain tailings frozen below active layer and to shed water.								
Key Details	Dike construction volumes required (m³)			1,140,000	1,140,000	1,250,000	250,000								
	Capping volume, assuming 2 m thickness (m3)			3,000,000	3,000,000	2,280,000	2,280,000								
	Length of tailings pipeline (m)			2,600	2,800	4,100	4,100								
	Length of reclaim pipeline (m)			800	2,800	1,200	1,000								
	Location of water pond			Near mill or 3rd Portage Arm	2nd Portage Arm	2nd Portage Arm and tailings	2nd or 3rd Portage Arm								
Environmental Factors (71% of Weighted Total)	Sub-catchment area (ha)	1	9	200	200	180	180	8	8	9	9	8	8	9	9
	Footprint area (ha)	1	9	150	150	114	114	7	7	9	9	7	7	9	9
	Potential for dust generation during operation	1	9	Moderate	Moderate	High	High	7	9	1	4	7	9	1	4
	Potential for dust generation after closure	1	9	Low	Low	Moderate	Moderate	9	9	6	6	9	9	6	6
	Potential for ARD generation during operation	1	9	Moderate	Low	High - Moderate	Moderate	7	9	3	5	7	9	3	5
	Potential for ARD generation after closure	1	9	Low	Low	Moderate	Moderate	7	7	5	5	7	7	5	5
	Potential for ML during operation	1	9	Low	Moderate	Moderate	Low	8	7	7	9	8	7	7	9
	Potential for ML after closure	1	9	Moderate	Moderate	Low	Low	7	7	9	9	7	7	9	9
	Potential for seepage to groundwater during operation	1	9	Low	Low	Low	Low	9	9	9	9	9	9	9	9
	Potential for geotechnical hazards ¹	1	9	Low	Low	High	Moderate	9	9	1	5	9	9	1	5
	Potential for seepage to groundwater after closure	1	9	Low - Moderate	Low - Moderate	Low	Low	7	7	9	9	7	7	9	9
	Area of lakes impacted (ha)	1	9	100 - 140	100	40 - 100	40 - 100	5	6	9	9	5	6	9	9
	Number of lakes impacted	1	9	1 - 2	1	1	1	6	9	9	9	6	9	9	9
	Visual Impact	1	9	Low	Low	High	Moderate	9	9	1	3	9	9	1	3
	Impact on Fish and Fish Habitat	1	9	High	High	Moderate	Moderate	1	1	4	4	1	1	4	4
Sum of Environmental Weightings		15	135									106	113	91	104
Operational Factors (24% of Weighted Total)	Ease of operation	1	9	High	Moderate	Low	Moderate	9	4	2	6	9	4	2	6
	Distance from mill	1	9	1200 m	1200 m	2800 m	2800 m	9	9	4	4	9	9	4	4
	Potential for delays due to freezing	1	9	Low	Moderate	High	Moderate	9	6	1	7	9	6	1	7
	Construction Risk	1	9	Moderate	Moderate	Low	Low	3	2	7	9	3	2	7	9
	Disposal system has precedent in arctic environment	1	9	No	Yes	Yes	Yes	1	5	9	8	1	5	9	8
	Sum of Operational Weightings	5	45									31	26	23	34
Economic Factors ² (assumes i = 8%) (5% of Weighted Total)	Initial Capital Cost (\$CDN) (Approximate) ³			\$11,800,000	\$2,860,000	\$5,955,000	\$14,675,000								
	Net Present Value of Delayed Costs ³			\$2,986,613	\$3,428,432	\$5,955,892	\$528,041								
	Total Present Value of costs	1	9	\$14,786,613	\$6,288,432	\$11,910,892	\$15,203,041	4	9	5	4	4	9	5	4
	Sum of Economic Weightings	1	9									4	9	5	4
TOTAL SCORE			189	141	148	119	142					141	148	119	142

Notes

1. Includes consideration of foundation conditions, impact of seismicity, and height of structure

2. Relative capital cost for comparison only. Interest rate assumed as 8%.

3. Value not used in scoring. Value is presented to allow calculation of total cost for comparison purposes.

4. Note the relative distribution of scores between the three primary factors has changed, due to the weightings allocated. The new distribution is Environmental = 71%, Operational = 24%, and Economic = 5%.

4.2.2 Sensitivity Analysis – Part 2

An additional sensitivity analysis was carried out by excluding economic factors, and by reducing the effect of operational factors. The resulting decision matrix was weighted strongly towards the influence of environmental factors. Based on the revisions to the weightings, the relative distribution of influence on the weighted total is:

- Environment 89%
- Operational 11%
- Economic 0%

Table 4.5 summarizes the results of the analysis.

Table 4.5: Summary of Decision Matrix Results – Sensitivity Analysis (Part 2)

Factor	Options			
	B	C	F	G
	Second Portage Arm	Second Portage Arm	West of Waste Rock Storage	West of Waste Rock Storage
	Sub-aerial Paste	Sub-aqueous/ Sub-aerial Slurry	Sub-aerial Slurry	Sub-aerial Paste
Environmental	438	475	372	432
Operational	8	40	72	64
Economic	0	0	0	0
TOTAL	446	515	444	496

The detailed analysis is presented in Table 4.6.

The analysis indicates that when the decision matrix is heavily weighted towards the consideration of environmental factors Option C (tailings slurry disposal in Second Portage Lake) is the preferred option.

TABLE 4.6: SENSITIVITY ANALYSIS RESULTS (PART 2)				Option B	Option C	Option F	Option G	Scale Factor				Sub-Indicator Weighted Scores			
				Second Portage Arm	Second Portage Arm	North of Second Portage Arm	North of Second Portage Arm								
				Sub-aerial Paste or Dry Stack	Sub-aerial Slurry	Sub-aerial Slurry	Sub-aerial Paste or Dry Stack								
				Construction - Dewater Second Portage Arm by 38 m (El. 95m ASL) and allow base to freeze. Build water management pond near mill or in 3rd Portage Arm. Construct and maintain pipeline.	Construction - Dewater Second Portage Arm by 28 m (El. 105m ASL) to allow construction of dike. Construct and maintain pipeline.	Construction - build conventional tailings containment berms on frozen ground; install and maintain pipeline.	Construction - build minor containment berms on frozen ground; install and maintain pipeline.								
				Operation - Place thickened/paste tailings to 4 to 7 m above current lake level such that tailings freeze each year. Transport tailings by pipeline for paste, or by truck for thickened.	Operation - Place slurry to 7 m above current lake level. Maintain water management and reclaim pond at west end of lake. Transport tailings by pipeline.	Operation - Place tailings slurry on surface. Use Second Portage Arm for water management and reclaim water, plus reclaim from tailings area. Allow tailings to freeze each year. Transport tailings by pipeline.	Operation - Place thickened/paste tailings on surface. Use Second Portage Arm or Third Portage Arm for water management and reclaim water. Allow tailings to freeze each year. Transport paste tailings by pipeline, or truck thickened tailings.								
Key Indicators	Sub-Indicators	Relative Weighting Factor	Maximum Possible Score	Closure - Permafrost encapsulation: Place ultramafic capping layer to maintain tailings frozen below active layer and to shed water.	Closure - Permafrost encapsulation: Place ultramafic capping layer to maintain tailings frozen below active layer and to shed water.	Closure - Permafrost encapsulation: Place ultramafic capping layer to maintain tailings frozen below active layer and to shed water.	Closure - Permafrost encapsulation: Place ultramafic capping layer to maintain tailings frozen below active layer and to shed water.								
Key Details	Dike construction volumes required (m ³)			1,140,000	1,140,000	1,250,000	250,000								
	Capping volume, assuming 2 m thickness (m3)			3,000,000	3,000,000	2,280,000	2,280,000								
	Length of tailings pipeline (m)			2,600	2,800	4,100	4,100								
	Length of reclaim pipeline (m)			800	2,800	1,200	1,000								
	Location of water pond			Near mill or 3rd Portage Arm	2nd Portage Arm	2nd Portage Arm and tailings	2nd or 3rd Portage Arm								
Environmental Factors (89% of Weighted Total)	Sub-catchment area (ha)	1	9	200	200	180	180	8	8	9	9	8	8	9	9
	Footprint area (ha)	1	9	150	150	114	114	7	7	9	9	7	7	9	9
	Potential for dust generation during operation	6	9	Moderate	Moderate	High	High	7	9	1	4	42	54	6	24
	Potential for dust generation after closure	4	9	Low	Low	Moderate	Moderate	9	9	6	6	36	36	24	24
	Potential for ARD generation during operation	5	9	Moderate	Low	High - Moderate	Moderate	7	9	3	5	35	45	15	25
	Potential for ARD generation after closure	7	9	Low	Low	Moderate	Moderate	7	7	5	5	49	49	35	35
	Potential for ML during operation	2	9	Low	Moderate	Moderate	Low	8	7	7	9	16	14	14	18
	Potential for ML after closure	5	9	Moderate	Moderate	Low	Low	7	7	9	9	35	35	45	45
	Potential for seepage to groundwater during operation	5	9	Low	Low	Low	Low	9	9	9	9	45	45	45	45
	Potential for geotechnical hazards ¹	6	9	Low	Low	High	Moderate	9	9	1	5	54	54	6	30
	Potential for seepage to groundwater after closure	5	9	Low - Moderate	Low - Moderate	Low	Low	7	7	9	9	35	35	45	45
	Area of lakes impacted (ha)	5	9	100 - 140	100	40 - 100	40 - 100	5	6	9	9	25	30	45	45
	Number of lakes impacted	4	9	1 - 2	1	1	1	6	9	9	9	24	36	36	36
	Visual Impact	2	9	Low	Low	High	Moderate	9	9	1	3	18	18	2	6
	Impact on Fish and Fish Habitat	9	9	High	High	Moderate	Moderate	1	1	4	4	9	9	36	36
	Sum of Environmental Weightings	67	603									438	475	372	432
Operational Factors (11% of Weighted Total)															
	Disposal system has precedent in arctic environment	8	9	No	Yes	Yes	Yes	1	5	9	8	8	40	72	64
	Sum of Operational Weightings	8	72									8	40	72	64
Economic Factors (0% of Weighted Total)															
	Sum of Economic Weightings	0	0									0	0	0	0
TOTAL SCORE			675	446	515	444	496					446	515	444	496

Notes
1. Includes consideration of foundation conditions, impact of seismicity, and height of structure
2. Note the relative distribution of scores between the three primary factors has changed, due to the revised number of sub-indicators. The new distribution is Environmental = 89%, Operational = 11%, and Economic = 0%.

4.2.3 Sensitivity Analysis – Part 3

A final sensitivity analysis was carried out on the baseline case to address specific concerns relating to the effect the proposed methods of disposal may have on fish and fish habitat. For this case, issues relating specifically to impact on fish and fish habitat were adjusted to weight these indicators high in the overall analysis. Based on the revisions to the weightings, the relative distribution of influence on the weighted total is:

- Environment 57%
- Operational 31%
- Economic 12%

The relative weighting factor for “number of lakes impacted” and “impact on fish and fish habitat” were adjusted so that these two indicators carried the highest relative weights of all the environmental sub-indicators. The scale factors for the sub-indicator “number of lakes impacted” remained the same as the previous analyses, as the number of lakes impacted by either on-land or in lake disposal is the same regardless of the disposal method selected. The scale factors for the sub-indicator “impacts on fish and fish habitat” however were increased to the maximum possible value of 9 for on-land disposal, representing the ‘best’ possible case, and were maintained at the least possible value of 1 for disposal in Second Portage Arm, representing the ‘worst’ possible case. The result of this re-scaling is that “impacts on fish and fish habitat” and “number of lakes impacted” contribute between 31% and 35% to the overall environmental weighting for on-land storage, compared with 13% to 17% contribution for disposal within Second Portage Arm.

Table 4.7 summarizes the results of the analysis.

Table 4.7: Summary of Decision Matrix Results – Sensitivity Analysis (Part 3)

Factor	Options			
	B	C	F	G
	Second Portage Arm	Second Portage Arm	West of Waste Rock Storage	West of Waste Rock Storage
	Sub-aerial Paste	Sub-aqueous/ Sub-aerial Slurry	Sub-aerial Slurry	Sub-aerial Paste
Environmental	468	520	462	522
Operational	263	216	160	256
Economic	60	135	75	60
TOTAL	791	871	697	838

The detailed analysis is presented in Table 4.8.

The analysis indicates that when environmental factors are weighted heavily towards impact on lakes and on fish habitat, disposal on-land or in Second Portage Lake carry equivalent total environmental weighting, resulting in a 'null' decision based on that category alone. When economic and operational issues are considered in the decision analysis, then Option C, disposal of slurry tailings in the basin of Second Portage Arm, is the preferred option.

TABLE 4.8: SENSITIVITY ANALYSIS RESULTS (PART 3)				Option B	Option C	Option F	Option G	Scale Factor				Sub-Indicator Weighted Scores			
				Second Portage Arm	Second Portage Arm	North of Second Portage Arm	North of Second Portage Arm	B	C	F	G	B	C	F	G
				Sub-aerial Paste or Dry Stack	Sub-aerial Slurry	Sub-aerial Slurry	Sub-aerial Paste or Dry Stack								
				Construction - Dewater Second Portage Arm by 38 m (El. 95m ASL) and allow base to freeze. Build water management pond near mill or in 3rd Portage Arm. Construct and maintain pipeline.	Construction - Dewater Second Portage Arm by 28 m (El. 105m ASL) to allow construction of dike. Construct and maintain pipeline.	Construction - build conventional tailings containment berms on frozen ground; install and maintain pipeline.	Construction - build minor containment berms on frozen ground; install and maintain pipeline.								
				Operation - Place thickened/paste tailings to 4 to 7 m above current lake level such that tailings freeze each year. Transport tailings by pipeline for paste, or by truck for thickened.	Operation - Place slurry to 7 m above current lake level. Maintain water management and reclaim pond at west end of lake. Transport tailings by pipeline.	Operation - Place tailings slurry on surface. Use Second Portage Arm for water management and reclaim water, plus reclaim from tailings area. Allow tailings to freeze each year. Transport tailings by pipeline.	Operation - Place thickened/paste tailings on surface. Use Second Portage Arm or Third Portage Arm for water management and reclaim water. Allow tailings to freeze each year. Transport paste tailings by pipeline, or truck thickened tailings.								
Key Indicators	Sub-Indicators	Relative Weighting Factor	Maximum Possible Score	Closure - Permafrost encapsulation. Place ultramafic capping layer to maintain tailings frozen below active layer and to shed water.	Closure - Permafrost encapsulation. Place ultramafic capping layer to maintain tailings frozen below active layer and to shed water.	Closure - Permafrost encapsulation. Place ultramafic capping layer to maintain tailings frozen below active layer and to shed water.	Closure - Permafrost encapsulation. Place ultramafic capping layer to maintain tailings frozen below active layer and to shed water.								
Key Details	Dike construction volumes required (m³)			1,140,000	1,140,000	1,250,000	250,000								
	Capping volume, assuming 2 m thickness (m3)			3,000,000	3,000,000	2,280,000	2,280,000								
	Length of tailings pipeline (m)			2,600	2,800	4,100	4,100								
	Length of reclaim pipeline (m)			800	2,800	1,200	1,000								
	Location of water pond			Near mill or 3rd Portage Arm	2nd Portage Arm	2nd Portage Arm and tailings	2nd or 3rd Portage Arm								
Environmental Factors (57% of Weighted Total)	Sub-catchment area (ha)	1	9	200	200	180	180	8	8	9	9	8	8	9	9
	Footprint area (ha)	1	9	150	150	114	114	7	7	9	9	7	7	9	9
	Potential for dust generation during operation	6	9	Moderate	Moderate	High	High	7	9	1	4	42	54	6	24
	Potential for dust generation after closure	4	9	Low	Low	Moderate	Moderate	9	9	6	6	36	36	24	24
	Potential for ARD generation during operation	5	9	Moderate	Low	High - Moderate	Moderate	7	9	3	5	35	45	15	25
	Potential for ARD generation after closure	7	9	Low	Low	Moderate	Moderate	7	7	5	5	49	49	35	35
	Potential for ML during operation	2	9	Low	Moderate	Moderate	Low	8	7	7	9	16	14	14	18
	Potential for ML after closure	5	9	Moderate	Moderate	Low	Low	7	7	9	9	35	35	45	45
	Potential for seepage to groundwater during operation	5	9	Low	Low	Low	Low	9	9	9	9	45	45	45	45
	Potential for geotechnical hazards¹	6	9	Low	Low	High	Moderate	9	9	1	5	54	54	6	30
	Potential for seepage to groundwater after closure	5	9	Low - Moderate	Low - Moderate	Low	Low	7	7	9	9	35	35	45	45
	Area of lakes impacted (ha)	5	9	100 - 140	100	40 - 100	40 - 100	5	6	9	9	25	30	45	45
	Number of lakes impacted	9	9	1 - 2	1	1	1	6	9	9	9	54	81	81	81
	Visual Impact	2	9	Low	Low	High	Moderate	9	9	1	3	18	18	2	6
	Impact on Fish and Fish Habitat	9	9	High	High	Moderate	Moderate	1	1	9	9	9	9	81	81
	Sum of Environmental Weightings	72	648									468	520	462	522
Operational Factors (31% of Weighted Total)	Ease of operation	9	9	High	Moderate	Low	Moderate	9	4	2	6	81	36	18	54
	Distance from mill	8	9	1200 m	1200 m	2800 m	2800 m	9	9	4	4	72	72	32	32
	Potential for delays due to freezing	10	9	Low	Moderate	High	Moderate	9	6	1	7	90	60	10	70
	Construction Risk	4	9	Moderate	Moderate	Low	Low	3	2	7	9	12	8	28	36
	Disposal system has precedent in arctic environment	8	9	No	Yes	Yes	Yes	1	5	9	8	8	40	72	64
	Sum of Operational Weightings	39	351									263	216	160	256
Economic Factors² (assumes i = 8%) (12% of Weighted Total)	Initial Capital Cost (\$CDN) (Approximate) ³			\$11,800,000	\$2,860,000	\$5,955,000	\$14,675,000					0	0	0	0
	Net Present Value of Delayed Costs³			\$2,986,613	\$3,428,432	\$5,955,892	\$528,041					0	0	0	0
	Total Present Value of costs	15	9	\$14,786,613	\$6,288,432	\$11,910,892	\$15,203,041	4	9	5	4	60	135	75	60
	Sum of Economic Weightings	15	135									60	135	75	60
TOTAL SCORE			1134	791	871	697	838					791	871	697	838

Notes
1. Includes consideration of foundation conditions, impact of seismicity, and height of structure
2. Relative capital cost for comparison only. Interest rate assumed as 8%.
3. Value not used in scoring. Value is presented to allow calculation of total cost for comparison purposes.

4.3 Discussion

The result of the initial base case decision matrix analysis, and the subsequent sensitivity analyses are similar. The best disposal option for tailings management at the Meadowbank Project is disposal of tailings into the natural rock basin of the northwest arm of Second Portage Lake. Permafrost encapsulation of the tailings will form the control strategy for acid mine drainage and metal leaching. The primary advantages provided by Option C are as follows:

- Lowest potential for the generation of acidic drainage and the release of metal constituents to the environment;
- Lowest potential for the generation of dust from the facility during operations and closure, and consequently the lowest potential for the migration of contaminants beyond the limits of the storage facility and the mine site. Facilities exposed to wind erosion will have a greater risk of release of wind-blown contaminants to the environment by deposition on-land or into lakes;
- Simplest construction methodology requiring construction materials from the mining activities;
- Simplest closure methodology, requiring least amount of borrow materials;
- Low risk of instability of tailings facility, and hence lower risk of potential release of tailings to the environment;
- Ease of operation in harsh Arctic climates;
- Lowest relative capital cost; and
- Precedence in Arctic climate.

5.0 CASE STUDY – NORTH RANKIN INLET NICKEL MINE

The North Rankin Inlet Nickel Mine presents a case study that is directly comparable to the conditions at the Meadowbank Project and to the recommended tailings management plan. Rankin Inlet is a community located approximately 250 km south, and 430 km east of the Meadowbank Project site (see Figure 1). The community is located on Hudson Bay. The similarities between the Meadowbank Project site and Rankin Inlet are: the sites are in the zone of continuous permafrost; the mean annual air temperature at both sites is approximately -11°C; remedial measures to manage the reactive and acid generating tailings at Rankin Inlet have included the disposal of the tailings by permafrost encapsulation in a drained bedrock basin to maintain the tailings and their saline pore water in a chemically inert state. Thermal instrumentation at the Rankin Inlet site has shown the tailings to be frozen or freezing, and that freeze-back is occurring more rapidly than predicted. There is no evidence of thermal heating due to oxidation of tailings. The results of the field and laboratory investigations of the tailings at Rankin Inlet are presented by Meldrum, et. al. (2001) and are summarized in the following sections.

5.1 Summary of Rankin Inlet Remediation Project

The North Rankin Inlet Nickel Mine was operated for five years from 1957 to 1962 and produced 297,000 tonnes of tailings. Prior to remediation the acid-generating sulphide rich tailings were exposed on the shores of Hudson Bay for 30 years, releasing acidic, metal-rich water. In addition to release of the contaminated pore water into Hudson Bay, oxidized tailings dust was wind blown through the town of Rankin Inlet, and deposited on the tundra as well as further out on to the sea ice covering the bay during the winter months, and on to the water surface during the summer months. In 1991 a remedial program was initiated which involved the burial of the tailings in a drained bedrock basin, relying on eventual permafrost encapsulation to limit the tendency of contaminated pore water to migrate further from the site. The remediation involved the *in-situ* treatment of 100,000 m³ of contaminated water, the draining of a bedrock basin, and the subsequent filling of the basin with 48,000 m³ of tailings to a maximum depth of 16 m with the intention of encapsulating the tailings in permafrost rendering them chemically inert (Erickson, 1995). The tailings were covered with 1 m of gravel fill from a nearby esker to host the active layer, thus keeping the tailings in a frozen state as permafrost was expected to grow downward over time through the tailings.

Pyrrhotite is estimated to comprise between 5% and 20% by volume of the tailings at Rankin Inlet. Pyrrhotite is the most rapidly oxidizing sulphide commonly found in mine waste. In addition to the rapidly oxidizing sulphides, the tailings exhibited freezing point depression due to the high salinity of the porewater resulting from inundation with seawater. By comparison, the tailings at the Meadowbank Project are estimated to contain between 4% and 5% sulphides, primarily pyrite.

Three years after burial a series of field investigations and instrumentation was undertaken at the site. The field investigations involved the drilling of boreholes, the collection of a frozen core sample of tailings using a Cold Regions Research and Engineering Laboratory (CRREL) core barrel, and the installation of a series of thermistor cables to monitor the thermal conditions within the tailings. Additional laboratory experimentation was carried out to determine the effect of freezing point depression on sulphide oxidation rates and whether or not this will affect the local thermal regime.

5.2 Thermal Regime in the Tailings at Rankin Inlet

A map showing the locations of the thermistor installations, as well as the results of the monitoring program between March 29, 1997 and February 4, 1998 are shown on Figure 10. The figures indicate that the tailings at the time the data were collected were freezing or were frozen. A thermistor installed outside of Deep Pond but adjacent to the reclamation site shows the permafrost thermal regime to a depth of 16 m, with a mean annual ground temperature of about -7°C (see Thermistor Cable 8 on Figure 10). By comparison, the mean annual ground temperature at the Meadowbank Project is expected to be on the order of -8°C to -10°C , based on site specific data collected from thermistors.

Figure 11 shows the predicted mean annual ground temperature in the reclaimed tailings for a range of time intervals after burial, with the data for borehole six plotted for comparison. The results indicate that the freezing of the tailings occurs more rapidly than predicted, and that the entire tailings thickness will be at least partly ice-bonded 15 years after burial (Meldrum et. al., 2001). Meldrum suggests this may be a result of lower volumetric moisture content than assumed by the modeling. However, an alternative explanation could be that the two-dimensional model used to predict ground freezing does not take into account the three-dimensional effect of perimeter freezing.

5.3 Key Conclusions of the Rankin Inlet Studies and Implications for the Meadowbank Project Site

The following key conclusions were drawn from the laboratory testing and field instrumentation measurements at the Rankin Inlet site and are compared with the expected site conditions at the Meadowbank Project.

- A significantly reduced but measurable oxidation takes place at -2°C , augmented by freezing point depression due to saline pore waters. There is no measurable oxidation at -10°C .
- The reactivity and oxidation of the tailings at Rankin Inlet below a mean annual ground temperature of -2°C is expected to be very low. It is expected that the reactivity and oxidation of the tailings at the Meadowbank Project will be similar, provided that similar disposal philosophies are adopted.

- Freeze-back of the reclaimed tailings at Rankin Inlet is underway. Eventually a pocket of unfrozen brine may remain, enclosed between the overlying ice-bonded tailings and the refrozen bedrock beneath the former Deep Pond. Although the salinity of the tailings pore water results in considerable freezing-point depression, the effect of this on oxidation rate is low.
- Heating by tailings oxidation has not been noticeable at Rankin Inlet.
- Based on the field studies and laboratory testing of tailings at the Rankin Inlet site, encapsulating tailings in permafrost should minimize oxidation where the tailings temperature is maintained below -2°C . At Rankin Inlet, a mean annual air temperature of about -11°C produces a mean annual ground temperature of about -7°C . Consequently, Meldrum et. al. (2001) suggest that any prospective site for tailings disposal by permafrost encapsulation should have a mean annual air temperature of less than -6°C , as the field studies at the Rankin Inlet site indicated that ice bonding of the tailings begins at about -4°C . At the Meadowbank Project, the mean annual air temperature of the site is estimated to be about -11.3°C , and the mean annual ground temperature is estimated to range from about -8°C to about -10°C , based on site specific measurements. Long-term temperature trends based on monitoring data collected over a period of 50 years at Baker Lake, when applied to the Meadowbank Project site, suggest a mean annual air temperature of -12.8°C . Consequently, the encapsulation of tailings in permafrost is a preferred control strategy for the Meadowbank Project site.
- The tailings at the Rankin Inlet site are expected to be fully ice-bonded approximately 15 years after burial. This is consistent with predicted thermal modeling of the Meadowbank Tailings Facility in the northwest arm of Second Portage Lake.
- Freezing of the tailings at Rankin Inlet is occurring at a faster rate than predicted. Meldrum et. al. (2001) attributes this to a lower volumetric moisture content than assumed in the modeling. However, an alternative explanation is that the two-dimensional modeling does not account for the three-dimensional effect of perimeter freezing of the tailings, or the advancement of the freezing front from the permafrost surrounding the drained rock basin into which the tailings were deposited. A similar situation, more rapid freezing than predicted, may occur at the Meadowbank Project with the permafrost freezing front advancing into the tailings deposited into the drained rock basin of the northwest arm of Second Portage Lake.
- The precipitation of secondary minerals due to progressive freezing of the tailings may locally inhibit fluid migration by cementation.

6.0 SUMMARY AND CONCLUSIONS

This report has provided additional clarification of terminology, and of the decision making process used to select a tailing management system (location and technology) for the Meadowbank Gold Project. A decision matrix approach was utilized. An important aspect of the decision matrix methodology is that it requires all factors be weighed in the final outcome, rather than allowing a single factor to dictate the overall outcome.

Three primary categories were considered:

- Environmental;
- Operational; and
- Economic.

Sub-indicators within each category were identified, and weighting factors were assigned based on the relative importance of sub-indicators to each other. A scale, or scoring factor was applied to help separate 'best' options from 'worst' options. In the evaluation of all options, environmental factors contributed the most significantly to the outcome of the decision analysis.

Seven potential tailings management facilities were identified. These facilities were screened to determine if they met the basic site selection criteria:

- The site was required to have sufficient volume to store planned volume of tailings;
- The site required the potential to provide additional capacity for tailings storage;
- The location would permit mine expansion;
- The location is within catchments of the open pits; and
- The site allows control and collection of supernatant.

Only four of the options met these criteria, as listed below.

Location	Disposal Type
Second Portage Arm	Sub-aerial Paste or Dry Stack
Second Portage Arm	Sub-aerial Slurry
North of Second Portage Arm	Sub-aerial Slurry
North of Second Portage Arm	Sub-aerial Paste or Dry Stack

A decision matrix analysis was carried out for these four options. In addition to the initial, or baseline analysis, two sensitivity analyses were completed to consider the impact of the weighting factors. The first sensitivity analysis removed the influence of the weighting factors by setting each to one, thus placing an equal level of importance on each sub-indicator. The second analysis reduced the influence of operational factors and eliminated any economic influence on the decision process.

The results of the decision matrix analysis indicate that the preferred tailings management option for the Meadowbank Project, based on environmental, operational, (including engineering and technical) and economic considerations, is the disposal of tailings into the natural basin of the northwest arm of Second Portage Lake, followed by permafrost encapsulation. The sensitivity analyses showed that even when economic factors were removed from consideration, and operational factors were reduced in terms of relative importance leaving environmental factors as having the greatest importance, the preferred option is still indicated to be disposal in the northwest arm of Second Portage Lake followed by permafrost encapsulation as a control strategy for acid mine drainage.

A case study of the oxidation of mine tailings from Ranking Inlet, Nunavut, at sub-zero temperatures was presented. The tailings are acid generating and metal leaching, with saline pore waters. A remediation program begun in 1991 consisted of depositing the tailings into a drained rock basin, with the expectation that permafrost would aggrade into the facility. This is similar to the preferred option for tailings management at the Meadowbank project. A series of thermistors installed in the test area indicated that freeze-back of the tailings was occurring more rapidly than predicted. There was no indication of heating by tailings oxidation, despite the highly reactive nature of the pyrrhotite rich tailings. The results of the laboratory and field investigations indicated that prospective sites for permafrost encapsulation of tailings should have a mean annual air temperature colder than about -6°C. The Meadowbank Project site has a mean annual air temperature of about -11.3°C and mean annual ground temperature of -8°C to -10°C. Based on long-term temperature trends at Baker Lake, applied to the Meadowbank Project site, a mean annual air temperature of -12.8°C is indicated. Based on the results presented in the case study, permafrost encapsulation of tailings disposed in a drained rock basin, such as the northwest arm of Second Portage Lake, is the preferred method of disposal of tailings at the Meadowbank Project.

7.0 CLOSURE

We trust that this report meets your requirements at this time. If you have any additional questions, please do not hesitate to contact the undersigned.

Yours very truly,

GOLDER ASSOCIATES LTD.

Fiona Esford, M.A.Sc., P.Eng., LEG
Geotechnical Engineer

Cameron J. Clayton, M.Eng., P.Geo.
Associate

FCE/CJC/kt/vee/lba

N:\FINAL\2005\1413\05-1413-036A\3000\RPT-1006_05 CUMBERLAND RESOURCES-TAILINGS STORAGE FACILITY SELECTION.DOC

REFERENCES

- AMEC Americas Ltd. 2005. Meadowbank Gold Project, Hydrologic Monitoring 2004 Data Report – Draft. February 2005.
- Access Consulting Group. 2003. Examination of Revegetation Methodologies for Dry Stack Tailings in Northern Environments. Prepared for: Mining Environmental Research Group, Government of Yukon. March 2003.
- Brown, Bruce S. 2002. Management of Tailings Disposal on Land. Knight Piesold Consulting.
- Caldwell, Jack A., and Andrew Mac G. Robertson. 1983. Selection of tailings impoundment sites. Die Siviele Ingenieur in Suid-Afrika. Oktober 1983.
- Canter. 1985. Ground Water Pollution Control. CRC – Taylor & Frances, New York.
- CH₂MHILL. 2004. Clark Fork River Operable Unit, of the Milltown Reservoir/Clark Fork River Superfund Site, Record of Decision, Part 3: Responsiveness Summary, April 2004, U.S. Environmental Protection Agency, Region 8, Montana.
- CRL. 2005a. Meadowbank Gold Project, Baseline Fish Habitat Report, Cumberland Resources Ltd., January 2005.
- CRL. 2005b. Meadowbank Gold Project, Baseline Aquatic Ecosystem Report, Cumberland Resources Ltd., January 2005.
- Davies, Michael, P. and Stephen Rice. 2001. An alternative to conventional tailing management – “dry stack” filtered tailings. Infomine.
- Decision – Makers Field Guide. 2005. Environmental and Water Quality Issues (Chapter 2); Sustainable Development, Technology, and a look to the Future (Chapter 4). Mining in New Mexico, Decision – Makers Field Conference 2005 Taos Region.
- European Commission. 2004. Reference Document on Best Available Techniques for Management of Tailings and Waste-Rock in Mining Activities. July 2004. Sustainability in Industry, Energy, and Transport European IPPC Bureau, Spain. (<http://eippcb.jrc.es>).


- Golder. 2004. Mine Waste and Water Management Meadowbank Gold Project, Nunavut. Prepared for Cumberland Resources Ltd. Golder Associates Ltd., March 5, 2004. Report No. 03-1413-427-5000.
- Golder. 2005. Alternative Waste and Water Management Plan, Meadowbank Gold Project, Nunavut. Prepared for Cumberland Resources Ltd. Golder Associates Ltd., March, 2005. Report No. 04-1413-034/2600.
- International Atomic Energy Agency (IAEA). 2000. Recycle and reuse of materials and components from waste streams of nuclear fuel cycle facilities. January 2000, Waste Technology Section, Austria.
- Martin, T.E., et.al. 2002. Stewardship of Tailings Facilities. Mining Minerals and Sustainable Development. No. 20, April 2002. AMEC Simons Ltd., Vancouver.
- Meldrum, J. L., et. al. 2001. Oxidation of Mine Tailings From Rankin Inlet, Nunavut, at Sub-zero Temperatures. Canadian Geotechnical Journal 38: 957-966.
- Mine Effluent Neutral Drainage (MEND) Project 1.61.2. 1996. Acid Mine Drainage in Permafrost Regions: Issues, Control, Strategies, and Research Requirements. July 1996.
- Molycorp Watch Project. ----. Current Regulatory Permitting for the Molycorp Mine, Amigos Bravos Friends of the Wild Rivers (NGO, New Mexico). Website: <http://amigosbravos.org/molycorpwatch/permits/index.html> (July 19, 2005).
- Norman, David K., and Robert L. Raforth. 1998. Innovations and Trends in Reclamation of Metal-Mine Tailings in Washington. Washington Geology, Vol. 26 No. 2/3, September 1998.
- Northern Liner. 2005. "Mining Across Alaska – Summaries. The Journal of the Northern Alaska Environmental Center, Summer 2005, Volume XXVII, Number 2.
- Robertson, A. MacG. 1982. Site selection and design options for uranium mine waste and plant tailings. Proceedings, 12th CMMI Congress. H.W. Glen (Ed.) Johannesburg, S. Africa. Institute of Mining and Metallurgy.
- Robertson, A. MacG., and S.C. Shaw. 1998. Alternative analysis for mine development and reclamation. Proceedings of the 22nd Annual BC Mine Reclamation Symposium, Penticton, BC. Canada, (September 14-17, 1998) pp. 51-62.

Robertson, A. MacG., and S.C. Shaw. 1999. A multiple accounts analysis for tailings site selection. In Sudbury '99 - Mining and the Environment II Proceedings, D. Goldsack, N. Belzile, P. Yearwood and G. Hall (Eds) September 12-16, Sudbury, Ontario, Can. Pages 883-892.

Robson Valley Land and Resource Management Plan – April 1999. Government of British Columbia.

Shaw, S.C., et.al. 2001. Review of the Multiple Accounts Analysis Alternatives Evaluation Process Completed for the Reclamation of the Zortman and Landusky Mine Sites. Presented at the 2001 National Association of Abandoned Mine Lands Annual Conference, August 19-22, 2001, Athens, Ohio.

Vick, Steven G. 1990. Planning, Design, and Analysis of Tailings Dams, BiTech Publishers Ltd., Vancouver. ISBN 0-921095-12-0.



LEGEND

- Meadowbank Project
- Town/Village
- Provincial Border
- Water
- Primary Highway
- Railroad



REFERENCE

Base digital data obtained from ESRI Inc.,
DATUM: WGS84 PROJECTION: Geographic

200 0 200 Kilometers
Scale - 1:10,000,000

PROJECT		CUMBERLAND RESOURCES LTD.			
TITLE		LOCATION PLAN MEADOWBANK PROJECT			
		PROJECT No. 05-1413-036A		SCALE AS SHOWN	REV. 0
		DESIGN	CJC	26 Sep. 2005	
		GIS	CDB	26 Sep. 2005	
		CHECK	CJC	26 Sep. 2005	
		REVIEW			
		FIGURE 1			

CADD FILE: N:\Bur-Graphics\Projects\2005\1413\05-1413-036A\1050\CAD\TAILINGS REPORT\051413036A-SK10.dwg
REVISION DATE: 05/10/07 11:33am By: WLI




REFERENCES


- 1) Drawing taken from AMEC, Drawing # A1-131395-100-C-0001.

LEGEND


SD: SADDLE DAM

PROJECT		CUMBERLAND RESOURCES LTD.	
TITLE		GENERAL SITE PLAN	
		PROJECT No. 05-1413-036A	
		FILE No. 051413036A-SK10	
		DESIGN CJC 26SEP05	SCALE AS SHOWN
		CADD WLI 26SEP05	REV. -
CHECK CJC 27SEP05	FIGURE 2		
REVIEW CJC 27SEP05			







Source: European Commission, 2002.

PROJECT		CUMBERLAND RESOURCES LTD.			
TITLE		GEOCHEMICAL AND PHYSICAL PROCESSES POTENTIALLY RESULTING IN ARD AND ML			
		PROJECT No. 05-1413-036A		FILE No. FIGURES 3	
		DESIGN	CC	28SEP05	SCALE NTS
		CADD	VEE	28SEP05	REV.
		CHECK	CC	28SEP05	FIGURE 4
		REVIEW			


HEAPED CONSTRUCTION




CONSTRUCTION CONFIGURATION



END-DUMPED CONSTRUCTION



RE-SLOPED CONFIGURATION




Freeze Controlled ARD Strategies

Climate Controlled ARD Strategies

Not to Scale


Reference: MEND 1.61.2, 1996

PROJECT		CUMBERLAND RESOURCES LTD.					
TITLE		WASTE ROCK STORAGE FACILITY CONSTRUCTION METHODS					
		PROJECT No.		05-1413-036A	FILE No.	FIGURE	
		DESIGN	CC	05OCT05	SCALE	NTS	REV.
		CADD	SS	05OCT05	FIGURE 5		
		CHECK	CC	05OCT05			
		REVIEW					




DRAWING DATE: 07-Oct-05 COREL FILE: N:\Bur-Graphics\Projects\2005\1413\05-1413-036A\Tailings Report\Corel\Figure 2.cdr


a) YEAR 1 - Winter




b) YEAR 1 - Summer








c) YEAR 2 - Winter



d) YEAR 2 - Summer




-  Starter Dyke
-  Frozen Cell
-  Thawed Tailings
-  Dam Raise
-  Frozen Overboard Material


Reference: MEND 1.61.2, 1996


PROJECT				
CUMBERLAND RESOURCES LTD.				
TITLE				
TAILINGS THIN LAYERED FREEZING DESIGN CONCEPT				
PROJECT No. 05-1413-036A			FILE No. FIGURE 2	
DESIGN	CC	06OCT05	SCALE NTS	REV.
CADD	SS	06OCT05	FIGURE 6	
CHECK	CC	06OCT05		
REVIEW				







Source: Martin, 2002.

PROJECT		CUMBERLAND RESOURCES LTD.			
TITLE		TAILING DAM CONSTRUCTION METHODS			
		PROJECT No. 05-1413-036A		FILE No. FIGURES 4	
		DESIGN	CC	28SEP05	SCALE NTS
		CADD	VEE	28SEP05	REV.
		CHECK	CC	28SEP05	
		REVIEW			
		FIGURE 7			










Source: European Commission, 2003.

PROJECT		CUMBERLAND RESOURCES LTD.			
TITLE		TAILINGS DAM AND WATER CYCLE			
		PROJECT No. 05-1413-036A		FILE No. FIGURES 3	
		DESIGN	CC	28SEP05	SCALE NTS
		CADD	VEE	28SEP05	REV.
		CHECK	CC	28SEP05	FIGURE 8
		REVIEW			



Source: European Commission, 2002.

PROJECT		CUMBERLAND RESOURCES LTD.			
TITLE		ABOVE GROUND PASTE TAILINGS DEPOSITION METHODS			
		PROJECT No. 05-1413-036A		FILE No. FIGURES 3	
		DESIGN	CC	28SEP05	SCALE NTS
		CADD	VEE	28SEP05	REV.
		CHECK	CC	28SEP05	FIGURE 9
		REVIEW			



Map of Deep Pond showing borehole locations and depth of bottom below surface of gravel cover (2 m contour interval). Insets show ground temperature records between March 29, 1997 and Feb. 4, 1998

Reference: Oxidation of Mine Tailings from Rankin Inlet, Nunavut, at Subzero Temperatures. Meldrum, et.al., 2001.

PROJECT

**CUMBERLAND
RESOURCES LTD.**


TITLE

**RANKIN INLET TAILINGS STUDY
THERMAL MONITORING**



PROJECT No.	05-1413-036A	FILE No.	FIGURES 2
DESIGN	CC	26SEP05	SCALE NTS
CADD	SS	26SEP05	REV.
CHECK	CC	26SEP05	
REVIEW			

FIGURE 10



Prediction of mean annual ground temperature in reclaimed tailings for a range of time intervals after burial in late 1993. Dashed line at -4°C shows temperature at which tailings become noticeably ice-bonded. Dots show mean annual ground temperatures for borehole 6, 4 years after burial. Temperature reversal for uppermost 2 m is due to annual variation of thermal properties in the active layer.

Reference: Oxidation of Mine Tailings from Rankin Inlet, Nunavut, at Subzero Temperatures. Meldrum, et.al., 2001.

PROJECT				
CUMBERLAND RESOURCES LTD.				
TITLE				
RANKIN INLET TAILINGS STUDY PREDICTED FREEZE-BACK TIME				
PROJECT No.		05-1413-036A	FILE No.	
DESIGN		CC	26SEP05	SCALE NTS
CADD		SS	26SEP05	REV.
CHECK		CC	26SEP05	FIGURE 11
REVIEW				



APPENDIX B

Waste Rock Site Selection

Golder Associates Ltd.

500 – 4260 Still Creek Drive
Burnaby, British Columbia, Canada V5C 6C6
Telephone (604) 296-4200
Fax (604) 298-5253



REPORT ON

**EVALUATION OF WASTE ROCK MANAGEMENT
ALTERNATIVES
MEADOWBANK GOLD PROJECT
NUNAVUT**

Submitted to:

Cumberland Resources Ltd.
Suite 950, One Bentall Centre
505 Burrard Street
Vancouver, BC
V7X 1M4

DISTRIBUTION:

- 3 Copies - Cumberland Resources Ltd.
- 2 Copies - Golder Associates Ltd.

October 14, 2005

05-1413-036A/1000



EXECUTIVE SUMMARY

A series of Technical Meetings were held in Baker Lake on June 2 and 3, 2005 to review the Draft Environmental Impact Statement (DEIS) for Cumberland Resources Limited (CRL), Meadowbank Gold Project. Following the technical meeting, a list of commitments by CRL was prepared, which would either be addressed as soon as possible or appear in the Final Environmental Impact Statement. This report responds to Items #5 and #26 from this list, which requested additional information relating to the decision matrix used to evaluate waste rock disposal options.

Items #5 and #26 from this list specifically requested that:

- 1) Revised wording for the elimination of options be provided;
- 2) Clarification be provided regarding the decision matrices for the Portage Rock Storage Facility (as it relates to the possible effects on all affected fish-bearing lakes) – to be provided to parties as soon as possible;
 - a) The rationale for selecting the various factors, sub-indicators and relative weightings and the ranking of the various options needs to be supported with scientific evidence. The various options need to be clearly described with supporting rationale for each component.

Two reports have been issued previously describing the strategy for selecting the waste rock storage facility and details of the mine waste and water management plan:

- Golder Associates Ltd., Report on Alternative Waste and Water Management Plan, Meadowbank Gold Project, Nunavut, March 7, 2005; and
- Golder Associates Ltd., Report on Mine Waste and Water Management, Meadowbank Gold Project, Nunavut, March 5, 2004.

The Meadowbank Gold Project is located near Baker Lake, Nunavut. Cumberland Resources Ltd. is conducting a feasibility study to develop a gold mine that will consist of a series of open pits with a single processing plant, a tailings storage facility and two waste rock storage areas. The revised mine plan estimates 22 million tonnes of ore will be produced over a mine life of 8.3 years, and will generate a total volume of 173 million tonnes (bulked) of waste rock. The geochemical testing has shown that the waste rock will have the potential to produce acid rock drainage (ARD) and metal leaching (ML). Consequently, disposal methods to limit the potential for ARD and ML are desirable.

The Mine Waste and Water Management Report (Golder, 2004) previously presented the results of the waste rock facility selection process. Due to the distance between the Portage and Goose Island mining areas and the Vault mining area and volume of waste rock storage required, it was decided that two waste rock storage facilities would be required. One facility would be near the Vault open pit, to accommodate waste rock generated from mining at this location, and the second would be near the Portage pits (North Portage and Third Portage) and Goose pit.

The process used to select the waste rock storage facilities involved:

- Identifying potential locations; and
- Developing a site specific, decision matrix model to evaluate, rank, and select the best overall facility or facilities.

This approach, sometimes known as a Multiple Accounts Analysis (MAA), is commonly used as a decision making tool for the selection of waste management facilities. The decision matrix model considered factors in three primary categories: environmental, operational and economic. Each category was further subdivided to consider various components. Weighting factors were assigned to each sub-indicator and to the overall factors. Environmental factors were judged as being the most important and were therefore assigned the highest overall weighting.

The Vault open pit is located in a region of low relief, is surrounded by numerous lakes (i.e., Phaser Lake, Vault Lake and Wally Lake), and near a drainage subdivide. There are few suitable locations for a waste rock storage facility near the Vault pit owing to the presence of numerous lakes adjacent to Vault Lake and the lack of topographical relief in the immediate area, which limits the height to which a rock storage facility could be constructed without becoming visible at great distance from the site. In addition, placing waste rock in areas south of Vault Lake would affect a sub-watershed that does not drain toward the Vault open pit. The best alternative for the storage of the waste rock from the Vault pit is on a broad area of land immediately to the west of the open pit area. Because there was only one suitable area for waste rock storage in the Vault area, a Multiple Accounts Analysis was not performed.

Alternatives for the Portage rock storage facility were evaluated in the Report on *Alternative Waste and Water Management Plan* (Golder, 2005), due to a revised mine plan. This report was prepared to provide additional information on the decision making process used to select the final location for the Portage rock storage facility. This information is provided to fulfill commitments made by Cumberland Resources Ltd. during a prehearing conference and technical meetings, specifically Items 5 and 26.

Options A and B were evaluated with options C and D located to the East of Vault Haul Road using the MAA decision matrix model. Locations for each are described below:

Option	Location Description
Option A*	North of Second Portage Arm – small footprint
Option B	North of Second Portage Arm – large footprint
Option C	East of Vault Haul Road – small footprint
Option D	East of Vault Haul Road – large footprint

* Option A was originally evaluated in Golder, 2004 report. Alternatives (A & B) to the original Option A were evaluated in *Report on Alternative Waste and Water Management Plan* (Golder, 2005) and compared to Option A.

Through this process Option A (located north of the Portage tailings storage facility) was shown to have the least impact on fish bearing lakes and the smallest over-all foot print. Option A along with the Vault rock storage facility were chosen as the best options for waste rock storage.

TABLE OF CONTENTS

<u>SECTION</u>	<u>PAGE</u>
1.0 INTRODUCTION.....	1
1.1 Physical Setting	2
1.2 Planned Mining Operations	4
1.3 Decision Matrix Models	4
1.4 Meadowbank Waste Rock Facility Selection Process	5
1.4.1 Potential Rock Storage Facilities	5
1.4.2 Meadowbank Decision Matrix Model	8
2.0 MEADOWBANK DECISION MATRIX METHOD OF ANALYSIS.....	11
2.1 Environmental Factors.....	11
2.1.1 Sub-catchment Area	12
2.1.2 Footprint Area	12
2.1.3 Area of Lakes Impacted.....	13
2.1.4 Potential for Geotechnical Hazards	13
2.1.5 Visual Impact	13
2.1.6 Potential for Dust Generation	13
2.1.7 Potential for Seepage to Impact Groundwater.....	13
2.1.8 Potential for Acid Rock Drainage (ARD) Generation	14
2.1.9 Potential for ARD Generation After Closure	14
2.1.10 Potential for Metal Leaching (ML) Generation During Operation	15
2.1.11 Potential for ML Generation After Closure	15
2.1.12 Impact on Fish and Fish Habitat	15
2.2 Operational Factors	17
2.2.1 Ease of Operation	17
2.2.2 Distance from Mill	17
2.2.3 Potential for Delays due to Freezing.....	17
2.2.4 Construction Risk.....	17
2.2.5 Disposal System has Precedent in Arctic Environment.....	18
2.3 Economic Factors	18
2.4 Weighting Factors and Scoring	19
2.5 Calculations	21
3.0 ANALYSIS OF MEADOWBANK WASTE ROCK STORAGE FACILITIES	22
3.1 Description of Potential Waste Rock Storage Methods	22
3.2 Description of Potential Waste Rock Storage Facility Areas	24
3.2.1 Portage Rock Storage Facility Alternatives	24
3.2.2 Vault Rock Storage Facility Alternatives	26

4.0	RESULTS.....	27
4.1	Analysis	27
5.0	DISCUSSION.....	29
6.0	SUMMARY AND CONCLUSIONS	30
7.0	REFERENCES.....	32

LIST OF TABLES

Table 2.1	Environmental Sub-Indicators
Table 2.2	Operational Sub-Indicators
Table 2.3	Economic Sub-Indicators
Table 2.4	Weighting Factors Used in the Decision Matrix
Table 2.5	Weighting Factors for Sub-Indicators
Table 2.6	Example of Scoring System used in the Decision Matrix
Table 3.1	Summary of Potential Waste Rock Storage Facility Options
Table 4.1	Waste Rock Storage Areas Decision Matrix Results
Table 4.2	Summary of Decision Matrix Results

LIST OF FIGURES

Figure 1.1	Location Plan Meadowbank Project
Figure 1.2	General Site Plan
Figure 1.3	Potential Portage Waste Rock Storage Options
Figure 1.4	Potential Vault Waste Rock Storage Options
Figure 2.1	Geochemical and Physical Processes Potentially Resulting in ARD and ML
Figure 3.1	Waste Rock Storage Facility Construction Methods

1.0 INTRODUCTION

A series of Technical Meetings were held in Baker Lake on June 2 and 3, 2005 to review the Draft Environmental Impact Statement (DEIS) for Cumberland Resources Limited (CRL), Meadowbank Gold Project. During these sessions stakeholders requested additional clarification regarding the decision matrix method used to select the waste rock storage facilities for the project. The following report has been prepared to explain in more detail the evaluation process used to select the rock storage facilities for the proposed Meadowbank Gold Project. The decision matrix used to identify the most appropriate rock storage site based on environmental, engineering and economic considerations is presented and explained in greater detail.

Golder Associates Ltd. (Golder) was retained by Cumberland Resources Ltd. (CRL) to identify and select appropriate waste rock storage facilities for the Meadowbank Gold Project in Nunavut. Two reports were prepared that described the strategy for selecting the rock storage facility:

- Golder Associates Ltd., Report on Alternative Waste and Water Management Plan, Meadowbank Gold Project, Nunavut, March 7, 2005; and
- Golder Associates Ltd., Report on *Mine Waste and Water Management, Meadowbank Gold Project, Nunavut*, March 5, 2004.

A Multiple Accounts Analysis (MAA), or decision matrix method of analysis, was used to rank and select the best rock storage facility for the project.

Based on the distance between the Portage and the Vault deposits and the volume of storage required, two waste rock storage facilities are required. The Vault Rock Storage Facility near the Vault Pit was selected on the basis of available on-land storage space near this pit, topographic relief, and the desire to have the facility located within the same watershed as the open pit. The rock storage facility near the Portage deposit (called Portage Waste Rock Storage Facility) was selected to contain waste rock generated from the Portage and Goose Island open pits.

Only one suitable site location was identified for the Vault Rock Storage Facility. Four options were evaluated for the Portage Rock Storage Facility using a decision matrix method of analysis. The best overall location selected for the waste rock was located north from Second Portage Lake, with a relatively small footprint.

The alternative analyses and subsequent revision to the initial waste rock storage facility location was conducted as the volume of waste rock was reduced and the option to store a portion of the waste rock within open pits became available, during the completion of the feasibility study.

Primary objectives established for the waste rock storage facility (or facilities) were:

- Minimize potential long-term environmental impacts (including ARD generation, metal leaching, seepage to the underlying groundwater regime);
- Maximize ease of water management during operation;
- Maximize ease of decommissioning/closure;
- Minimize catchment area impacted;
- Minimize dust generation;
- Minimize visual impact;
- Minimize areas of fish bearing lakes impacted;
- Minimize footprint area (to reduce the volume of affected runoff);
- Minimize the potential for geotechnical hazards (including slope instability, seismic risk); and
- Minimize haul costs.

1.1 Physical Setting

The proposed Meadowbank Gold Project is located approximately 70 km north of Baker Lake, Nunavut, as shown in Figure 1.1.


The site area consists of low, rolling hills with numerous small lakes. Laterally extensive deposits of glacial till cover the area, with thicknesses typically of 2 to 4 meters. Bedrock consists of a sequence of Archean greenstone (ultramafic and mafic flow sequences) and metasedimentary rocks. The area has low seismic activity.

The site has vegetation cover interspersed with bedrock outcrops and continuously aggrading surfaces. The vegetation includes lichens, mosses, shrubs, heaths, grasses and sedges (CRL, 2003).







No vital caribou areas or protected wildlife areas have been identified in close proximity to the site (CRL, 2003). The area is not regularly used for hunting due to its remoteness from Baker Lake and relatively low abundance of wildlife (CRL, 2003).

Water quality in the lakes is excellent, however, the lakes are nutrient poor and are classified as ultra-oligotrophic and hence have low fish productivity (CRL, 2003).

The annual average air temperature at the site is about -11.3°C, based on site data collected between 1997 and 2004, and has an annual precipitation of less than 200 mm. The depth of permafrost is estimated to range from about 450 meters to about 550 meters, but varies based on proximity to lakes. Taliks typically are located beneath bodies of water with depth exceeding 2 to 2.5 meters. The depth of the active layer ranges from about 1.3 meters in areas of shallow overburden and up to 4 meters adjacent to lakes.



LEGEND

-  Meadowbank Project
-  Town/Village
-  Provincial Border
-  Water
-  Primary Highway
-  Railroad

REFERENCE

Base digital data obtained from ESRI Inc.,
DATUM: WGS84 PROJECTION: Geographic

200 0 200 Kilometers
Scale - 1:10,000,000

PROJECT				CUMBERLAND RESOURCES LTD.			
TITLE				LOCATION PLAN MEADOWBANK PROJECT			
		PROJECT No. 05-1413-036A		SCALE AS SHOWN		REV. 0	
		DESIGN	CJC 26 Sep. 2005	FIGURE 1.1			
		GIS	CDB 26 Sep. 2005				
		CHECK	CJC 26 Sep. 2005				
		REVIEW					

1.2 Planned Mining Operations

A general site plan is shown in Figure 1.2. The mine plan estimates that 22 million tonnes of ore will be produced over the mine life of approximately 8.3 years. The project consists of several gold bearing deposits within reasonable proximity to one another. Mining of the deposits will primarily be performed as a truck and shovel, open pit operation. Ore is to be transported to a central plant site for processing.

Approximately 173 million tonnes of waste rock will be produced, with approximately 68 million tonnes (intermediate volcanic rocks) from the Vault Pit and 104 million tonnes (iron formation, intermediate volcanic and ultramafic rocks) from the Portage and Goose pits. Ultramafic rocks are not expected to be acid generating. Some of the intermediate volcanic rocks from the Vault Deposit are potentially acid generating. All other waste rock and the tailings are potentially acid generating.

Waste from the pits will be used as construction material for the dikes, tailings dam, roads and general site construction. Excess waste will be deposited in two waste dumps: 1) the Vault Rock Storage Facility located to the West of the Vault Pit and 2) the Portage Rock Storage Facility located to the north and east of Portage Pit. In addition, following Year 6, waste rock will be stored in empty sections of the Portage Pits.

1.3 Decision Matrix Models

Decision matrix types of analyses are also sometimes referred to as Multiple Accounts Analyses (MAA) or alternatives analyses. These types of analyses have been successfully used as site selection tools for mining facilities and related decision processes including at: Zortman and Landusky Mine Sites, Montana (Shaw et al., 2001), Red Dog Mine, Alaska (Northern Miner, 2005), and Questa Molybdenum Mine, New Mexico (MolyCorp Watch Project, 2005). Numerous papers have been published on these types of analyses including: Robertson and Shaw (1998 and 1999), Caldwell and Robertson (1983), Vick (1990), Brown (2002), Decision – Makers Field Guide (2005).

Similar types of analyses are also used in the fields of risk assessment, risk management, selection of the best available technologies or options for environmental remediation projects, resource planning, and sustainable development (Canter, 1985; International Atomic Energy Agency, 2000; CH2MHill, 2004, Robson Valley Land and Resource Management Plan, 1999).

1.4 Meadowbank Waste Rock Facility Selection Process

The mining operations (open pits) for the Meadowbank project are located in two main areas, as shown on Figure 1.2:

- Vault Area which consists of the Vault Open Pit; and
- Portage Area which consists of the North Portage Pit, Third Portage Pit and Goose Island Pit.

The use of two separate waste rock storage facilities for each area was judged as being most efficient.

The Portage rock storage facility and the Vault facility were selected based on consideration of the following criteria:

- The potential for long-term environmental impacts, including ARD generation and metal leaching;
- Ease of water management during operation and closure;
- Ease of decommissioning and closure;
- Impact on lakes and catchment areas;
- Visual impact;
- Footprint size to reduce the volume of affected runoff;
- The potential for geotechnical hazards, such as slope instability and response to seismic activity; and
- Haulage costs.

1.4.1 Potential Rock Storage Facilities

Potential storage locations and design footprints for the Rock Storage Facilities were identified in the area of the proposed mine site that would accommodate the predicted volume of waste rock. Alternatives for the Portage and Vault Rock Storage Facilities are shown on Figures 1.3 and 1.4.


The best alternative for the storage of the waste rock from the Vault pit is on a broad area of land immediately to the west of the open pit area. A cover layer of non-PAG rock is not presently required at the Vault waste rock storage facility because this rock is considered to be non-PAG. Further testing and monitoring during operations will be completed to confirm this.

To select an appropriate location for waste rock in the Portage Area four initial sites were identified (Golder, 2004). Portage Rock Storage Facilities included two additional alternatives (A and B) for Option A. These were evaluated in the Alternative Waste and Water Management Plan (March 7, 2005). The final selection process involved three main steps:

- Identifying potential locations;
- Developing a decision matrix model upon which the locations would be evaluated; and
- Evaluating each facility using the model and selecting the best overall facility.

The remaining portion of this report focuses on the process used to select the final locations for the waste rock storage facilities.

REVISION DATE: 05/10/13 3:19pm By: sreddy CADD FILE: N:\Bur-Graphics\Projects\2005\1413\05-1413-036A\1050\CAD\1100 Mine Waste and Water Management\051413036A-1100-1.2.dwg




REFERENCES

- 1) Drawing taken from AMEC, Drawing # A1-131395-100-C-0001.

LEGEND

SD: SADDLE DAM

PROJECT		CUMBERLAND RESOURCES LTD.			
TITLE		GENERAL SITE PLAN			
	PROJECT No.	05-1413-036A	FILE No.	051413036A-1100-1.2	
	DESIGN	CJC	30SEP05	SCALE	AS SHOWN
	CADD	WLI	30SEP05	REV.	
	CHECK	CJC	30SEP05	FIGURE 1.2	
REVIEW					

1.4.2 Meadowbank Decision Matrix Model

The development of the decision matrix model for the Portage Rock Storage Facility involved developing a site specific list of criteria that would be utilized to evaluate and rank the facilities. The criteria covered three main areas:


- Environmental factors;
- Operational factors; and
- Economic factors.

Each of the factors was further subdivided into sub-indicators, in order to evaluate specific aspects. Weightings were assigned to each factor and sub-indicator.



Each facility option was then evaluated based on the sub-indicator and a relative score was assigned. These scores were then multiplied by the weighting factors and summed to give the overall score. The options were ranked according to the overall score, with the highest score indicating the preferred option.

Quantitative methods were utilized to assign the relative scores where possible, however some sub-indicators necessitated the use of qualitative assessment. Judgement and perception of the individual conducting the analyses is inevitably a part of any such decision making system, both in the assignment of qualitative scores and of weighting factors.

The weighting factors were specifically designed to place a higher significance on the environmental factors, and less on the operational and economic factors.




REVISION DATE: 05/10/21 9:53am By: sreddy CADD FILE: N:\Bur-Graphics\Projects\2005\1413\05-1413-036A\1050\CAD\2000 Commitments\051413036A-2000-1.4.dwg



REFERENCES

1) AMEC Americas Ltd., Drawing Number A1-131395-100-c-0001 (100-c-0001.dwg), Meadowbank Feasibility Study, April 2005.

PROJECT		CUMBERLAND RESOURCES LTD.	
TITLE			
VAULT ROCK STORAGE OPTIONS			
	PROJECT No.		05-1413-036A
	FILE No.		051413036A-2000-1.4
	DESIGN	CJC	17OCT05
	CADD	GG	17OCT05
CHECK	CJC	17OCT05	FIGURE 1.4
REVIEW	CJC	17OCT05	
SCALE		AS SHOWN	REV. 0

2.0 MEADOWBANK DECISION MATRIX METHOD OF ANALYSIS

This section will explain in greater detail the decision matrix component of the site selection analyses, and each of the sub-indicators used in the selection process, under the three primary factors of environmental, operational and economics. Sub-indicators were chosen to evaluate a wide spectrum of potential impacts, without double counting impacts.

2.1 Environmental Factors

The European Commission published a Report on Best Available Techniques (BAT) reference document for Management of Tailings and Waste-Rock in Mining Activities (2004). This document was developed in response to a Communication from the European Commission COM(2000) 664 [COM(2003) 319 final, 2.6.2003] on the 'Safe Operation of Mining Activities' that was a follow-up action to tailings dam bursts that occurred in Aznalcollar and Baia Mare. The follow-up measures included: an elaboration of the BAT Reference Document based on an exchange of information between European Union's Member States and the mining industry. The document was developed in response to the Commission's initiative and in anticipation of the proposed Directive on the management of waste from extractive industries (European Commission, 2004). The following key environmental issues or impacts associated with tailing and waste rock facilities were listed in this document:

- Site specific issues relating to facility location and relative land take;
- Potential emissions of dust and effluents during operation (to air, land and water) and their impact;
- Potential emissions of dust and effluents after closure (to air, land and water) and their impact;
- ARD and metal leaching generation, release and impact;
- Potential releases due to failures of facilities (i.e., burst or collapses of containment berms or dams); and
- Site rehabilitation and aftercare to minimize environmental impacts.

Table 2.1 presents a list of the sub-indicators that were used to evaluate the environmental impact of the various waste rock storage options. The following subsections briefly describe each of these sub-indicators and how they were evaluated.

Table 2.1: Environmental Sub-Indicators

	Sub-Indicators
Environmental Factors	Sub-catchment area
	Footprint area
	Area of lakes impacted
	Potential for geotechnical hazards ¹
	Visual impact
	Potential for dust generation
	Potential for seepage to groundwater
	Potential for ARD generation
	Potential for ML

Note:

¹ Includes consideration of foundation conditions, and impact of seismicity.

2.1.1 Sub-catchment Area

A catchment is an area of land bounded by natural high points (hills, ridges and mountains). Surface water (rainfall and runoff) flows down through the catchment area and into one low point (a creek, river or bay). Catchment areas may be further divided into sub-catchments, typically each sub-catchment area will have homogeneous physical characteristics.

A sub-catchment area for the purpose of this evaluation was defined as the primary portion of the watershed that would be impacted by the waste rock facility. The total sub-catchment area (hectares) was used to assign the relative scores and determine the impact of each option. Options having lower sub-catchment areas are preferable to those with greater areas, and hence were assigned a relatively higher score.

2.1.2 Footprint Area

The footprint area is defined as the area covered by the waste rock both on land and in water. The total footprint area, in hectares, was used to assign the relative scores and judge the impact of each facility location. The site having the smallest footprint area was given the highest relative score and the other options were assigned a lower score, relative to their footprint area.

2.1.3 Area of Lakes Impacted

The area of lakes impacted by the waste rock facility (footprint) was calculated and quantitatively used to assign relative scores. The site with no or little impact on lakes is most desirable, and would therefore receive the highest score.

2.1.4 Potential for Geotechnical Hazards

The relative potential for geotechnical hazards to occur at each facility, and in turn the potential release of contaminants into the environment was qualitatively judged and a value of low, moderate or high was assigned. The assessment included a consideration of foundation conditions, and seismic impacts. Depending on the type of waste rock facility and site conditions, failures of the containment facilities or structures may occur and cause the release of contaminants to the environment. The potential for geotechnical hazards of each option was qualitatively judged and a score assigned. The facility with the lowest potential for failure was assigned the highest score and the facility with the highest potential was assigned the lowest score.

2.1.5 Visual Impact

The relative visual impact for each facility was qualitatively judged and a value of low, moderate, or high was assigned. This factor considered such items as height, shape, and contrast with the surrounding terrain. A facility with a low profile and that would blend in with the surrounding area would receive a higher relative score than a facility with a high topographic relief that did not blend into the surrounding terrain.

2.1.6 Potential for Dust Generation

The relative potential for each facility to generate dust both during operation and after closure was qualitatively judged and a value of low, moderate, or high was assigned. This factor is dependent on grain size of material, methods of erosion protection, topographic profile, exposure of the site to wind, haulage distance and the planned method for closure. A facility with a closure plan that includes covering the waste rock, thus reducing or eliminating the potential for dust would receive a higher score. A facility that remained exposed after mine closure would have a lower value assigned.

2.1.7 Potential for Seepage to Impact Groundwater

The relative potential for seepage from each facility to impact groundwater resources during operation and closure was qualitatively judged and a value of low, moderate, or high was assigned. This factor is primarily dependent on the method of containment, including any steps that will be taken to control seepage into the groundwater. Methods

of collecting and treating runoff from the site and generation of runoff are considered during the assessment of this sub-indicator. Facilities that generate low rates of seepage or runoff and with low levels of contamination would receive a high relative score in comparison to facilities that are expected to generate high quantities of seepage or runoff with a high concentration of contaminants (including metals and low pH).

One method of reducing the potential for groundwater impact may be achieved by controlling the flux of water through the facility, thus reducing the potential for groundwater impact. This may be controlled by the surrounding berms and diversion channels and liner and cap or low permeability boundary. Facility liners or caps may be man-made or natural, such as low permeability rock, till, clay, permafrost, or synthetic materials (i.e., high density polyethylene).

2.1.8 Potential for Acid Rock Drainage (ARD) Generation

Geochemical testing has shown that much of the waste rock that will be produced from mining operations may contain metal sulphides and will have the potential to generate ARD. The relative potential for each facility to generate ARD during mine operation and after closure was qualitatively judged and a value of low, moderate, or high was assigned. This factor is primarily dependent on the facility location, planned method of design, and the closure that may minimize the generation of ARD or contain and treat potential contaminated water.

Sulphides oxidize when exposed to oxygen and air, which in turn creates an acidic metal-laden leachate which can be generated over a prolonged period of time if acid buffering minerals are not present. The rate of generation of ARD is accelerated with fine particles as the surface area potentially exposed to oxygen is much greater, which is typically the case when dealing with tailings and processed mine waste. Other factors that may increase the rate of ARD generation are: high oxygen concentration, high temperature, low pH, and bacterial activity (European Commission, 2004).

Although quarry sites 8, 10, 21 and 22 from the proposed access road have a sulphide content that is expected to be too low to generate ARD, consideration should be given to avoiding these quarry sites as a precautionary measure. The quality of runoff contacting the open quarry sites and the excavated rock should be monitored during construction to document the effect of exposure of the quarry rock on receiving water quality.

2.1.9 Potential for ARD Generation After Closure

The relative potential for each facility to generate ARD after closure was qualitatively judged and a value of low, moderate, or high was assigned. This factor is primarily dependent on the planned method for closure which may reduce or control generation of

ARD. As discussed in the previous subsection, facilities that in the long term control factors that lead to acid generation would receive a relatively higher score in comparison to facilities that do not control these factors. For example a permafrost encapsulated facility would receive a higher score in comparison to above ground facilities exposed to air and precipitation.

2.1.10 Potential for Metal Leaching (ML) Generation During Operation

Geochemical testing has shown that waste rock generated at Meadowbank will have the potential to generate ML. The impact of metals released into the environment may be toxic, but depends on many factors including: concentration, pH, temperature, and water hardness (European Commission, 2004). Figure 2.1 schematically shows some of the primary geochemical and physical processes and their interaction that may lead to the generation of ARD and the potential release of metals (ML).

The relative potential for each facility to generate ML during mine operation was qualitatively judged and a value of low, moderate, or high was assigned. Facilities that reduce or eliminate the generation and/or transmission of soluble metals to the environment (i.e., hydraulic containment) would receive a high relative score, in comparison to facilities that do not control metal leaching.


Metals may leach from waste rock facilities and controlling the flux of water through and out of the waste rock storage facility may have the most significant impact on reducing contamination. Therefore, facilities that isolate waste rock from natural water sources (groundwater, surface water and precipitation) through the use of low permeability liners and covers, containment berms and diversion ditches, and prevent flow out of the facility will reduce the impact on the surrounding environment.

2.1.11 Potential for ML Generation After Closure

The relative potential for each facility to generate ML after closure was qualitatively judged and a value of low, moderate, or high was assigned. This factor is primarily dependent on the planned method for closure which may reduce or control generation and migration of ML. The evaluation of this sub-indicator is the same as discussed in the previous subsection.

2.1.12 Impact on Fish and Fish Habitat

The relative potential for each facility to have an impact on fish and/or fish habitat was qualitatively judged and a value of low, moderate, or high was assigned. Facility options that would have no impact on fish would receive a high relative score compared to options that would impact a larger fish population. This factor considered the fish habitat survey, bathymetric and aquatic ecosystem information.



Source: European Commission, 2002.

PROJECT

CUMBERLAND
RESOURCES LTD.

TITLE

**GEOCHEMICAL AND PHYSICAL PROCESSES
POTENTIALLY RESULTING IN ARD AND ML**



PROJECT No.	05-1413-036A	FILE No.	ARD & ML
DESIGN	CC	28SEP05	SCALE NTS
CADD	VEE	28SEP05	REV.
CHECK	CC	28SEP05	
REVIEW			

FIGURE 2.1

2.2 Operational Factors

Table 2.2 presents a list of the sub-indicators that were used to evaluate the operational factors for the waste rock facility options under consideration. The following subsections briefly describe each of these sub-indicators and how they were evaluated.

Table 2.2: Operational Sub-Indicators

Operational Factors	Sub-Indicators
	Ease of operation
	Distance from open pit
	Potential for delays due to freezing
	Construction risk
	Disposal system has precedent in arctic environment

2.2.1 Ease of Operation

The relative ease of operation of each facility was qualitatively judged and a value of low, moderate, or high was assigned. Various factors were considered including such items as: number of personnel, energy requirements and mechanical components.

2.2.2 Distance from Mill

The nominal distance from the mill to the proposed waste rock facility location was measured. This value was used to assign a relative score for each facility. The facility closest to the pit would receive the highest relative score, and the facility located furthest from the pit would receive the lowest relative score. Increased distance results in increased transportation costs, but also increased risk of accidents and hence environmental impacts, as well as additional dust generation.

2.2.3 Potential for Delays due to Freezing

The relative potential for delays to be caused due to freezing are considered negligible for the waste rock facility.

2.2.4 Construction Risk

The relative potential for delays or problems to occur during construction was qualitatively judged and a value of low, moderate, or high was assigned. Various factors including type of construction, likely construction schedule, and site conditions, were

taken into account. Facilities that utilized local materials that can be placed on a year round basis received a higher score. In comparison, facilities that required a large number of components to be imported, and that could only be delivered by ship and during summer months when the port is open and free of ice, received a lower score.

2.2.5 Disposal System has Precedent in Arctic Environment

The relative precedent for use of the proposed waste rock facilities was qualitatively judged based on the evaluators' experience and published literature. Similar design and construction of waste rock dumps in cold climates include the Lupin, Ekati and Diavik mines.

A report titled Acid Mine Drainage in Permafrost Regions: Issues, Control Strategies and Research Requirements (Dawson and Morin, 1996) outlines perspectives on issues related to ARD from tailings and mine waste rock in permafrost conditions. Site information from 18 active and abandoned sites show that waste rock at only two sites in the Yukon and North West Territories have the potential to generate significant acid mine drainage (AMD). Consequently, disposal of potentially acid generating waste rock followed by permafrost encapsulation has been shown to be an effective method for managing acid rock drainage and metal leaching.

2.3 Economic Factors

Table 2.3 shows the sub-indicator factor that was used to evaluate the economic benefits of each of the waste rock facility options that were considered.

Table 2.3: Economic Sub-Indicators

Economic Factors	Sub-Indicator
	Total present value of costs (initial costs + delayed costs)

The previous report considered two economic factors, overall present value cost, and initial capital costs. To further reduce the influence of economic factors on the decision making process, the waste rock facility selection matrix was revised and now only considers the total present value cost.

The total present value costs for each facility were estimated and used to quantitatively rank the facilities. This value includes initial construction costs, facility operational costs over the 8.3 year mine life and closure costs. An 8% interest rate was used for these calculations. The resulting total costs were then ranked and scored, with the lowest cost allocated the highest score.

2.4 Weighting Factors and Scoring

Weighting factors amongst the three primary categories were assigned such that environmental factors had the most significance, followed by operational factors, and lastly economic factors (Table 2.4).

Table 2.4: Weighting Factors Used in the Decision Matrix

Factor	Contribution to Overall Weighting
Environmental	50 %
Operational	30 %
Economic	20 %

The weighting factors assigned to each of the sub-indicators is shown in Table 2.5.

Table 2.5: Weighting Factors for Sub-Indicators

Factor	Sub-Indicator	Relative Weighting	Max. Possible Score	Max. Possible Weighted Score¹	Max. Possible Category Score
Environmental	Sub-catchment area	5	9	45	396
	Footprint area	4	9	36	
	Potential for generating dust	6	9	54	
	Potential for Acid Rock Drainage (ARD) generation during operation	7	9	63	
	Potential for metal leaching (ML) during operation	6	9	54	
	Potential for seepage to impact groundwater	6	9	54	
	Potential for geotechnical hazards ²	3	9	27	
	Lake area impacted	4	9	36	
	Visual impact	3	9	27	
Operational	Difference between crest and adjacent land	5	9	45	234
	Ease of Water Management	7	9	63	
	Catchment Impacted	6	9	54	
	Ease of operation Decommissioning/closure	8	9	72	
Economic	Distance from north edge of North Portage Pit	18	9	162	162
TOTAL					792

Notes:

¹ Values represent the maximum score, if 9 points was assigned for each sub-indicator.² Includes consideration of foundation conditions, impact of seismicity, and height of structure.

Each of the sub-indicators was assigned a score between 1 and 9 points (Robertson and Shaw, 1999). The scores provide a relative ranking between the options under consideration with the best option receiving a score of 9. All subsequent options are then compared to the 'best' option and assigned a lower score. An example of the scoring method is presented in Table 2.6.

Table 2.6: Example of Scoring System used in the Decision Matrix

Option	Foot Print Area	Points	Notes
A	30 ha	9	9 points awarded for least footprint area (BEST)
		8	
		7	
		6	
C	60 ha	5	9 points x 30 ha (least area)/60 ha = 5 points
		4	
B	90 ha	3	9 points x 30 ha (least area)/90 ha = 3 points
		2	
		1	

2.5 Calculations

For each sub-indicator, the point value was multiplied by the weighting to give a "weighted score" (see Table 2.5 for a sample calculation). Then all of these scores were summed to give an overall rating score for each of the three primary factors, environment, operation and economic.

Operational Factor Score = "Ease of operation weighted score" + "Distance from mill weighted score" + "Potential for delays due to freezing score" + "Construction risk score" + "System precedent score"

The scores were then summed to give one overall total score.

Overall Score = "Environmental Factor Score" + "Operational Factor Score" + "Economic Factor Score"

3.0 ANALYSIS OF MEADOWBANK WASTE ROCK STORAGE FACILITIES


3.1 Description of Potential Waste Rock Storage Methods

The Meadowbank Project proposes the use of on-land rock storage methods followed by permafrost encapsulation for waste rock disposal. The revised mining plan has not yet been finalised in terms of mining sequence, waste rock disposal and mining areas, however assumptions have been made to allow completion of a conceptual level assessment of alternative waste rock management plans. Figure 3.1 shows waste rock storage facility construction methods.


At closure, a capping layer of ultramafic rock would be placed over the Portage Rock Storage Facility. The thickness of capping material would exceed the active layer thickness, such that the waste rock would be maintained in a frozen state, year round to constrain the active layer within relatively inert materials. The potential acid generating waste rock below the capping layer will freeze, reducing the low rates of acid mine drainage (AMD) over the long-term.

Water seepage and runoff from the waste rock of the Vault Rock Storage Facility is expected to be of suitable quality to allow discharge to the environment without treatment and capping of this facility is therefore not proposed.


HEAPED CONSTRUCTION




CONSTRUCTION CONFIGURATION



END-DUMPED CONSTRUCTION



RE-SLOPED CONFIGURATION



Freeze Controlled ARD Strategies

Climate Controlled ARD Strategies

Not to Scale

Reference: MEND 1.61.2, 1996

PROJECT		CUMBERLAND RESOURCES LTD.			
TITLE		WASTE ROCK STORAGE FACILITY CONSTRUCTION METHODS			
		PROJECT No.	05-1413-036A	FILE No.	FIGURE
DESIGN	CC	05OCT05	SCALE	NTS	REV.
CADD	SS	05OCT05	FIGURE 3.1		
CHECK	CC	05OCT05			
REVIEW					



3.2 Description of Potential Waste Rock Storage Facility Areas

Due to the distance between the Vault open pit and other pits, it was determined that two rock storage facilities were required: one facility near the Portage Pit and Goose Pits; and one near the Vault open pit. Figure 1.2 shows the general site plan.

Alternatives that were considered are shown for the Portage and Vault rock storage facility in Figures 1.3 and 1.4 respectively, and are described in the following sections.

3.2.1 Portage Rock Storage Facility Alternatives

Figure 1.4 shows the alternatives for the Portage Rock Storage Facility. Four potential locations were considered and are listed in Table 3.1.

Table 3.1: Summary of Potential Portage Waste Rock Storage Facility Options

Option	Location	Footprint
A	North of Second Portage Arm	Small
B	North of Second Portage Arm	Large
C	East of Vault Haul Road	Small
D	East of Vault Haul Road	Large

Two options were located north of Second Portage Arm (Options A and B); and two east of Vault Haul Road (Option C and D). The following sections briefly describe each of areas and the ancillary components and structures for each of the options that were evaluated.

North of Second Portage Arm (Option A and B)

Recent revisions to the management of waste from the pits resulted in a reduction in surface storage requirements for the Portage rock storage facility (RSF) to about 34 mm³. Ancillary components and structures are similar among the four sites and include a diversion ditch, sump pumps and attenuation pond. Primary differences are related to the size of the foot print. The maximum elevation of adjacent topography is 192 m.

Option A was the smallest footprint developed for the RSF and has a crest elevation of 210 m and estimated capacity of 34 mm³, a height of 60 m, a footprint of 58 ha and a surface area of 66 ha. Option A was selected as the preferred alternative.

Option B was a larger footprint in the same area.

Based on the current study the proposed advantages to Option A includes the following benefits:

- The larger northernmost of the two small lakes will remain undisturbed;
- Option F has the smallest footprint and surface area. Consequently, runoff from the dump for Alternative B will be less than for the original designs (Options A & B) as well as Option E;
- The total area of non-contact water to be diverted is minimized, and hence the quantity of water will increase as a result of the decrease in size of the RSF; and
- Capping the RSF will reduce the potential for post-closure dust generation and also help ensure that potentially acid generating (PAG) waste rock remains in a frozen state, year round.

Disadvantages to Option A includes:

- A small tributary lake of Second Portage Arm will permanently contain waste rock and will not have any suitable fish habitat or contain fish.

East of Vault Haul Road (Option C and Option D)

Portage Rock Storage Facility Options located east of Vault Haul Road include Options C and D. Option C has an estimated crest elevation of 176 m, and estimated capacity of 35 Mm³. Height is estimated at 30 m, with a footprint of 126 ha and a surface area of 195 ha.

Option D was located in the same area and had a larger footprint which is not required under the current design concept. Thus Option C was considered the preferred option for the Vault RSF.

- Capping of the RSF will reduce the potential for post-closure dust generation and also help ensure that PAG waste rock remains in a frozen state, year round.

Disadvantages to Option C and D include:

- Drainage is outside of drainage basin of main mine facility area; and
- Increased impacts to fish bearing lakes.

3.2.2 Vault Rock Storage Facility Alternatives

Figure 1.4 shows the alternatives for the Vault Rock Storage Facility. There are few suitable locations for a waste rock storage facility near the Vault pit owing to the presence of numerous lakes adjacent to Vault Lake and the lack of topographical relief in the immediate area, which limits the height to which a rock storage facility could be constructed without becoming visible at great distance from the site. In addition, placing waste rock in areas south of Vault Lake would affect a sub-watershed that does not drain toward the Vault open pit.

- Immediately west of the Vault pit (Option A): This alternative consists of a broad, relatively flat area within the catchment area of the Vault pit. This alternative offers the advantage of allowing the storage facility to be developed with a low profile, reducing the potential visual impact as well as reducing the potential impact to wildlife movement. The location of Option A results in the least travel distance for waste rock haulage and disposal.
- South of the Vault deposit (Options B1 and B2). This alternative was rejected as it places the waste rock material within a catchment area and sub-watershed that previously remained unaffected.
- On-land storage to the east of Vault Lake (Option C). This alternative was rejected due to the small area in which to store the waste rock, and due to the distance from the deposit area, which would result in an increase in the overall footprint area for the mine development, as well as an increase in haulage costs. The smaller area in which to store the material would result in a waste dump with a higher final elevation, resulting in visual impact as well as exposure to wind dispersion. The additional distance for haulage would require the construction of additional roads. Increased traffic would result in increased levels of particulate matter (including dust and exhaust) to the atmosphere to be transported and deposited elsewhere.
- Disposal into Wally Lake (Option D). This alternative was rejected because there is no convincing evidence to suggest that placing the Vault waste rock material in a submerged environment will have less impact than placing on land. Placing the waste rock into Wally Lake would un-necessarily impact on fish habitat within that lake.

The best alternative for the storage of the waste rock from the Vault pit is on a broad area of land immediately to the west of the open pit area. A cover layer of non-PAG rock is not presently required at the Vault waste rock storage facility because this rock is considered to be non-PAG. Further testing and monitoring during operations will be completed to confirm this.

4.0 RESULTS

4.1 Analysis

Options for the Portage Rock Storage Facility for the proposed Meadowbank Mine were then analyzed using the Multiple Accounts Analysis decision matrix method of analysis described in Section 2.0. Table 4.1 presents the results of this analysis. The individual scores for each sub-indicator are shown along with the summed scores for environmental factors, operational factors and economic factors. Table 4.2 summarizes the results.

Table 4.2: Summary of Decision Matrix Results

Factor	Rock Storage Options			
	A	B	C	D
	North of Second Portage Arm	North of Second Portage Arm	East of Vault Haul Road	East of Vault Haul Road
	Small foot print (58ha)	Large foot print (296 ha)	Small foot print (126 ha)	Large foot print (222 ha)
Environmental	268	199	241	188
Operational	148	170	33	51
Economic	144	90	162	116
TOTAL	560	459	436	355

Option A scored the highest among the four Portage Rock Storage Facility options.

TABLE 4.1: WASTE ROCK STORAGE AREAS DECISION MATRIX			ROCK STORAGE OPTIONS (Portage and Goose Pits)				SCORE, S _{IND} (1=worst 9=best)				WEIGHTED SCORE			
Key Indicators	Sub-Indicators	Weighting, W _{IND}	Stockpile Option A	Stockpile Option B	Stockpile Option C	Stockpile Option D	A	B	C	D	A	B	C	D
			North-west from Second Portage Lake	North-west from Second Portage Lake	East from Vault Haul Road Small Footprint	East from Vault Haul Road Large Footprint								
Key Details	Crest Elevation to Store 60 Mm3		210m	172m	210m	178m								
	Maximum elevation of nearby land		El. 192m	El 192m	El. 164m	El. 164m								
	Maximum height from foundation		60 m	28 m	71 m	94 m								
	Total Surface Area		660,000 m2	3,000,000 m2	1,280,000 m2	2,200,000 m2								
	Capping volume (assumes 2m thickness)		1,3200,000 m3	6,000,000 m3	2,560,000 m3	4,400,000 m3								
Environmental Factors	Sub-catchment area	5	147 ha	426 ha	215 ha	268 ha	9	3	4	5	45	15	20	25
	Footprint area	4	58 ha	296 ha	126 ha	222 ha	8	4	9	5	32	15	36	20
	Area of lakes impacted	4	3 ha	29.2 ha	26.8 ha	34.2 ha	9	3	5	1	36	12	20	4
	Potential for geotechnical hazards ¹	3	Moderate	Low	Moderate	Moderate	2	9	2	2	6	27	6	6
	Visual Impact	3	Moderate	Low-Moderate	Moderate	Low-Moderate	5	9	6	7	15	27	18	21
	Potential for dust generation	6	High	Moderate	Moderate	Moderate	4	9	3	6	24	54	18	36
	Potential for seepage to groundwater	6	Moderate	Moderate	Moderate	Moderate	8	6	9	7	48	36	54	42
	Potential for ARD generation	7	Moderate	Moderate to High	Moderate	Moderate to High	8	1	9	4	56	7	63	28
	Potential for Metal Leaching	6	Low	Low	Low	Low	1	1	1	1	6	6	6	6
	Sum of Environmental Weightings, SW _{ENV}	44	Weighted Subtotals for Environmental Factors, IND _{SCORE} = S(W _{IND} x S _{IND})				268	199	241	188				
Operational Factors	Difference between crest and adjacent land	5	+13 m	-20 m	+46 m	+14 m	6	9	1	6	30	45	5	30
	Ease of water management	7	Good	Good	Good	Good	8	9	2	1	56	63	14	7
	Catchment impacted	6	Same as Mine	Same as Mine	Adjacent catchment	Adjacent catchment	9	9	1	1	54	54	6	6
	Ease of decommissioning/closure	8	Place dry cover	Place dry cover	Place dry cover	Place dry cover	1	1	1	1	8	8	8	8
	Sum of Operational Weightings, SW _{OPS}	26	Weighted Subtotals for Operational Factors, IND _{SCORE} = S(W _{IND} x S _{IND})				148	170	33	51				
Cost Factors	Distance from north edge of North Portage Pit	18	1,200 m	1,700 m	1,000 m	1,4 00 m	8	5	9	6	144	90	162	116
	Sum of Economic Weightings, SW _{COST}	18	Weighted Subtotals for Cost Factors, IND _{SCORE} = S(W _{IND} x S _{IND})				144	90	162	116				
TOTAL OPTION SCORE = SIND _{SCORE}			560	459	436	355	560	459	436	355				

Notes

1. Includes consideration of foundation conditions, impact of seismicity, and height of structure

2. Relative capital cost for comparison only.

3. Value not used in scoring. Value is presented to allow calculation of total cost for comparison purposes.

N:\Final\2005\1413\05-1413-036A\1000[Table 4-1 Waste Rock Decision Matrix_Rev1.xls]Waste Rock Dumps

5.0 DISCUSSION

Only one potential site for the Vault Rock Storage Facility was identified due to environmental factors. Four potential sites (A, B, C, D) were identified for the Portage Rock Storage Facility. Results of the Multiple Accounts Analysis indicated that Option A was the best site overall site for the Portage Rock Storage site.

The primary advantages provided by these site locations are as follows:

- Minimizes potential long-term impacts;
- Minimizes catchment area impact;
- Minimizes height and visual impact;
- Minimizes loss of lake habitat;
- Reduces spatial footprint and surface area;
- Minimizes haul costs;
- Minimizes dust generation during hauling;
- Minimizes risk of haulage accidents and accidental release of waste rock to the environment;
- Improves ease of management;
- Lowest potential for ARD/ML generation;
- Simplifies closure, requiring least amount of borrow materials;
- Low risk of instability of rock storage facility;
- Ease of operation in harsh arctic climates;
- Lowest relative capital cost; and
- Precedence in arctic climate.

6.0 SUMMARY AND CONCLUSIONS

This report has provided an additional explanation on the decision making process used to select waste rock storage facilities (location and technology) for the Meadowbank Gold Project. A decision matrix approach was utilized. Three primary factors were utilized: environmental, operational and economic. Each factor was further subdivided to consider various components. Weighting factors were assigned to each sub-indicator and to the overall factors. Environmental factors were judged as being the most important, and were therefore assigned the highest overall weighting.

There are two waste rock storage facility locations (Vault and Portage). For the Portage Rock Storage Facility, four potential rock storage facilities were identified. These facilities were screened to determine if they met the basic site selection criteria:

- The site was required to have sufficient volume to store planned volume of waste rock;
- The site required the potential to provide additional capacity for waste rock storage;
- The location would permit mine expansion; and
- The location is within catchments of the open pits.

All four options met these criteria, as listed below.

Option	Location Description
Option A*	North of Second Portage Arm – small footprint
Option B	North of Second Portage Arm – large footprint
Option C	East of Vault Haul Road – small footprint
Option D	East of Vault Haul Road – large footprint

*Option A was originally evaluated in Golder, 2004 report. Alternatives (a & b) to the original Option A was evaluated *Report on Alternative Waste and Water Management Plan* (Golder, 2005) and compared to Option A.

The decision matrix analysis was then carried out on these four options. Option A had the highest score in all cases for the rock storage facility options. Thus, the Portage Rock Storage Facility Option A was selected as the best waste rock disposal site for the Portage and Goose Pits. Only one suitable site location was identified for the Vault Rock Storage Facility.

We trust that this report meets your requirements at this time. If you have any additional questions, please do not hesitate to contact the undersigned.

Yours very truly,

GOLDER ASSOCIATES LTD.

Cameron J. Clayton, M.Eng., P.Geo.
Associate, Mining Group

Marke Wong, M.Sc. (Cand.)
Project Manager, Mining, Environment
and Community Affairs

CJC/MW/lba

N:\FINAL\2005\1413\05-1413-036A\1000\RPT-1014_05 CUMBERLAND RESOURCES-EVALUATION OF WASTE ROCK MANAGEMENT ALTERNATIVES.DOC

7.0 REFERENCES

- Brown, Bruce S. 2002. Management of Tailings Disposal on Land. Knight Piesold Consulting.
- Caldwell, Jack A., and Andrew Mac G. Robertson. 1983. Selection of tailings impoundment sites. Die Siviele Ingenieur in Suid-Afrika. Oktober 1983.
- Canter. 1985. Ground Water Pollution Control. CRC – Taylor & Frances, New York.
- CH2MHill. 2004. Clark Fork River Operable Unit, of the Milltown Reservoir / Clark Fork River Superfund Site, Record of Decision, Part 3: Responsiveness Summary, April 2004, U.S. Environmental Protection Agency, Region 8, Montana.
- CRL. 2003. Meadowbank Gold Property, Project Description Report, Cumberland Resources Ltd., March 2003.
- Dawson, R.F. and K.A. Morin, 1996. Acid Mine Drainage in Permafrost Regions: Issues Control Strategies and Research Requirements – MEND Project 1.61.2. Prepared by AGRA Earth and Environmental Limited Calgary, Alberta and Morwijk Enterprises Ltd., Vancouver, B.C. for the Department of Indian and Northern Affairs Canada, Ottawa, Canada CG250047.
- Decision – Makers Field Guide. 2005. Environmental and Water Quality Issues (Chapter 2); Sustainable Development, Technology, and a look to the Future (Chapter 4). Mining in New Mexico, Decision – Makers Field Conference 2005 Taos Region.
- European Commission. 2004. Reference Document on Best Available Techniques for Management of Tailings and Waste-Rock in Mining Activities. July 2004. Sustainability in Industry, Energy, and Transport European IPPC Bureau, Spain. (<http://eippcb.jrc.es>)
- Golder Associates Ltd. 2005. Alternative Mine Waste and Water Management Plan, Meadowbank Gold Project, Nunavut. Prepared for Cumberland Resources Ltd. Golder Associates Ltd., March, 2005. Report No. 04-1413-034/2600.
- Golder Associates Ltd. 2004. Mine Waste and Water Management, Meadowbank Gold Project, Nunavut. Prepared for Cumberland Resources Ltd. Golder Associates Ltd., March 5, 2004. Report No. 03-1413-427-5000.

- International Atomic Energy Agency (IAEA). 2000. Recycle and reuse of materials and components from waste streams of nuclear fuel cycle facilities. January 2000, Waste Technology Section, Austria.
- Molycorp Watch Project. 2005. Current Regulatory Permitting for the Molycorp Mine, Amigos Bravos Friends of the Wild Rivers (NGO, New Mexico). Website: <http://amigosbravos.org/molycorpwatch/permits/index.html> (July 19, 2005)
- Northern Miner. 2005. "Mining Across Alaska – Summaries". The Journal of the Northern Alaska Environmental Center, Summer 2005, Volume XXVII, Number 2.
- Robertson, A. MacG., and S.C. Shaw. 1999. A multiple accounts analysis for tailings site selection. In Sudbury '99 - Mining and the Environment II Proceedings, D. Goldsack, N. Belzile, P. Yearwood and G. Hall (Eds) September 12-16, Sudbury, Ontario, Can. Pages 883-892.
- Robertson, A. MacG., and S.C. Shaw. 1998. Alternative analysis for mine development and reclamation. Proceedings of the 22nd Annual BC Mine Reclamation Symposium, Penticton, BC. Canada, (September 14-17, 1998) pp. 51-62.
- Robson Valley Land and Resource Management Plan – April 1999. Government of British Columbia.
- Shaw, S.C., et al. 2001. Review of the Multiple Accounts Analysis Alternatives Evaluation Process Completed for the Reclamation of the Zortman and Landusky mine Sites. Presented at the 2001 National Association of Abandoned Mine Lands Annual Conference, August 19-22, 2001, Athens, Ohio.
- Vick, Steven G. 1990. Planning, Design, and Analysis of Tailings Dams, BiTech Publishers Ltd., Vancouver. ISBN 0-921095-12-0.

APPENDIX C

Blast Design

Golder Associates Ltd.

500 – 4260 Still Creek Drive
Burnaby, British Columbia, Canada V5C 6C6
Telephone (604) 296-4200
Fax (604) 298-5253



REPORT ON

**BLAST DESIGN
MEADOWBANK GOLD PROJECT
NUNAVUT**

Submitted to:

Cumberland Resources Ltd.
Suite 950, One Bentall Centre
505 Burrard Street
Vancouver, BC
V7X-1M4

DISTRIBUTION:

- 3 Copies - Cumberland Resources Ltd.
- 2 Copies - Golder Associates Ltd.

February 10, 2004

03-1413-427



TABLE OF CONTENTS

<u>SECTION</u>	<u>PAGE</u>
1.0 INTRODUCTION.....	1
1.1 Ore Deposits.....	1
1.2 Mining.....	1
1.3 Deposit Characteristics.....	1
2.0 SUMMARY OF GEOMECHANICAL PROPERTIES	2
2.1 Geotechnical Model.....	2
2.2 Rock Properties	2
2.3 Discontinuity Properties.....	3
2.4 Pit Slope Design Configurations.....	4
2.5 Permafrost	5
2.6 Groundwater.....	6
3.0 BLAST DESIGN	7
3.1 Lilly's Blastability Index.....	7
3.1.1 Blast Hole Diameter, D (mm).....	8
3.2 Explosive Selection	9
3.2.1 ANFO.....	9
3.2.2 ANFO/Emulsion Mixtures	9
3.3 Blast Design Assumptions.....	10
3.4 Production Blast Design	11
3.4.1 Rock Fragmentation	13
3.5 Controlled Blasting for Final Walls.....	13
3.6 Nitrate/Ammonia Considerations.....	15
3.7 Blast Induced Vibration.....	15
3.7.1 Estimates of Peak Particle Velocity	16
3.7.2 Minimum Setback Distance for 50 mm/s PPV Guideline	20
3.8 Instantaneous Pressure Change	22
4.0 CLOSURE.....	26
REFERENCES	28

LIST OF TABLES

Table 2-1	Summary of Rock Strength Properties.....	3
Table 2-2	Summary of Main Discontinuity Properties – Portage and Goose Island Deposits	3
Table 2-3	Summary of Main Discontinuity Properties – Vault Deposit	4
Table 2-4	General Bench Configurations	4
Table 2-5	Footwall Design Criteria	5
Table 3 1:	Blastability Index and Rock Factor for Meadowbank Rock Types	9

Table 3-2	Typical Properties of ANFO/Emulsion Mixtures.....	11
Table 3-3	Blasthole Parameters	12
Table 3-4	Blast Patterns	12
Table 3-5	Charge Table – Wet Blastholes (Emulsion:ANFO 70:30).....	13
Table 3-6	Charge Table – Dry Blastholes (Emulsion:ANFO 30:70)	13
Table 3-7	Predicted Fragmentation.....	14
Table 3-8	Charge Table – Trim Blast	15
Table 3-9	Charge Table – Buffer Blast.....	15
Table 3-10	Preliminary Estimate of Peak Particle Velocities based on Production Blasting (420 kg charge weight per delay; 12 m bench height, 229 mm blasthole)	19
Table 3-11	Preliminary Estimate of Peak Particle Velocities based on Production Blasting (250 kg charge weight per delay; 12 m bench height, 165 mm blasthole)	19
Table 3-12	Preliminary Estimate of Peak Particle Velocities based on Production Blasting (86 kg charge weight per delay; 6 m bench height, 165 mm blasthole)	20
Table 3-13	Minimum Setback Distance for 13 mm/s Peak Particle Velocity Guideline	21
Table 3-14	Peak Particle Velocity Threshold Damage Levels	22
Table 3-15	General Guidelines to Vibration Damage Thresholds for Blasting Near Dams	22
Table 3-16	Minimum Setback Distance for 50 mm/s Peak Particle Velocity Guideline	23
Table 3-17	Typical Values for Substrate Density and Compression Wave Velocity	24
Table 3-18	Properties Used to Assess Setback Distance for Instantaneous Overpressure	25
Table 3-19	Minimum Setback Distance for Instantaneous Overpressure Guideline.....	26

LIST OF FIGURES

Figure 1	Location Plan
Figure 2	General Site Plan
Figure 3	Goose Island Deposit Typical Cross Section
Figure 4	Third Portage Deposit Typical Cross Section
Figure 5	North Portage Deposit Typical Cross Section
Figure 6	Vault Deposit Typical Cross Section
Figure 7	Conceptual Controlled Blast Design – General Configuration
Figure 8	Conceptual Controlled Blast Design – Shallow Dipping Ore
Figure 9	Conceptual Controlled Blast Design – Areas of Potential Toppling
Figure 10	Charge Weight versus Distance from Blast – PPV = 13 mm/s

Figure 11	13 mm/s Peak Particle Velocity Isopleth for Various Charge Weights
Figure 12	Charge Weight versus Distance from Blast – PPV = 50 mm/s
Figure 13	50 mm/s Peak Particle Velocity Isopleth for Various Charge Weights
Figure 14	Charge Weight versus Setback Distance for 100 kPa Instantaneous Overpressure
Figure 15	100 kPa Instantaneous Pressure Isopleth for Various Charge Weights

LIST OF APPENDICES

Appendix I	Fragmentation Predictions
------------	---------------------------

1.0 INTRODUCTION

Cumberland Resources Ltd. is currently evaluating the development of the Meadowbank Gold Project located some 70 km north of Baker Lake, Nunavut (Figure 1). This report will address the drilling and blasting operations related to open pit mining. This report should be read in conjunction with detailed geotechnical design reports.

1.1 Ore Deposits

The Meadowbank Gold Project consists of several gold bearing deposits within reasonably close proximity to one another (Figure 2). These are:

- Third Portage Deposit (including Bay Zone and Connector Zone).
- North Portage Deposit.
- Goose Island Deposit.
- Vault Deposit.

The Third Portage Deposit is located on a peninsula, and extends northward under Second Portage Lake, and southward under Third Portage Lake. The Goose Island Deposit lies some 1000 m to the south of the Third Portage Deposit, and beneath Third Portage Lake. The North Portage Deposit is located on the northern shore of Second Portage Lake, and is interpreted as an extension of the Third Portage Deposit. The Vault Deposit is located some 5 km to the northeast of the North Portage Deposit.

1.2 Mining

Mining of the deposits will be primarily by open pit production. Many of the deposits are situated adjacent to, or beneath, lakes. Consequently, a series of dikes will need to be constructed to allow mining of the deposits where these occur beneath the lakes.

1.3 Deposit Characteristics

The deposits of the Meadowbank Project generally consist of stratabound gold mineralization associated with fold limbs inclined at steep angles (>60 degrees) to shallow angles (<30 degrees). The gold mineralization at the Goose Island and Portage Deposit areas is generally associated with iron formation rock. The gold mineralization at the Vault Deposit is associated with intermediate volcanic rock.

Drill and blast designs have been developed for the project rather than for individual deposits. This is primarily due to the similarity in rock type, rock mass quality, and structure throughout the various deposits.

2.0 SUMMARY OF GEOMECHANICAL PROPERTIES

As part of the geotechnical investigations information was gathered on both the intact rock and discontinuity properties of the rock units at the project site. For the purposes of developing drill and blast designs summary information has been extracted from the larger geotechnical database. Complete geotechnical assessments for the various deposits have been issued in a series of Technical Memoranda over the period of August to December 2003, and January 2004. Typical cross sections through the deposits are shown on Figures 3 through 6.

2.1 Geotechnical Model

The following summarizes the geotechnical model for the Goose Island, Portage, and Vault Deposit areas.

- There are three main rock types: iron formation, intermediate volcanic, and ultramafic volcanic. A fourth rock type, quartzite, may form substantial portions of the upper west pit wall of the Goose Island and Portage Deposits. The ultramafic volcanic rock may be serpentized, and where this occurs, may be considerably weaker than the non-serpentized ultramafic rock.
- The sheared and faulted stratigraphic contacts, and overall foliation orientations for the Third Portage and Goose Island Deposits will dip at steep angles (>60 degrees) to the west at the eastern and western margins of these deposits. They will dip at shallower angles (<30 degrees) to the west through the central portion of the Third Portage Deposit, at the north end of the Third Portage Deposit, through the Connector Zone, and at the North Portage Deposit.
- The sheared stratigraphic contacts and overall foliation orientations at the Vault Deposit will dip to the south and southeast at inclinations between about 20 degrees and 30 degrees.
- The stratigraphic contacts are considered to be continuous structures, and will control bench scale and pit wall stability. The orientation of the contacts can be assumed to follow the general trend of the overall foliation orientations for the deposit area, although the foliation may exhibit a high degree of variability on a local scale.
- The iron formation, intermediate volcanic rock, and quartzite are expected to have good rock mass quality. The ultramafic rock is expected to have fair to good rock mass quality.
- Overall pit slope configurations will be controlled by the sheared and faulted main stratigraphic contacts.

2.2 Rock Properties

The Table 2-1 summarizes the results of laboratory strength testing of rock core samples. These are average values based on valid test results of samples collected from Goose Island, Third Portage, North Portage, and Vault. The values for Young's Modulus have been estimated from quality values for the individual rock types.

Table 2-1: Summary of Rock Strength Properties

Rock Type	Minimum Unconfined Compressive Strength (MPa)	Maximum Unconfined Compressive Strength (MPa)	Average Unconfined Compressive Strength (MPa)	E (GPa)	Density (g/cc)
Intermediate Volcanic	51.0	148.3	94	46	2.75 to 2.89
Iron Formation	137.1	248.3	175	50	3.44
Quartzite	69.5	140.1	107	46	2.70
Ultramafic	40.2	91.6	66	25	2.91

2.3 Discontinuity Properties

The orientation, spacing and condition of discontinuities in the rock mass can influence the determination of drill and blast designs. Table 2-2 is a summary level description of the discontinuity parameters relevant to this design procedure.

Table 2-2: Summary of Main Discontinuity Properties – Portage and Goose Island Deposits

Type	Dip	Dip Direction	Average Spacing (m)	Joint Roughness and Condition	Large Scale Joint Roughness
Foliation	12 – 73	255 – 300	0.5 – 1.5	Smooth to rough and planar, slightly altered.	Rough and Wavy
Orthogonal	76 – 10	067 – 121	1.4 – 12	Smooth and wavy, slightly altered.	Rough and Wavy
CJ1	43 – 79	201 – 237	2.5 – 11.4	Smooth and wavy, slightly altered.	Rough and Wavy
CJ2	36 – 81	025 – 068	2.5 – 8.3	Smooth and wavy, slightly altered.	Rough and Wavy
CJ3	65 – 86	125 – 148	1.2 – 9.5	Smooth and wavy, slightly altered.	Rough and Wavy
CJ4	58 – 73	299 – 340	1.0 – 7.0	Smooth and wavy, slightly altered.	Rough and Wavy
Cross	46 – 63	002 – 031	0.4 – 19.4	Smooth and wavy, slightly altered.	Rough and Wavy
Cross	62 – 88	341 – 350			
Cross	26 – 62	170 – 191			

Table 2-3: Summary of Main Discontinuity Properties – Vault Deposit

Type	Dip	Dip Direction	Average Spacing (m)	Joint Roughness and Condition	Large Scale Joint Roughness
Foliation	21 – 23	136 – 164	0.5 – 0.8	Smooth to rough and planar, slightly altered to staining.	Rough and Wavy
Orthogonal	60 – 70	333 – 336	2.8 – 8.1	Rough planar to smooth wavy, no alteration.	Rough and Wavy
CJ1	83 – 85	197 – 209	1.7 – 7.4	Smooth to rough planar, slightly altered to none.	Rough and Wavy
CJ2	80 – 82	040 – 053			
East Dipping	67 – 81	086 – 108	3.7 – 6.1	Smooth and wavy, slightly altered to none.	No Data
South Dipping	45 – 48	174 – 198	2.8 – 14.3	Smooth to rough planar, slightly altered.	No Data
Cross	73	253	4.4	Rough planar to smooth wavy, no alteration.	No Data
Flat	10 – 13	330 - 335	8.3	Rough planar to smooth wavy, no alteration.	No Data

2.4 Pit Slope Design Configurations

The general bench configurations for the north and south end walls of the Goose Island, Portage, and Vault Deposits, and the west pit walls for the Goose Island and Portage Deposits, are given in the Table 2-4.

Table 2-4: General Bench Configurations

Bench Face Angle	Operating Bench Height, m	Final Bench Height, m	Bench Width, m	General Wall Application		
				Goose Island	Portage Pits	Vault Pit
60° to 70°	12 (6m in ore)	24	8 to 10 m	North South West	North South West	West South East

For the east pit wall of the Goose Island and Portage Pit, and the west pit wall of the Vault Pit, a footwall design philosophy will be used whereby pit slopes will be excavated parallel to the dip of the stratigraphy to avoid undercutting the sheared stratigraphic contacts.

Table 2-5: Footwall Design Criteria

Dip of Faulted Contacts	Slope Configuration	
<30° to 35°	Unbenched Slope	Parallel to Bedding/Stratigraphy/Faulted Contacts
>35°	Bench Face Angle:	Parallel to Bedding/Stratigraphy/Faulted Contacts to a maximum 70°
	Bench Height:	24 metres
	Catch Bench Width:	10 metres
	Inter-Ramp Angle:	32° to 52° dependent on bench face

For the purposes of production blast design, the proposed pit area has been divided into sectors on the basis of the general orientation of the main structural features that may influence the effectiveness of the blast design. Consequently, there are potentially four wall orientations for the production blasts. These are:

- West facing walls.
- East facing walls.
- North facing walls.
- South facing walls.

The dominant structural influence on blast design will be the orientation of the main stratigraphic contacts, and axial planar foliation. The spacing of the foliation is expected to be on the order of 1 m to 2 m. The secondary structural influence on the blast design will be the orientation of the orthogonal jointing. As discussed previously, the orthogonal joints are expected to be discontinuous but systematically distributed throughout the various rock types in the deposit area. The spacing of these features is expected to be on the order of several metres.

2.5 Permafrost

The site is located in the zone of continuous permafrost. Based on thermistor installations at the site, the permafrost is well developed. The active layer is between 1.5 m and 2 m below the ground surface. Permafrost temperatures beneath the landmass are on the order of -8 degrees C. Permafrost temperatures are expected to be warmer adjacent to and beneath lakes. Where mining occurs in de-watered area of the lake, talik zones will be present. Water inflows to the open pits will therefore occur through the talik.

Successful blast design in Arctic environments carries with it the need to understand the nature of permafrost, and the effect permafrost may have on the blast design. Based on site instrumentation, the permafrost underlying the land mass is expected to be cold;

hence the drilled blast holes are likely to be dry. Where pit walls are excavated within the talik underlying the de-watered lakes, the drilled blast holes are expected to be wet.

The overall strength and modulus of the rock mass may be enhanced by the presence of permafrost, and this may have an effect on blasting results. The presence of permafrost may also influence stress induced fracturing and gas penetration if the fractures are ice filled.

2.6 Groundwater

The current operational plan to develop the Portage Pit will involve initial draw-down of the Second Portage Lake arm to a level approximately 28 m below the current lake surface elevation. Based on the lake bathymetry survey carried out in 2002, a north trending ridge is located to the west of the North Portage deposit. The water will be drawn down below this ridge, which will aid as a natural barrier to restrict flow into the open pit. In addition to drawing down of the lake, a tailings dike will be constructed west of the pit crest. At this time, a minimum setback of 80 m from the proposed crest of the open pits to the inside (pit side) toe of the de-watering dikes has been assumed. The central core of the dike will be located on the order of 100 m back from the pit crest.

The overburden is expected to consist of silt, sand and gravel till, with areas of sand and gravel deposits possibly of glacio-fluvial origin.

The hydraulic conductivity within the overburden is estimated to be 1×10^{-5} m/s. The hydraulic conductivity of the shallow bedrock (less than 25 m) is generally higher than that of the deeper bedrock (greater than 25 m). The geometric mean value of the shallow bedrock is approximately 1×10^{-6} m/s while that of the deeper bedrock is 1×10^{-8} m/s. Based on the hydraulic conductivity testing carried out to date at the site, the hydraulic conductivity of the Bay Zone Fault and Fault Splay is similar to that of the less fractured rock, while the hydraulic conductivity of the Second Portage Fault is higher at 5×10^{-6} m/s.

Potential sources of water inflows to the open pit will be from water stored in the overburden sediments, through potentially hydraulically conductive structures such as the Second Portage Lake Fault, and through the talik beneath Second Portage Lake. Initial estimates of water inflow to the Third Portage pit and North Portage pit through the bedrock talik are on the order of 250 m³/day and 350 m³/day, respectively (Ref. "Predictions of Groundwater Inflow to Open Pits – Meadowbank Project", Technical Memorandum, 6 Feb. 2004). Pit inflows along the Second Portage Lake Fault have initially been estimated to be on the order of 50 m³/day to 100 m³/day.

Based on this information, blasting will have to be undertaken in both wet and dry conditions. Explosive selection will be influenced by the presence of water.

3.0 BLAST DESIGN

3.1 Lilly's Blastability Index

An empirical method to assess the blastability of a rock mass was developed by Lilly (1986, 1992). The method takes into account both geotechnical factors, geological (structure) factors, and physical properties of a rock mass to arrive at an index rating known as the Blastability Index, or BI.

The following factors determine the Blastability Index:

1. **Rock Mass Description (RMD):** The Rock Mass Description is concerned with the overall character of the rock, and considers whether the rock is massive with little to no structural character, blocky with systematic jointing, or powdery and friable. The fragmentation of a massive rock will depend largely on the strain energy of the blast inducing fractures in the rock mass. The fragmentation of a heavily jointed rock mass will be controlled more so by the orientation of the joint systems.
2. **Joint Plane Spacing (JPS):** The Joint Plane Spacing refers to the spacing between all planes of weakness in the rock mass. Lower energy factors are required to break a rock mass having closely spaced joints. This value can be determined as the Block Size Index (Ib) as described by ISRM "Suggested Methods for the Quantitative Description of Discontinuities" (1978). The block size index represents the average dimensions of typical rock blocks, and is based on modal spacing of the joints.
3. **Joint Plane Orientation (JPO):** The Joint Plane Orientation accounts for the influence of major structural orientations on the distribution of the strain energy in a blast. The orientation of the major joint or bedding planes can significantly impact blasting results.
4. **Rock Density Influence (RDI):** The Rock Density Influence affects the blastability of the rock as greater energy is required to fragment a heavier rock mass than a lighter rock mass. The RDI is given by:

$$RDI = 25 \times \text{Rock Density (t/m}^3\text{)} - 50$$

5. **Hardness Factor (HF):** The Hardness Factor links the blastability of a rock mass to the Young's Modulus (γ) of weaker rocks where γ is less than 50 GPa (weak confinement). For stronger rock masses ($\gamma > 50$ GPa, strong confinement), the Hardness Factor is linked to the Unconfined Compressive Strength of the rock (in MPa). The hardness

The index has a maximum value of 100 corresponding to extremely hard, iron rich cap rock having a specific gravity of 4 t/m³, while weaker rocks, such as shale, have indices of about 20.

The Blastability Index is defined as:

$$BI = [0.5 \times (RMD + JPS + JPO + RDI + HF)]$$

Where:

RMD = Rock Mass Description
 JPS = Joint Plane Spacing
 RDI = Rock Density Influence
 HF = Hardness Factor

The Blastability Index is used to determine an appropriate powder factor and in the Kuz-Ram model for rock fragmentation to determine the parameter Rock Factor A.

Table 3-1: Blastability Index and Rock Factor for Meadowbank Rock Types

Rock Type	Iron Formation	Intermediate Volcanic	Ultramafic	Quartzite
Rock Mass Description	50	50	20	50
Joint Plane Spacing	50	50	50	50
Joint Plane Orientation	20	20	20	20
Rock Density Influence	30	18	18	18
Hardness Factor	14	15	9	15
BLASTABILITY INDEX, BI	82	76	58	76
Rock Factor, A (0.12*BI)	9.8	9.1	7.0	9.1

3.1.1 Blast Hole Diameter, D (mm)

The selection of an appropriate blasthole diameter is important in terms of fragmentation and cost. Ideally, it is desirable to obtain the maximum fragmentation at a minimum cost. The cost of drilling and of explosives decreases as the diameter of the blasthole increases. Other factors must be considered such as bench height, rock structure and rock hardness. Smaller diameter blastholes are more suited to strongly jointed rocks as the decreased spacing results in fewer joints between holes. This will tend to reduce the amount of oversize and result in better fragmentation.

Based on discussions with Cumberland the blasthole diameter will be 165 mm (6½ in.) with the capability of drilling larger diameter blast holes. Alternative designs are presented for larger blastholes of 229 mm (9 in.).

3.2 Explosive Selection

The project is located in the zone of continuous permafrost. Known permafrost temperatures in the area are as low as -8 to -10 degrees C. The depth of the active layer is between 1.5 m and 2 m. Much of the pit wall development will be within talik zones beneath de-watered lakes, and consequently will be unfrozen during development. These conditions will result in wet blast holes. Consequently, the water resistance of the chosen explosive must be considered. Where pit wall development will be within permafrost (i.e., beneath the existing land surface) dry blasthole conditions may exist. Under these circumstances, a product having a lower resistance to water may be considered.

3.2.1 ANFO

The location of the site is remote. Therefore, cost is a consideration. Ammonium nitrate-fuel oil, or ANFO, is the least expensive explosive used by the mining industry. However, the water resistance of ANFO is poor, and it can be desensitized relatively easily even with low water contents. The effect on ANFO of the presence of water in the blasthole has been overcome by a number of methods. Dewatering equipment can be used to dewater the blastholes before loading. The ANFO is then loaded using dryliners, or polythene tubing sealed at the bottom and installed in the blasthole. For surface mining, the ANFO is handled by bulk mix trucks.

3.2.2 ANFO/Emulsion Mixtures

An alternative to ANFO that overcomes some of the problems associated with water resistance, is an ANFO/emulsion mixture. The amount of emulsion added to the mixture varies depending on the energy and water resistance requirements. The use of emulsion improves the bulk strength of the explosive and allows for an increase in breakage capacity. Since the ANFO can be surrounded by emulsion, the water resistance of the product is enhanced considerably from that of straight ANFO.

Table 3-2: Typical Properties of ANFO/Emulsion Mixtures

ANFO (%)	Emulsion (%)	Density (g/cc)	Velocity of Detonation (m/s)	RWS/RBS	Minimum Diameter (mm)	Water Resistance	Loading
30	70	1.3	5700	84/132	115	Excellent	Pump
50	50	1.3	5500	89/141	150	Good	Auger
70	30	1.2	4700	93/131	125	Poor	Auger
75	25	1.1	4600	94/127	100	Poor	Auger

Reference: Dyno Nobel, Inc.

Given that the conditions in the talik areas will be wet and that there will be some water infiltration through and under the dike it is recommended that a "doped" emulsion be used. At this stage a 70:30 (emulsion:ANFO) mixture is recommended. Pumpable blends have better water resistance than augerable blends which tend to lose their water resistance as the percentage of emulsion decreases. Where blasthole conditions are found to be dry, alternative blast designs (30:70 Emulsion:ANFO) can be considered.

3.3 Blast Design Assumptions

The production blast design criteria were formulated on the basis of the engineering geological models for the deposits. Basic assumptions used for the process were:

- A doped emulsion will be used (70:30, emulsion:ANFO) to address potentially wet blasting conditions.
- The available equipment will be capable of drilling blasthole diameters ranging from 165 mm (6½ in) up to 229 mm (9 in). For the 12 m working benches, the larger blasthole size is appropriate to optimize fragmentation, reduce drilling inaccuracy, and reduce the number of blastholes required. For the 6 m high benches in ore, the smaller diameter blasthole is appropriate. **However, it is important to note that the critical diameter of the doped emulsion product is close to 165 mm (6½ in). This could potentially result in incomplete detonation of the product and poor fragmentation of the rock for smaller diameter holes.**
- A staggered pattern with millisecond delays and an echelon firing sequence shooting from a corner is assumed. An inter-hole 25 ms delay is suggested. The staggered pattern will result in better distribution of the explosives energy and consequently better movement of material and a lower muckpile for easier digging. If it is necessary to blast to one free face, a staggered V1 (flat) pattern should be used.
- Operating bench heights within the waste rock will be 12 m. Operating bench heights within the ore will likely be 6 m to facilitate grade control. A high degree of care and attention to blast design will be required.

- Final benches will generally be double-benched to 24 m. Single benching (12 m) in areas that may be susceptible to toppling failure may be required.
- The length of the blasted block will be a minimum of twice the width, which will be between three and five rows for production blasts.
- The bench face angles will generally be steep, between 60 and 70 degrees and hence vertical blastholes have been assumed. Inclined blastholes could improve the consistency of the burden and the efficiency of fragmentation, however, accuracy of drilling angled holes is difficult to achieve, particularly with smaller diameter blastholes.

3.4 Production Blast Design

The following tables summarize the blast designs considered for the Meadowbank Project.

Table 3-3: Blasthole Parameters

	Units	Constant Blasthole Diameter		Blasthole Diameter based on Bench Height	
		Waste	ORE	Waste	ORE
Working Bench Height	m	12	6	12	6
Blasthole Diameter	mm	165	165	229	165
Bench Face Angle	degrees	60 - 70	60 - 70	60 – 70	60 – 70
Hole Inclination	deg	90	90	90	90
Inclined Depth	m	12.0	6.0	12.0	6.0
Subdrill	m	1.3	1.3	1.8	1.3
TOTAL DRILLED DEPTH	m	13.3	7.3	13.8	7.3

Table 3-4: Blast Patterns

Blasthole Pattern	Staggered
Blast Sequence	En Echelon
Spacing/Burden Ratio	1:1.15
Number of Rows	5
Number of Holes per Row	10

Table 3-5: Charge Table – Wet Blastholes (Emulsion:ANFO 70:30)

Rock Type	Units	165 mm Blasthole, 6 m bench in ore, 12 m bench in waste			229 mm Blasthole, 12 m bench in waste	
		Ore	IV and Quartzite	Ultramafic	IV and Quartzite	Ultramafic
Stemming Length	m	3.8	5.4	5.4	5.7	5.9
Fallback	m	0.1	0.2	0.2	0.2	0.2
Charge Length	m	3.4	7.7	7.7	7.9	7.7
Linear Charge Density	kg/m	27.8	27.8	27.8	53.6	53.6
Burden	m	5.0	5.0	5.0	6.9	6.9
Spacing	m	5.7	5.7	5.7	7.9	7.9
Burden Volume	m ³	169	338	338	651	651
Explosives Mass per Hole, Q	kg	95	215	215	424	412
Powder Factor, PF	kg/m³	0.56	0.63	0.64	0.65	0.63

The proposed general blast configuration is shown on Figure 7. Where blasting occurs within the shallow dipping ore and stratigraphy, a conceptual blast design is shown on Figure 8. For areas where toppling may be a concern, a conceptual blast design layout is shown on Figure 9.

In areas where dry blasthole conditions are encountered the following designs can be adopted.

Table 3-6: Charge Table – Dry Blastholes (Emulsion:ANFO 30:70)

Rock Type	Units	165 mm Blasthole, 6 m bench in ore, 12 m bench in waste			229 mm Blasthole, 12 m bench in waste	
		Ore	IV and Quartzite	Ultramafic	IV and Quartzite	Ultramafic
Stemming Length	m	3.5	4.8	4.7	5.1	5.3
Fallback	m	0.1	0.2	0.2	0.2	0.2
Charge Length	m	3.7	8.3	8.3	8.5	8.3
Linear Charge Density	kg/m	25.7	25.7	25.7	49.4	49.4
Burden	m	5.0	5.0	5.0	6.9	6.9
Spacing	m	5.7	5.7	5.7	7.9	7.9
Burden Volume	m ³	169	338	338	651	651
Explosives Mass per Hole, Q	kg	95	214	216	422	412
Powder Factor, PF	kg/m³	0.56	0.63	0.64	0.65	0.63

3.4.1 Rock Fragmentation

The predicted fragmentation of the rock mass for the blast designs presented above is based on the Kuz-Ram Model (Cunningham, 1983; Kuznetsov, 1973; Rosin and Rammler 1933). The Rosin-Rammler equation defines the grain size curve for rock fragmentation. The Kuznetsov equation gives the mean fragmentation size when the Rosin-Rammler equation is equal to 0.5, or the point on the grain size curve with the mesh size that 50% of the blasted rock would pass. The following table summarizes the predicted rock fragmentation for the preceding design criteria, and for a five row blast pattern with ten holes per row. The predicted fragmentation curves are contained in Appendix I. The predicted fragmentation assumes a ratio of actual to theoretical VOD of 0.85, although this ratio could be as high as 0.95 if the bulk product is well mixed.

Table 3–7: Predicted Fragmentation (Emulsion:ANFO 70:30)

Rock Type	Bench Height, m	Hole Size, mm	t/blast, t¹	Powder Factor, kg/m³	50% passing, m	80% passing, m	Characteristic Size, m
Iron Formation	6 m	165 mm	29,412	0.56	0.51	1.1	0.70
Ultramafic	12 m	165 mm	46,170	0.63	0.38	0.72	0.50
Intermediate Volcanic	12 m	165 mm	47,880	0.64	0.49	0.94	0.65
Ultramafic	12 m	229 mm	88,306	0.63	0.42	0.79	0.55
Intermediate Volcanic	12 m	229 mm	91,577	0.65	0.54	1.01	0.71

1. Assumes 5 rows and 10 holes per row.

3.5 Controlled Blasting for Final Walls

Trim blasting should be used to shape the final wall. Trim blasting uses large-diameter blastholes for both production and final row holes and thus eliminates the additional costs associated with small diameter blasthole drilling. The trim row is designed as the last row of the blast.

The trim row burden volume should be approximately one-third of the volume of the production row and should be loaded with sufficient explosive to maintain the same powder factor as for the production row. The burden volume of the two buffer rows in front of the trim row should be approximately two-thirds of the rock volume of the production holes. The buffer rows should be loaded to maintain the same powder factor as for the production row. A typical layout for a trim and buffer blast for final wall

shaping is shown on Figures 7 through 9 and will be applicable to areas of the final pit walls of the Goose Island, Portage, and Vault pits.

Table 3-8: Charge Table – Trim Blast

Rock Type	Units	165 mm Blasthole, 12 m bench		229 mm Blasthole, 12 m bench	
		IV and Quartzite	Ultramafic	IV and Quartzite	Ultramafic
Stemming Length	m	4.1	4.1	5.7	5.7
Fallback	m	0.2	0.2	0.2	0.2
Charge Length	m	9.0	9.0	7.9	7.9
Linear Charge Density	kg/m	6.3	6.4	13.7	13.4
Burden	m	2.5	2.5	3.4	3.4
Spacing	m	3.0	3.0	4.1	4.1
Burden Volume	m ³	90	90	167	169
Explosives Mass per Hole, Q	kg	57	58	109	107
Powder Factor, PF	kg/m³	0.63	0.64	0.65	0.63

Table 3-9: Charge Table – Buffer Blast

Rock Type	Units	165 mm Blasthole, 6 m bench in ore, 12 m bench in waste		229 mm Blasthole, 12 m bench in waste	
		IV and Quartzite	Ultramafic	IV and Quartzite	Ultramafic
Stemming Length	m	4.1	4.1	5.7	5.7
Fallback	m	0.2	0.2	0.2	0.2
Charge Length	m	9.0	9.0	7.9	7.9
Linear Charge Density	kg/m	11.7	11.9	26.0	25.2
Burden	m	3.5	3.5	4.8	4.8
Spacing	m	4.0	4.0	5.5	5.5
Burden Volume	m ³	168	168	317	317
Explosives Mass per Hole, Q	kg	106	108	206	200
Powder Factor, PF	kg/m³	0.63	0.64	0.65	0.63

Certain areas of the east pit wall of the Portage and the Goose Island pits will be excavated within shallow dipping structure, with bench face angles paralleling the stratigraphic contacts and foliation orientations. In these areas, the length of the trim holes will be shortened substantially. Pocket charges may be required to improve fragmentation. Alternatively a series of stab holes may be drilled between the trim and buffer rows.

In certain areas of the west wall of the Portage and Goose Island pits, the potential for toppling failure exists. This will be particularly true adjacent to the Bay Fault. In these areas, it may be necessary to alter the geometry of the buffer and trim rows.

3.6 Nitrate/Ammonia Considerations

The use of nitrate based explosives products in a wet environment increases the potential for nitrogen (as nitrate, nitrite or ammonia) to enter the water system. In order to minimize any potential impacts an effective explosives management system should be implemented as part of production startup. The management strategy should include the following:

- An education program for all production employees that outlines the potential problem and appropriate mitigation techniques.
- A spill handling procedure.
- A monitoring program that is integrated with baseline water quality information.
- A review of blasting operations early in production to determine efficiency levels.

3.7 Blast Induced Vibration

Blast induced vibrations have the potential to reduce the stability and performance of nearby earthen structures such as dikes. Where saturated conditions exist within the foundation materials and within the earthen structural fills of the de-watering dikes and the tailings dike, blast induced vibrations could result in the development of increased pore water pressures within the foundation and structural fill materials. This could lead to potential settlement of the structures and consequently impact to the water retaining capacity of the dikes.

As part of the mine development, a vibration monitoring program will be required in order to measure the response of the de-watering dikes and tailings dike to pit blasting. The data from this program would be assessed in conjunction with continuous measurements from piezometers that would be installed in the dikes, and within the dike foundation materials. From this analysis, the blasting could be adjusted to minimize the impact on the dikes. Mitigative measures to the blast design to minimize the development of blast induced vibration could include modifications to the blasthole patterns, reduction in blasthole size and hence charge weight in critical areas of the pit walls within a certain distance from the proposed de-watering and tailings dike, single blasthole initiation per delay, reduction in operating bench height in critical areas, or a combination of all these measures.

A more comprehensive program of blast vibration modelling and test blasting may be required during operations if blast vibration levels remain high and their frequency (cycles per second) is low.

The effects of blasting are typically assessed in terms of Peak Particle Velocity (PPV).

3.7.1 Estimates of Peak Particle Velocity

The preliminary estimates of Peak Particle Velocity (PPV) are based on the current understanding of the site layout, mine plan, and blast design. Changes to the current site layout, mine plan, and blast design will result in changes to the estimates of PPV. Certain site specific factors that are required to calculate PPV have been estimated based on published values. However, site specific parameters can only be determined by site vibration monitoring of actual blasts. Consequently, the actual PPV values may differ from those presented here.

The US Bureau of Mines has established that the peak particle velocity, PPV, is related to the scaled distance by the following relationship:

$$PPV = k * (R/W^{0.5})^{-b}$$

Where:

- PPV = Peak Particle Velocity, mm/s
- R = Distance from blast to point of concern, m
- W = Charge weight per delay, kg
- k = confinement factor – specific to site
- b = site factor

The constants k and b are specific to the site, and can be determined by blast vibration monitoring.

For this evaluation, a value of b = 1.6 was assumed. The PPV was evaluated for a range of values of confinement, 'k', of 400, 800, and 1500, for down hole blasting. This range in values is considered to be reasonable for the site and to provide an estimate of the sensitivity of PPV to different values of confinement. Based on the current understanding of site conditions and experience at two other northern sites, the confinement value of 800 is expected to be the most likely representative value for average conditions at the site. The actual value for confinement can only be determined through a detailed field monitoring program.

3.7.2 Minimum Setback Distance for Canadian Fisheries Guidelines

Design guidelines governing the use of explosives adjacent to Canadian fisheries waters (Guidelines for the Use of Explosives in or Near Canadian Fisheries Waters; Wright and Hopky, 1998) indicate that no explosive is to be detonated that produces a peak particle velocity greater than 13 mm/s in a spawning bed during the period of egg incubation.

For the Meadowbank Site, three scenarios have been assessed: the first assumes a charge weight per delay of 420 kg for 229 mm (9 in) blastholes and an operating bench height of 12 m, the second assumes a maximum charge weight of 250 kg for 165 mm (6½ in) blastholes and a bench height of 12 m, and the last assumes a charge weight of 86 kg for 165 mm blasthole and bench height of 6 m. The maximum charge weight determined in the above analyses has been used to assess the PPV. An Emulsion:ANFO ratio of 70:30 has been assumed.

The PPV's were evaluated for the Second Portage Lake East Dike, the Third Portage Peninsula east shoreline, the Bay Dike, and the Goose Island east shoreline. Based on the current mine layout, estimates of the minimum distance from the estimated final production blast near the pit crest, to the point of concern (either shoreline or dike face), and estimates of the distance from the pit centre to the point of concern (either shoreline or dike face) were made. The PPV were evaluated based on these estimated distances. The estimates of PPV will change as a result of further changes to the mine plan, pit optimization, dike alignment optimization, and blast design optimization.

The Table 3-10 summarizes the estimated PPV at points of concern either along the upstream face of the dike, or along the shoreline, whichever is closest.

Table 3-10: Preliminary Estimate of Peak Particle Velocities based on Production Blasting (420 kg charge weight per delay; 12 m bench height, 229 mm blasthole)

Location	Distance to Point of Concern (m)		PPV (mm/sec)		
			k=400	k=800	k=1500
Second Portage Lake East Dike	Pit Crest to U/S Dike Face	255	7	14	27
	Pit Centre to U/S Dike Face	375	4	8	14
Third Portage Peninsula	Pit Crest to Shoreline	101	31	62	117
	Pit Centre to Shoreline	295	6	11	21
Bay Dike	Pit Crest to U/S Dike Face	145	17	35	66
	Pit Centre to U/S Dike Face	355	4	8	16
Goose Island	Pit Crest to Shoreline	105	29	59	110
	Pit Centre to Shoreline	335	5	9	17

Distances are measured from approximate location of last production blast, not final trim blast.
Values of PPV in bold exceed 13 mm/sec.

To assess the sensitivity of the estimates of PPV to blast design, a charge weight of 250 kg, corresponding to a smaller 165 mm (6½ in) blasthole diameter, was used (decking of the charges could produce a similar result, while maintaining the larger blasthole diameter of 229 mm). The results are presented in the following table, and indicate that optimization and modification of the blast design near the crest areas can result in reduced PPV.

Table 3-11: Preliminary Estimate of Peak Particle Velocities based on Production Blasting (250 kg charge weight per delay; 12 m bench height, 165 mm blasthole)

Location	Distance to Point of Concern (m)		PPV (mm/sec)		
			k=400	k=800	k=1500
Second Portage Lake East Dike	Pit Crest to U/S Dike Face	255	5	9	18
	Pit Centre to U/S Dike Face	375	3	5	9
Third Portage Peninsula	Pit Crest to Shoreline	101	21	41	77
	Pit Centre to Shoreline	295	4	7	14
Bay Dike	Pit Crest to U/S Dike Face	145	12	23	43
	Pit Centre to U/S Dike Face	355	3	6	10
Goose Island	Pit Crest to Shoreline	105	19	39	73
	Pit Centre to Shoreline	335	3	6	11

Distances are measured from approximate location of last production blast, not final trim blast.
Values of PPV in bold exceed 13 mm/sec.

By reducing the working bench height further to 6 m within both the waste rock as well as within the ore, the charge weight can be reduced to approximately 86 kg per blasthole. This reduction in charge weight has the following effect on PPV.

Table 3-12: Preliminary Estimate of Peak Particle Velocities based on Production Blasting (86 kg charge weight per delay; 6 m bench height, 165 mm blasthole)

Location	Distance to Point of Concern (m)		PPV (mm/sec)		
			k=400	k=800	k=1500
Second Portage Lake East Dike	Pit Crest to U/S Dike Face	255	2	4	7
	Pit Centre to U/S Dike Face	375	1	2	4
Third Portage Peninsula	Pit Crest to Shoreline	101	9	18	33
	Pit Centre to Shoreline	295	2	3	6
Bay Dike	Pit Crest to U/S Dike Face	145	5	10	18
	Pit Centre to U/S Dike Face	355	1	2	4
Goose Island	Pit Crest to Shoreline	105	8	16	31
	Pit Centre to Shoreline	335	1	3	5

Distances are measured from approximate location of last production blast, not final trim blast.

Values of PPV in bold exceed 13 mm/sec.

The above analysis indicates that the Peak Particle Velocities along the upstream (lake side) face of the de-watering dikes can be managed and minimized, but not eliminated, through modifications to the blast design to adjust the charge weight in specific areas of the pit. These modifications would include reduction of blasthole size, reduction of bench height, or a combination of the two. Figure 10 shows the relationship between charge weight and distance from blast for a constant Peak Particle Velocity of 13 mm/s. The figure can be used as a guide to estimate the maximum charge weight per blasthole required so as not to exceed 13 mm/s criteria for fish habitat at a given distance from the blast, and to develop blast designs to minimize potential impacts to fish habitat where the 13 mm/s criteria can not be achieved. The minimum setback distances to achieve a PPV of 13 mm/s have been estimated for the various values of 'k', and for four potential charge weights per delay used in the above PPV estimates. The following table summarizes the estimates of minimum setback required to achieve a PPV value of 13 mm/s.

**Table 3-13: Minimum Setback Distance for 13 mm/s Peak
Particle Velocity Guideline**

k	86 kg charge weight per delay (6 m bench, 165 mm hole)	250 kg charge weight per delay, (12 m bench, decked charge, 229 mm hole)	420 kg charge weight per delay, (12 m bench, 229 mm hole)
	Minimum Setback Distance to Achieve PPV = 13 mm/s		
400	79 m	135 m	175 m
800	122 m	208 m	269 m
1500	180 m	308 m	399 m

The above analysis suggests that for a charge weight per delay of 420 kg, the minimum setback for a PPV of 13 mm/s will be on the order 269 m, based on an average expected confinement value, k, of 800. The minimum setback distance can be reduced by modifying the bench blast designs and incorporating smaller bench heights, smaller blastholes, or a combination of the two. Figure 11 shows the 13 mm/s isopleth relative to the current dike configuration for the above charge weights and a confinement value, k, of 800.

In some cases it will be impractical to construct the proposed de-watering dikes at the minimum setback distances for fish habitat indicated in the above analyses. This is primarily due to engineering and constructability constraints relating to the proposed method of dike construction. However, during detailed engineering design, the final alignment of the proposed de-watering dikes can be assessed further to consider, among other items, the minimum setback required to minimize the impact of explosives detonation on the potential fish habitat along the upstream dike faces. As discussed previously, the effects on fish habitat of explosives detonation within the open pits can be mitigated to some degree by reducing the charge weight per delay through the use of smaller diameter blastholes or by decking of charges, by reducing the bench height, or through a combination of the two. Other mitigative methods may include the use of 'bubbler' systems along the upstream face of the dikes in areas that will be affected by PPV of 13 mm/s or greater. These systems would be operated during blasting operations to discourage fish from along the upstream embankment face.

3.7.3 Minimum Setback Distance for Threshold Damage Levels

Common threshold vibration levels for damage have been developed relating PPV to potential vibration damage. The following table summarizes additional threshold damage levels typically used in urban areas for assessing the potential for blast damage to occur.

Table 3-14: Peak Particle Velocity Threshold Damage Levels

Velocity (mm/s)	Damage
3 – 5	Vibrations Perceptible
10	Approximate limit for poorly constructed, and historic buildings
33 – 50	Vibrations objectionable
50	Limit below which risk of damage to structures is very slight (less than 5%)
125	Minor damage, cracking of plaster, serious complaints
230	Cracks in concrete blocks
300	Rock falls in unlined tunnel
380	Horizontal offset in cased drillholes
635	Onset of cracking in rock
1000	Shafts misaligned in pumps, compressors
1500	Prefabricated metal buildings on concrete pads, metal twisted and concrete cracked
2500	Breakage of rock

Charlie et al (1987) suggest the following criteria for blasting near dams, based on liquefaction potential.

Table 3-15: General Guidelines to Vibration Damage Thresholds for Blasting Near Dams

	Maximum PPV
Dams constructed of or having foundation materials consisting of loose sand or silts that are sensitive to vibration.	25 mm/s
Dams having medium dense sand or silts within the dam or foundation materials	50 mm/s
Dams having materials insensitive to vibrations in the dam or foundation materials	100 mm/s

Ref. Charlie et al, 1987.

The information presented in the above tables can be used as general guidelines for assessing the potential for blast vibration damage to structures. Due to the inherent variability in site conditions, caution must be exercised in assessing the potential damage from blast induced vibration. Actual vibrations will need to be monitored during construction and operations.

Minimum setback distances based on a maximum PPV of 50 mm/s, representing the situation of a dam having medium dense sands or silts in the dam or foundations, have been calculated for the various values of confinement, 'k', and for three potential charge weights per delay. The actual velocities will need to be determined during a vibration monitoring program that will be required in order to measure the response of the de-

watering dikes and tailings dike to pit blasting. Depending on the actual velocities experienced by the dikes, charge weights may need to be modified during operations. The threshold value of 50 mm/s may be modified once more detailed information is obtained relating to the foundation materials beneath the dikes. Furthermore, in the case of the tailings dike, it is proposed to construct the till core of the dike in compacted lifts. Consequently, a threshold value on the order of 100 mm/s may be more appropriate, and would be on the order of requirements for similar dikes in the north which have used design threshold values of up to 125 mm/s to limit structural damage. However, for this stage of design, a threshold value of 50 mm/s is considered appropriate to limit structural damage.

Figure 12 shows the relationship between charge weight and distance from blast for a constant Peak Particle Velocity of 50 mm/s. The Table 3-15 summarizes the estimates of minimum setback required to achieve a PPV value of 50 mm/s.

Table 3-16: Minimum Setback Distance for 50 mm/s Peak Particle Velocity Guideline

k	86 kg charge weight per delay (6 m bench, 165 mm hole)	250 kg charge weight per delay, (12 m bench, decked charge, 229 mm hole)	420 kg charge weight per delay, (12 m bench, 229 mm hole)
	Minimum Setback Distance to Achieve PPV = 50 mm/s		
400	32 m	58 m	75 m
800	53 m	89 m	116 m
1500	78 m	133 m	172 m

The above analysis suggests that the peak particle velocities that the de-watering and tailings dikes may be exposed to can be managed effectively, if necessary, through the use of lighter charge weights by reducing bench heights, blasthole diameter, or combinations of the two. The table also suggests that the minimum toe setback distance of 80 m that is currently being carried through the feasibility study is a reasonable distance from the perspective of managing PPV. Additional sampling and testing of the till materials may allow refinements to be made to the above estimates of setback distance.

3.8 Instantaneous Pressure Change

Design guidelines governing the use of explosives adjacent to Canadian fisheries waters (Guidelines for the Use of Explosives in or Near Canadian Fisheries Waters; Wright and Hopky, 1998) indicate that no explosive is to be detonated in or near fish habitat that

produces an instantaneous pressure change greater than 100 kPa in the swimbladder of a fish.

The required setback distance for confined explosives to achieve the 100 kPa guideline can be estimated from the following relationships (Guidelines for the Use of Explosives in or Near Canadian Fisheries Waters; Wright and Hopky, 1998).

The relationship between acoustic impedance and the density and velocity of the medium through which the compression wave travels is given by:

$$Z_w/Z_r = (D_w * C_w) / (D_r * C_r)$$

Where:

- D_w = density of water = 1 g/cm³
- D_r = density of the substrate, g/cm³
- C_w = compression wave velocity in water
= 146,300 cm/s
- C_r = compression wave velocity in substrate, cm/s

Typical values used for D_r and C_r for various substrates are:

Table 3–17: Typical Values for Substrate Density and Compression Wave Velocity

Substrate	D _r (g/cm ³)	C _r (cm/s)
Rock	2.64	457,200
Frozen Soil	1.92	304,800
Ice	0.98	304,800
Saturated Soil	2.08	146,300
Unsaturated Soil	1.92	45,700

Reference: Guidelines for the Use of Explosives in or Near Canadian Fisheries Waters; Wright and Hopky, 1998

The transfer of shock pressure from the substrate to the water can be estimated from:

$$P_w = (2 * (Z_w / Z_r) * P_r) / (1 + (Z_w / Z_r))$$

Where:

- P_w = pressure (kPa) in water
- P_r = pressure (kPa) in substrate
- Z_w = acoustic impedance of water
- Z_r = acoustic impedance of substrate

The equation can be re-written to solve for the pressure in the substrate, P_r , as:

$$P_r = (P_w * (1 + (Z_w / Z_r))) / (2 * (Z_w / Z_r))$$

The equation is solved by setting the value of P_w to the 100 kPa guideline to determine the pressure in the substrate, P_r , which is required to produce this detonation overpressure in the water. The resulting value for P_r is used to determine the Peak Particle Velocity in the rock for the given conditions based on the following:

$$PPV = (2 * P_r) / (D_r * C_r)$$

The relationship between Peak Particle Velocity, charge weight, and distance was described in Section 3.7.1 and is given by:

$$PPV = k * (R / W^{0.5})^{-b}$$

Equating the two equations for Peak Particle Velocity, and solving for distance, R for a given charge weight, W , gives the minimum setback distance from fish habitat required so as not to exceed the 100 kPa overpressure guideline.

The following properties were used to assess the minimum setback distance.

Table 3–18: Properties Used to Assess Setback Distance for Instantaneous Overpressure

Medium	Density, g/cm ³	Compressional Wave Velocity, cm/s
Water	1	146,300 ¹
Rock (Intermediate Volcanic)	2.8	457,200 ¹

1. Guidelines for the Use of Explosives in or Near Canadian Fisheries Waters; Wright and Hopky, 1998

Based on the above properties, the range of potential charge weights, and the range in confinement value, k , the following minimum setback distances, below which the 100 kPa overpressure guideline will not be exceeded, are estimated.

Table 3-19: Minimum Setback Distance for Instantaneous Overpressure Guideline

Charge Weight per Delay	Minimum Setback Distance, m		
	k=400	k=800	k=1500
kg			
86	26 m	40 m	60 m
250	45 m	69 m	102 m
420	58 m	89 m	132 m

The relationship between charge weight per delay and minimum setback distance to achieve the 100 kPa guideline for instantaneous overpressure is shown on Figure 14. The figure can be used as a guide to the development of alternative blast designs in areas that may be affected by instantaneous overpressures greater than 100 kPa.

The analyses indicate that through the use of lighter charge weights, decreased blasthole diameters, and decreased operating bench heights, the guideline of 100 kPa instantaneous overpressure can be achievable for substantial portions of the proposed de-watering dike system, for the charge weights considered. Figure 15 shows the 100 kPa isopleth for the charge weights considered above, and for a confinement value, k , of 800. The figure illustrates that limited lengths of the proposed dikes will be subjected to instantaneous overpressure exceeding 100 kPa. In these areas, mitigative procedures to discourage fish habitat development could be adopted, and might include the use of ‘bubbler’ systems, or alternative means such as the development of an ‘ice barrier’ to prevent fish from spawning or inhabiting specific areas.

4.0 CLOSURE

Production bench blast designs have been presented for the proposed open pits at the Meadowbank Gold Project. The blast designs have been based on standard design methods applied to the specific rock types and structure that is known to exist in the deposit areas. Designs for two blasthole sizes have been presented, 229 mm and 165 mm. Due to the strength of the iron formation and intermediate volcanic rocks, and to the nature of the structure in the proposed open pit area, a smaller blasthole size would provide better fragmentation. However, the smaller blasthole size could result in greater inaccuracy during drilling, particularly for the 12 m working bench heights proposed. The economics of a reduced blasthole diameter would need to be compared with the need to drill more blastholes due to the reduction in spacing and burden. Under these conditions, the drilling costs usually over-ride the fragmentation.

Where the development of the pit walls is beneath the de-watered lakes, wet blasthole conditions can be expected. Where the walls are developed within permafrost beneath the existing land mass, drier blasthole conditions may be encountered, although actual conditions will remain unknown until the development phase. Two charge tables have been presented: one for wet blasthole conditions using a doped emulsion of 70:30 Emulsion/AN, and the other for dry blasthole conditions using a Emulsion/AN ratio of 30:70.

Analyses indicate that Peak Particle Velocities (PPV) along portions of the upstream (lake side) face of the de-watering dikes will exceed the fish spawning habitat guideline threshold of 13 mm/s, based on operating bench height of 12 m and full charge weight. Analyses indicate that the guideline threshold of 100 kPa for instantaneous overpressure is achievable for substantial portions of the dikes for the charge weights considered.

Along portions of the dikes where fisheries guidelines are exceeded, mitigative methods may include modifications to blasting designs to incorporate lower bench heights and lighter charge weights as described above, as well as the use of ‘bubbler’ systems along the upstream face of the dikes in specific areas. These ‘bubbler’ systems could be operated during blasting to discourage fish along the upstream embankment face. Alternatively, in areas where fisheries guidelines for blasting may be exceeded, the upstream (lake side) dike width could be increased by dumping of additional rock fill material, and thereby increasing the setback distance from the blasting.

Analyses indicate that peak particle velocity thresholds of 50 mm/s for limiting damage to the dike structures may be exceeded along certain portions of the proposed dike alignments. However, the threshold of 50 mm/s is likely conservative, based on experience with other mines in the north, but is considered to be appropriate for this level

of study. Furthermore, the peak particle velocities experienced by the dikes can be effectively managed, if necessary, by modifications to the blast design.

During mine development, a vibration monitoring program will be required in order to measure the response of the de-watering dikes and tailings dike to pit blasting, and to measure peak particle velocities on the upstream (lake side) of the dikes to assess the blast designs.

GOLDER ASSOCIATES LTD.

Cameron J. Clayton, P.Geo.
Mining Group

Reviewed By:

W.W. (Bill) Forsyth, P.Eng.
Principal

CJC/WWF/vee
03-1413-427

N:\FINAL\2003\1413\03-1413-427\RPT0210 - BLAST DESIGN.DOC

REFERENCES

Atlas Powder Company. **Explosives and Rock Blasting**. Field Technical Operations, Atlas Powder Company, Dallas, Texas, 1987.

Charlie, W. A., Doehring, D. O., and Lewis, W.A. (1987). “Explosive Induced Damage Potential to Earthfill Dams and Embankments”, Proc. 13th Conference on Explosives and Blasting Technique, Society of Explosives Engineers, Annual Meeting, Feb. 1-6, Miami.

Cunningham, Claude. “The Kuz-Ram Model for Prediction of Fragmentation from Blasting”, First International Symposium on Rock Fragmentation by Blasting, Lulea, Sweden, 1983.

Cunningham, Claude. “Fragmentation Estimations and the Kuz-Ram Model – Four Years On”, 1987.

Golder Associates Ltd. **Pre-Feasibility Geotechnical Studies, Third Portage Deposit, Meadowbank Gold Project, Northwest Territories**. Report, February, 1999.

Golder Associates Ltd. **1997 Geotechnical Investigations, Meadowbank Gold Project, Northwest Territories**. Report, December, 1997.

Golder Associates Ltd. **Goose Island Pit Slope Design Criteria**. Technical Memorandum, July, 2003.

Golder Associates Ltd. **North Portage Pit Slope Design Criteria**. Technical Memorandum, October, 2003.

Golder Associates Ltd. **Third Portage Pit Slope Design Criteria**. Technical Memorandum, December, 2003.

Golder Associates Ltd. **Vault Pit Slope Design Criteria**. Technical Memorandum, January, 2004.


Golder Associates Ltd. **Preliminary Estimates of Peak Particle Velocity Along Meadowbank Dikes**. Technical Memorandum, November, 2003.


Golder Associates Ltd. **Summary of Rock Quality and Estimates of In-Situ Deformation Modulus and Pit Inflows – Portage Pit Area**. Technical Memorandum, October, 2003.

Hoek, E., and Bray, J.W. **Rock Slope Engineering**, Revised 3rd Edition, Institution of Mining and Metallurgy, London, 1981.

Hoek, E. and Brown, E.T. “Practical Estimates of Rock Mass Strength”, International Journal of Rock Mechanics and Mining Sciences, 1997?.


Lilly, P.A. “An Empirical Method of Assessing Rock Mass Blastability”, Large Open Pit Mining Conference, Newman, Australia, 1986.






REVISION DATE: 04/02/05 2:18pm By: mcg
CADD FILE: N:\Blue-Graphics Projects\2003\1413\03-1413-427\Drafting\Basemap\031413427Base1.dwg

- REFERENCES**
- 1) Drawing taken from AMEC, Dated 28-01-04, Drawing # A1-131395-100-C-0001
Revision A - OVERALL SITE PLAN YEAR 1-5.

PROJECT		CUMBERLAND RESOURCES LTD.			
TITLE		GENERAL SITE PLAN			
	PROJECT No.	03-1413-427	FILE No.	031413427BASE1	
	DESIGN	CJC	05JAN2004	SCALE	AS SHOWN
	CADD	RCR	05JAN2004	REV.	A
	CHECK				
REVIEW					
		FIGURE 2			

CADD FILE: N:\Bur-Graphics\Projects\2003\1413\03-1413-427\4300\Drafting\cad\031413427SK03.dwg
REVISION DATE: 04/01/27 9:51am By: sreddy



LEGEND

LITHOLOGY : ROCK TYPE

IF*: iron formation
QM: chert > magnetite
MQ: magnetite > chert

IVchl: vfg-aphanitic chl-rich sediment
(transition between clastic & chemical sediments,
correlates with IFQM/IFMQ along strike)

IV*: intermediate volcanics
c: chlorite alteration
cs: chlorite/sericite alteration
sc: sericite/chlorite alteration

IVs: intermediate volcanics,
strong sericite alteration

IVs(sil): IVs with silicification

IVbio: intermediate volcanics,
biotite alteration

IVlt: intermediate volcanics,
lapilli tuff

QIVT: quartz-eye intermediate volcanic tuff

IVT: tuffaceous felsic volcanics,
lapilli tuff (grain size > 2mm)

FV: felsic volcanics

IVA: intermediate polymictic agglomerate,
fragments & clasts > 4cm

QV: quartz vein

QCV: quartz carbonate vein

QCCV: quartz calcite vein

FD: felsic dyke

QFP: quartz-feldspar porphyry

FQP: feldspar-quartz porphyry

QP: quartz porphyry

FP: feldspar porphyry

GR: granite

QTZT: quartzite

QPC: quartz pebble conglomerate

LAMP: lamprophyre dyke

CB: carbonate

Chert: chert

MYL: mylonite

MV: mafic volcanic

UM*: ultramafic volcanics
A: actinolitic
S: serpentinized
V: massive flow
f: foliated

FLT: fault

ORE SHELL

REFERENCES

1) Cumberland Resources Ltd. drawing filename 1150S03.dwg
dated September 2003.

PROJECT

CUMBERLAND
RESOURCES LTD.

TITLE


GOOSE ISLAND
TYPICAL CROSS SECTION
SECTION 11+50S

PROJECT No.	03-1413-427	FILE No.	031413427SK03
DESIGN	CJC	23 JAN 04	SCALE AS SHOWN REV. A
CADD	SRR	27 JAN 04	
CHECK	CJC	27 JAN 04	
REVIEW			

FIGURE 3

CADD FILE: N:\Bur-Graphics\Projects\2003\1413\03-1413-427\4300\Drafting\cad\031413427SK04.dwg

REVISION DATE:04/01/27 10:26am By: sreddy




LEGEND

LITHOLOGY : ROCK TYPE

- IF*: iron formation
 - QM: chert > magnetite
 - MQ: magnetite > chert
- IVchl: vfg-aphanitic chl-rich sediment (transition between clastic & chemical sediments, correlates with IFQM/IPMQ along strike)
- IV*: intermediate volcanics
 - c: chlorite alteration
 - cs: chlorite/sericite alteration
 - sc: sericite/chlorite alteration
- IVs: intermediate volcanics, strong sericite alteration
- IVs(sil): IVs with silicification
- IVbio: intermediate volcanics, biotite alteration
- IVlt: intermediate volcanics, lapilli tuff
- QIVT: quartz-eye intermediate volcanic tuff
- IVT: tuffaceous felsic volcanics, lapilli tuff (grain size > 2mm)
- FV: felsic volcanics
- IVA: intermediate polymictic agglomerate, fragments & clasts > 4cm
- QV: quartz vein
- QCV: quartz carbonate vein
- QCCV: quartz calcite vein
- FD: felsic dyke
- QFP: quartz-feldspar porphyry
- FQP: feldspar-quartz porphyry
- QP: quartz porphyry
- FP: feldspar porphyry
- GR: granite
- QTZT: quartzite
- QPC: quartz pebble conglomerate
- LAMP: lamprophyre dyke
- CB: carbonate
- Chert: chert
- MYL: mylonite
- MV: mafic volcanic
- UM*: ultramafic volcanics
 - A: actinolitic
 - S: serpentinized
 - V: massive flow
 - f: foliated
- FLT: fault
- ORE SHELL

REFERENCES


- 1) Cumberland Resources Ltd. drawing filename 120SF99.dwg dated March 30, 2003.



PROJECT		CUMBERLAND RESOURCES LTD.			
TITLE		THIRD PORTAGE DEPOSIT TYPICAL CROSS SECTION SECTION 1+20S			
	PROJECT No.	03-1413-427	FILE No.	031413427SK04	
	DESIGN	CJC	23 JAN 04	SCALE	AS SHOWN
	CADD	SRR	27 JAN 04	REV.	A
	CHECK	CJC	27 JAN 04	FIGURE 4	
REVIEW					

CADD FILE: N:\Bur-Graphics\Projects\2003\1413-03-1413-427\4300\Drafting\cad\031413427SK05.dwg

REVISION DATE: 04/01/27 10:11am By: sreddy



LEGEND

LITHOLOGY : ROCK TYPE


- IF*: iron formation
 - QM: chert > magnetite
 - MQ: magnetite > chert
- IVchl: vfg-aphanitic chl-rich sediment (transition between clastic & chemical sediments, correlates with IPQM/IPMQ along strike)
- IV*: intermediate volcanics
 - c: chlorite alteration
 - cs: chlorite/sericite alteration
 - sc: sericite/chlorite alteration
- IVs: intermediate volcanics, strong sericite alteration
- IVs(sil): IVs with silicification
- IVbio: intermediate volcanics, biotite alteration
- IVit: intermediate volcanics, lapilli tuff
- QIVT: quartz-eye intermediate volcanic tuff
- IVT: tuffaceous felsic volcanics, lapilli tuff (grain size > 2mm)
- FV: felsic volcanics
- IVA: intermediate polymictic agglomerate, fragments & clasts > 4cm
- QV: quartz vein
- QCV: quartz carbonate vein
- QCCV: quartz calcite vein
- FD: felsic dyke
- QFP: quartz-feldspar porphyry
- FQP: feldspar-quartz porphyry
- QP: quartz porphyry
- FP: feldspar porphyry
- GR: granite
- QTZT: quartzite
- QPC: quartz pebble conglomerate
- LAMP: lamprophyre dyke
- CB: carbonate
- Chert: chert
- MYL: mylonite
- MV: mafic volcanic
- UM*: ultramafic volcanics
 - A: actinolitic
 - S: serpentinized
 - V: massive flow
 - f: foliated


FLT: fault

ORE SHELL

REFERENCES

1) Cumberland Resources Ltd. drawing filename 1225N02.dwg dated April 22, 2003.




PROJECT					
CUMBERLAND RESOURCES LTD.					
TITLE					
NORTH PORTAGE DEPOSIT TYPICAL CROSS SECTION SECTION 12+25N					
 Golder Associates	PROJECT No. 03-1413-427		FILE No. 031413427SK05		
	DESIGN	CJC 23 JAN 04	SCALE	AS SHOWN	REV. A
	CADD	SRR 27 JAN 04	FIGURE 5		
	CHECK	CJC 27 JAN 04			
	REVIEW				



- IF*: iron formation
 - QM: chert > magnetite
 - MQ: magnetite > chert
- IVchl: vfg-aphanitic chl-rich sediment
(transition between clastic & chemical sediments,
correlates with IFQM/IFMQ along strike)
- IV*: intermediate volcanoclastics
 - c: chlorite alteration
 - cs: chlorite/sericite alteration
 - sc: sericite/chlorite alteration

- ORE SHELL

1) Cumberland Resources Ltd. drawing filename
4675NO1.dwg dated December 6, 2001.



PROJECT

CUMBERLAND


RESOURCES LTD.

TITLE

VAULT DEPOSIT

TYPICAL CROSS SECTION

SECTION 46+75N



Golder


Associates

PROJECT	No.	03-1413-427
DESIGN	CJC	10 DEC 03
CADD	SRR	27 JAN 04
CHECK	CJC	27 JAN 04
REVIEW		

FILE No.	031413427SK06
SCALE	AS SHOWN
REV.	A

FIGURE 6


SECTION



APPROXIMATE BLAST CONFIGURATION

	CHARGE (%)	BURDEN			SPACING		
		d = 229	d = 165		d = 229	d = 165	
PRODUCTION	100	30d	6.9m	5.0m	35d	7.9m	5.7m
BUFFER	67	21d	4.8m	3.5m	24d	5.5m	4.0m
TRIM	33	15d	3.4m	2.5m	18d	4.1m	3.0m

PLAN



SCHEMATIC ONLY

Not to Scale

PROJECT


**CUMBERLAND
RESOURCES LTD.**

TITLE


**CONCEPTUAL CONTROLLED
BLAST DESIGN
GENERAL CONFIGURATION**



PROJECT No. 03-1413-427			FILE No. P427-01	
DESIGN	CJC	02DEC03	SCALE	AS SHOWN
CADD	SS	02DEC03	REV.	A
CHECK	CJC	02DEC03	FIGURE 7	
REVIEW				

SECTION**APPROXIMATE BLAST CONFIGURATION**

	CHARGE (%)	BURDEN			SPACING		
		d = 229	d = 165		d = 229	d = 165	
PRODUCTION	100	30d	6.9m	5.0m	35d	8.0m	5.8m
BUFFER	67	20d	4.6m	3.3m	24d	5.5m	4.0m
TRIM	33	15d	3.4m	2.5m	17d	3.9m	2.8m

PLAN**SCHEMATIC ONLY**

Not to Scale

PROJECT


**CUMBERLAND
RESOURCES LTD.**

TITLE

**CONCEPTUAL CONTROLLED
BLAST DESIGN FOR
SHALLOW DIPPING ORE**


PROJECT No. 03-1413-427			FILE No. P421-01		
DESIGN	CJC	02DEC03	SCALE	AS SHOWN	REV. A
CADD	SS	02DEC03	FIGURE 8		
CHECK	CJC	02DEC03			
REVIEW					

SECTION



APPROXIMATE BLAST CONFIGURATION							
	CHARGE (%)	BURDEN			SPACING		
			d = 229	d = 165		d = 229	d = 165
PRODUCTION	100	30d	6.9m	5.0m	35d	8.0m	5.8m
BUFFER	67	20d	4.6m	3.3m	24d	5.5m	4.0m
TRIM	33	15d	3.4m	2.5m	17d	3.9m	2.8m

PLAN



SCHEMATIC ONLY

Not to Scale

PROJECT

**CUMBERLAND
RESOURCES LTD.**


TITLE

**CONCEPTUAL CONTROLLED
BLAST DESIGN IN
AREAS OF POTENTIAL TOPPLING**




PROJECT No. 03-1413-427			FILE No. P427-01	
DESIGN	CJC	02DEC03	SCALE	AS SHOWN
CADD	SS	02DEC03	REV.	A
CHECK	CJC	02DEC03	FIGURE 9	
REVIEW				


Charge Weight as a Function of Distance from Blast
Constant Peak Particle Velocity = 13 mm/s
site factor b = -1.6 for downhole blasting



— k=400 - - - k=800 k=1500

PROJECT		CUMBERLAND RESOURCES LTD.			
TITLE		CHARGE WEIGHT vs DISTANCE FROM BLAST - PPV = 13mm/s			
		PROJECT No. 03-1413-427		FILE No. FIGURE 3	
		DESIGN	CJC	28JAN04	SCALE NTS
		CADD	SS	28JAN04	REV.
		CHECK	CJC	28JAN04	FIGURE 10
		REVIEW			

CADD FILE: N:\Bur-Graphics\Projects\2003\1413\03-1413-427\4300\Drafting\cad\031413427SK11.dwg
REVISION DATE: 04/01/27 4:46pm By: sreddy



LEGEND

- 86 kg Charge Weight, 122m Offset
- 250 kg Charge Weight, 208m Offset
- 420 kg Charge Weight, 269m Offset


Confinement, $k = 800$



NOTES

- 1) Area behind dykes is de-watered during operations.


REFERENCES

- 1) Drawing taken from AMEC, dated 28-01-04, Drawing # A1-131395-100-C-0001
Revision A - OVERALL SITE PLAN YEAR 1-5.




PROJECT		CUMBERLAND RESOURCES LTD.			
TITLE		PEAK PARTICLE VELOCITY 13 mm/s ISOPLETH			
	PROJECT No. 03-1413-427		FILE No. 031413427SK11		
	DESIGN	CJC 23 JAN 04	SCALE AS SHOWN REV. A		
	CADD	SRR 27 JAN 04			
	CHECK	CJC			
	REVIEW				


Charge Weight as a Function of Distance from Blast
Constant Peak Particle Velocity = 50 mm/s
site factor b = -1.6 for downhole blasting



— k=400 - - - k=800 - . - . k=1500

PROJECT		CUMBERLAND RESOURCES LTD.			
TITLE		CHARGE WEIGHT vs DISTANCE FROM BLAST - PPV = 50mm/s			
		PROJECT No. 03-1413-427		FILE No. FIGURE 3	
		DESIGN	CJC	28JAN04	SCALE
		CADD	SS	28JAN04	REV.
		CHECK	CJC	28JAN04	FIGURE 12
		REVIEW			

CADD FILE: N:\Bur-Graphics\Projects\2003\1413\03-1413-427\4300\Drafting\cad\031413427SK13.dwg
REVISION DATE: 04/01/27 4:46pm By: sreddy



LEGEND

- 86 kg Charge Weight, 53m Offset
- 250 kg Charge Weight, 89m Offset
- 420 kg Charge Weight, 116m Offset


Confinement, $k = 800$

NOTES

1) Area behind dykes is de-watered during operations.

REFERENCES


1) Drawing taken from AMEC, dated 28-01-04, Drawing # A1-131395-100-C-0001
Revision A - OVERALL SITE PLAN YEAR 1-5.



PROJECT		CUMBERLAND RESOURCES LTD.	
TITLE		PEAK PARTICLE VELOCITY 50 mm/s ISOPLETH	
PROJECT No.	03-1413-427	FILE No.	031413427SK13
DESIGN	CJC	23 JAN 04	SCALE AS SHOWN REV. A
CADD	SRR	27 JAN 04	
CHECK	CJC		
REVIEW			

FIGURE 13

Setback Distance as a Function of Charge Weight
to Achieve 100 kPa Instantaneous Overpressure
site factor $b = -1.6$ for downhole blasting conditions




—◇— k = 400 —□— k = 800 —△— k = 1500

PROJECT		CUMBERLAND RESOURCES LTD.	
TITLE			
CHARGE WEIGHT vs SETBACK DISTANCE FOR 100 kPa OVERPRESSURE			
PROJECT No. 03-1413-427		FILE No. FIGURE 3	
DESIGN	CJC	28JAN04	SCALE
CADD	SS	28JAN04	REV.
CHECK	CJC	28JAN04	FIGURE 14
REVIEW			



REVISION DATE: 04/01/27 4:04pm By: sreddy CADD FILE: N:\Bur-Graphics\Projects\2003\1413\03-1413-427\4300\Drafting\cad\031413427SK15.dwg



LEGEND

- 86 kg Charge Weight, 40m Offset
- 250 kg Charge Weight, 69m Offset
- 420 kg Charge Weight, 89m Offset


Confinement, k = 800


NOTES

1) Area behind dykes is de-watered during operations.

REFERENCES

1) Drawing taken from AMEC, dated 28-01-04, Drawing # A1-131395-100-C-0001
Revision A - OVERALL SITE PLAN YEAR 1-5.





PROJECT		CUMBERLAND RESOURCES LTD.		
TITLE		INSTANTANEOUS OVERPRESSURE 100kPa ISOPLETH		
	PROJECT No.	03-1413-427	FILE No.	031413427SK15
	DESIGN	CJC	23 JAN 04	SCALE AS SHOWN
	CADD	SRR	27 JAN 04	REV. A
	CHECK	CJC		
REVIEW				
FIGURE 15				

APPENDIX I


FRAGMENTATION PREDICTIONS


**30:70 ANFO:Emulsion
165 mm Blasthole**




PROJECT				
CUMBERLAND RESOURCES LTD.				
TITLE				
IRON FORMATION FRAGMENTATION PREDICTION 6m BENCH - 165mm BLASTHOLE				
		PROJECT No. 03-1413-427		FILE No. FIGURE 3
		DESIGN	CJC 28JAN04	SCALE
		CADD	SS 28JAN04	REV.
		CHECK	CJC 28JAN04	FIGURE I-1
		REVIEW		


30:70 ANFO/Emulsion 165mm Blasthole




PROJECT				
CUMBERLAND RESOURCES LTD.				
TITLE				
ULTRAMAFIC VOLCANIC FRAGMENTATION PREDICTION 12m BENCH - 165mm BLASTHOLE				
		PROJECT No. 03-1413-427		FILE No. FIGURE 3
		DESIGN	CJC	28JAN04
		CADD	SS	28JAN04
		CHECK	CJC	28JAN04
		REVIEW		
				FIGURE I-2


30:70 ANFO/Emulsion 165 mm blasthole




PROJECT					CUMBERLAND RESOURCES LTD.	
TITLE					INTERMEDIATE VOLCANIC FRAGMENTATION PREDICTION 12m BENCH - 165mm BLASTHOLE	
			PROJECT No. 03-1413-427		FILE No. FIGURE 3	
			DESIGN	CJC	28JAN04	SCALE
			CADD	SS	28JAN04	REV.
			CHECK	CJC	28JAN04	FIGURE I-3
			REVIEW			


30:70 ANFO/Emulsion 229 mm Blasthole



PROJECT				
CUMBERLAND RESOURCES LTD.				
TITLE				
ULTRAMAFIC VOLCANIC FRAGMENTATION PREDICTION 12m BENCH - 229mm BLASTHOLE				
		PROJECT No. 03-1413-427		FILE No. FIGURE 3
		DESIGN	CJC	28JAN04
		CADD	SS	28JAN04
		CHECK	CJC	28JAN04
		REVIEW		
FIGURE I-4				REV.

12m BENCH
30:70 ANFO/Emulsion
229 mm Blasthole



PROJECT					CUMBERLAND RESOURCES LTD.	
TITLE					INTERMEDIATE VOLCANIC FRAGMENTATION PREDICTION 12m BENCH - 229mm BLASTHOLE	
			PROJECT No. 03-1413-427		FILE No. FIGURE 3	
			DESIGN	CJC	28JAN04	SCALE
			CADD	SS	28JAN04	REV.
			CHECK	CJC	28JAN04	FIGURE I-5
			REVIEW			

Golder Associates Ltd.

500 – 4260 Still Creek Drive
Burnaby, British Columbia, Canada V5C 6C6
Telephone (604) 296-4200
Fax (604) 298-5253



May 25, 2004

03-1413-427/4300

Cumberland Resources Ltd.
Suite 950, One Bentall Centre
505 Burrard Street
Vancouver, BC
V7X-1M4

Attention: Mr. Brad Thiele

RE: BLASTING REPORT ADDENDUM

Dear Mr. Thiele:

1.0 INTRODUCTION

This document is an Addendum to a more detailed report titled “Blast Design, Meadowbank Gold Project, Nunavut” issued February 10, 2004, and should be read in conjunction with that report.

A request was made by Cumberland Resources to consider the use of 3-m high benches and 76-mm (3”) diameter for blasting both ore and waste at the Meadowbank Project. It is understood that issues related to grade control and blasting vibrations are the primary driving influences behind the use of smaller diameter blastholes with lower bench heights.

2.0 EXPLOSIVE TYPE

The explosive selected for blasting with the larger diameter holes would not be suitable for use with the smaller diameter blastholes due to sensitivity issues. Consequently, a more sensitive emulsion product will be required. The emulsion product would have to



be sensitized (either with gas, micro-balloons or with small amounts of a molecular explosive) to ensure detonation in the smaller diameter blastholes. This will increase the cost of the explosive product. The product would be pumped directly to the bottom of the blastholes.

The following table summarizes typical properties of sensitized emulsion products.

Table 1: Typical Properties of Sensitized ANFO/Emulsion Mixtures for Small Diameter Blastholes

ANFO (%)	Emulsion (%)	Density (g/cc)	Velocity of Detonation (m/s)	RWS/RBS	Minimum Diameter (mm)	Water Resistance	Loading
	100	1.20	5700	77/113	75	Excellent	Pump
20	80	1.23	5400	82/123	90	Excellent	Pump
30	70	1.24	4800	84/127	100	Excellent	Pump
50	50	1.27	4700	93/130	125	Good	Auger

Reference: Dyno Nobel, Inc.

3.0 PRODUCTION BLAST DESIGN

The following tables summarize blast designs developed for the smaller blasthole diameter, lower bench height, and a straight emulsion product.

Table 2: Blasthole Parameters

	Units	76 mm Diameter Blasthole	
		Waste	ORE
Working Bench Height	m	3	3
Blasthole Diameter	mm	76	76
Hole Inclination	deg	90	90
Subdrill	m	0.6	0.6
TOTAL DRILLED DEPTH	m	3.6	3.6

Table 3: Blast Patterns

Blasthole Pattern	Staggered
Blast Sequence	En Echelon
Spacing/Burden Ratio	1:1.15
Number of Rows	5
Number of Holes per Row	10

Table 4: Charge Table – (100% Emulsion)

Blasting Variables	Units	Ore	IV and Quartzite	Ultramafic
Bench Height	m	3	3	3
Subdrill	m	0.3	0.3	0.3
Stemming Length	m	1.2	1.2	1.2
Charge Length	m	2.1	2.1	2.1
Linear Charge Density	kg/m	5.9	5.9	5.9
Burden	m	2.4	2.3	2.3
Spacing	m	2.7	2.6	2.6
Burden Volume	m ³	19	18	18
Explosives Mass per Hole, Q	kg	12.4	12.4	12.4
Powder Factor, PF	kg/m³	0.64	0.69	0.69

The general blast configurations are the same as those proposed for the larger diameter blastholes with the obvious changes to the burden and spacing dimensions. The shorter blastholes lengths are more amenable to following a gentle sloping footwall and should not require the “stab” holes proposed for the larger bench heights.

3.1 Drilling

The change in cubic meter of rock broken per drilled meter is dramatically decreased using the smaller blasthole diameter. The change is from approximately 23 m³ for the 165 mm holes to 5.5 m³ for the 76 mm diameter holes. This represents a 76% reduction in the rock fragmentation volume for each meter of blasthole drilled. The smaller holes are less expensive to drill but many more are required to break the same volume of rock.

3.2 Wall Control

The general concept for wall control blasting does not change with the smaller blasthole diameter. The smaller holes will produce less damage to the wall rocks and will result in smoother, sounder wall conditions. However, the use of 3 m bench heights will result in a reduction in the overall slope angle for the final pit walls. This is because there will be a “step-out” of at least 1 m for every 3-m high bench to allow access for the drill. For example, for a design bench configuration of a 65 degree bench face angle with two 12-m high working benches to reach the final bench height of 24 m, and a 49 degree design inter-ramp angle, the effective inter-ramp angle will be approximately 47 degrees allowing for a 1 m “step-out”. If a 3 m working bench height is considered, this will require eight working benches to reach the final 24 m bench height, and will result in an effective inter-ramp angle of approximately 43 degrees, allowing a 1 m “step-out” on seven of the eight working benches for drill access.

3.3 Rock Fragmentation

The fragmentation was predicted using the Kuz-Ram model defined in the main text of the report. The following table summarizes the predicted rock fragmentation for the preceding design criteria, and for a five row blast pattern with ten holes per row. The fragmentation is predictably finer given improvement in energy distribution that results from the smaller burden and spacing dimensions. However, the tonnage per blast is lower than for the greater bench heights and larger blastholes proposed in the previous report. The predicted fragmentation curves are contained in Appendix I.

Table 5: Predicted Fragmentation

Rock Type	Bench Height, m	Hole Size, mm	t/blast, t ¹	Powder Factor, kg/m ³	50% passing, m	80% passing, m	Characteristic Size, m
Iron Formation	3 m	76	3,344	0.64	0.33	0.59	0.42
Ultramafic	3 m	76	2,422	0.69	0.22	0.39	0.28
Intermediate Volcanic	3 m	76	2,512	0.69	0.28	0.51	0.37

1. Assumes 5 rows and 10 holes per row.

The impact of the smaller hole diameters and bench heights on productivity should be assessed in greater detail. As an approximate assessment of this impact, consider a stripping ratio of about 7:1 for the Portage Pit area. Approximately 39,000 t/day of waste will need to be moved to feed the 5,500 t/day milling operation. Based on the smaller blast design, this would require about 16 blasts per day in waste assuming five rows and

ten holes per row. By comparison, a 6-m bench with 86 kg charge weight would move about 30,000 t/day in waste per blast, and a 12-m bench with 250 kg charge weight would move about 46,000 t/day in waste per blast.

4.0 BLAST INDUCED VIBRATION

The following sections summarize the results of previous analyses, and include additional analyses based on the revised production blast designs for the proposed 3-m bench height.

4.1 Minimum Setback Distance for Canadian Fisheries Guidelines

For the Meadowbank Site, three blast designs were previously assessed: the first assumed a charge weight per delay of 420 kg for 229 mm (9") blastholes and an operating bench height of 12 m, the second assumed a maximum charge weight of 250 kg for 165 mm (6½") blastholes and a bench height of 12 m, and the third assumed a charge weight of 86 kg for 165-mm blasthole and bench height of 6 m (see Golder Report on Blast Design, February 2004). An Emulsion:ANFO ratio of 70:30 was assumed for the first three cases. An additional scenario is considered here for a charge weight of 12 kg for a 76 mm blasthole and 3-m bench height. The fourth case assumes a sensitized emulsion product.

The PPV's were evaluated for the Second Portage Lake East Dike, the Third Portage Peninsula east shoreline, the Bay Dike, and the Goose Island east shoreline. Based on the current mine layout, estimates of the minimum distance from the estimated final production blast near the pit crest, to the point of concern (either the shoreline or the dike face), and estimates of the distance from the pit centre to the point of concern (either the shoreline or the dike face) were made. The PPV were evaluated based on these estimated distances.

By reducing the working bench height to 3 m within the waste rock and the ore, the charge weight per blasthole is reduced. The following table summarizes the estimated PPV at points of concern either along the upstream face of the dike, or along the shoreline, whichever is closest, for a 12 kg charge weight, 76 mm blasthole, and 3 m bench height.

Table 6: Preliminary Estimate of Peak Particle Velocities based on Production Blasting (12-kg charge weight per delay; 3-m bench height, 76-mm blasthole)

Location	Distance to Point of Concern (m)		PPV (mm/sec)		
			k=400	k=800	k=1500
Second Portage Lake East Dike	Pit Crest to U/S Dike Face	255	<1	1	2
	Pit Centre to U/S Dike Face	375	<1	<1	1
Third Portage Peninsula	Pit Crest to Shoreline	101	2	4	7
	Pit Centre to Shoreline	295	<1	1	1
Bay Dike	Pit Crest to U/S Dike Face	145	1	2	4
	Pit Centre to U/S Dike Face	355	<1	<1	1
Goose Island	Pit Crest to U/S Dike Face*	210*	1	1	2
	Pit Centre to U/S Dike Face*	500*	<1	<1	1

Distances are measured from approximate location of last production blast, not final trim blast.

Values of PPV in bold exceed 13 mm/sec.

*The Goose Island Dike alignment has been modified since the previous report. The new distance and results reflect the current concept for the dike alignment.

The following table summarizes the results of the analyses for the four charge weights that were considered, assuming a confinement value, k, of 800, which is considered to be appropriate for the Meadowbank Project based on experience at other northern mines.

Table 7: Summary of Estimates of Peak Particle Velocities based on Production Blasting Charge Weights (k=800)

Location	Distance to Point of Concern (m)		PPV (mm/sec)			
			12kg/3m bench	86kg/6m bench	250kg/12m bench	420kg/12m bench
Second Portage Lake East Dike	Pit Crest to U/S Dike Face	255	1	4	9	14
	Pit Centre to U/S Dike Face	375	<1	2	5	8
Third Portage Peninsula	Pit Crest to Shoreline	101	4	18	41	62
	Pit Centre to Shoreline	295	1	3	7	11
Bay Dike	Pit Crest to U/S Dike Face	145	2	10	23	35
	Pit Centre to U/S Dike Face	355	<1	2	6	8
Goose Island	Pit Crest to U/S Dike Face*	210*	1	5	13	36
	Pit Centre to U/S Dike Face*	500*	<1	1	3	9

Distances are measured from approximate location of last production blast, not final trim blast.

Values of PPV in bold exceed 13 mm/sec.

*The Goose Island Dike alignment has been modified since the previous report. The new distance and results reflect the current concept for the dike alignment.

The analysis indicates that, for the charge weight of 12 kg and bench height of 3 m, the peak particle velocity along the upstream (lake side) dike faces will not exceed 13 mm/s. With the exception of a short segment of the Third Portage Pit wall adjacent to the east shoreline of the Third Portage Peninsula, charge weights of 86 kg on 6 m benches will result in PPV less than the required 13 mm/s. Finally, with the exception of the segment of the Third Portage Pit wall just described, and short segments of the south end of the Goose Island Dike re-alignment, charge weights of 250 kg and 12 m bench heights can be used without exceeding the required 13 mm/s guideline.

For the portions of the dike or shoreline where the 13 mm/s guideline is exceeded, modified blast designs consisting of lower charge weights on lower bench heights have been shown to result in PPV that meet the guideline requirement. Alternatively, additional fill materials could be placed along the shoreline or dike upstream (lake side) face to increase the distance from the blasting area.

Figure 1 presents the relationship between charge weight and distance from blast for a constant Peak Particle Velocity of 13 mm/s for lower charge weights. The figure can be used as a guide to estimate the maximum allowable charge weight per blasthole that will not exceed a peak particle velocity of 13 mm/s at a specified distance from the blast.

The minimum setback distances to achieve a PPV of 13 mm/s have been estimated for the various values of 'k', and for the four potential charge weights per delay used in the above PPV estimates. The following table summarizes the estimates of minimum setback required to achieve a PPV value of 13 mm/s.

**Table 8: Minimum Setback Distance for 13 mm/s
Peak Particle Velocity Guideline**

k	12 kg charge weight per delay (3 m bench, 76 mm hole)	86 kg charge weight per delay (6 m bench, 165 mm hole)	250 kg charge weight per delay, (12 m bench, decked charge, 229 mm hole)	420 kg charge weight per delay, (12 m bench, 229 mm hole)
	Minimum Setback Distance to Achieve PPV = 13 mm/s			
400	30 m	79 m	135 m	175 m
800	46 m	122 m	208 m	269 m
1500	67 m	180 m	308 m	399 m

The relationships presented in the above table are shown on Figure 2 for a confinement value, k, of 800.

4.2 Minimum Setback Distance for Threshold Damage Levels

General guidelines for blasting nears dams indicate vibration damage thresholds on the order of 50 mm/s to be reasonable for dams having medium to dense sand or silts within the dam or foundation materials. The following table summarizes the estimates of minimum setback required to achieve a PPV value of 50 mm/s for the charge weights considered.

Table 9: Comparison of Minimum Setback Distance for a Peak Particle Velocity of 50 mm/s for Various Blast Configurations

k	12 kg charge weight per delay (3 m bench, 76 mm hole)	86 kg charge weight per delay (6 m bench, 165 mm hole)	250 kg charge weight per delay, (12 m bench, decked charge, 229 mm hole)	420 kg charge weight per delay, (12 m bench, 229 mm hole)
	Minimum Setback Distance to Achieve PPV = 50 mm/s			
400	13 m	32 m	58 m	75 m
800	20 m	53 m	89 m	116 m
1500	29 m	78 m	133 m	172 m

Figure 3 presents the relationship between charge weight and distance from blast for a constant Peak Particle Velocity of 50 mm/s. The relationships presented in the above table are shown on Figure 4 for a confinement value, k, of 800.

The analysis indicates that for the 80-m toe setback currently assumed for the dikes at the Meadowbank Project, a charge weight of up to 200 kg per delay could be used resulting in PPV less than 50 mm/s, based on the assumptions presented in this report. Additional blast monitoring during construction will be required to confirm the assumptions on which these results are based.

4.3 Instantaneous Pressure Change for Canadian Fisheries Guidelines

The required setback distance for confined explosives to achieve the 100 kPa instantaneous pressure change guideline can be estimated from relationships presented in "Guidelines for the Use of Explosives in or Near Canadian Fisheries Waters" (Wright and Hopky, 1998).

The following properties were used to assess the minimum setback distance.

**Table 10: Properties Used to Assess Setback Distance for
Instantaneous Pressure Change**

Medium	Density, g/cm ³	Compressional Wave Velocity, cm/s
Water	1	146,300 ¹
Rock (Intermediate Volcanic)	2.8	457,200 ¹

1. Guidelines for the Use of Explosives in or Near Canadian Fisheries Waters; Wright and Hopky, 1998

Based on the above properties, the range of potential charge weights, and the range in confinement value, k, the following minimum setback distances, below which the 100 kPa overpressure guideline will not be exceeded, are estimated.

**Table 11: Minimum Setback Distance for Instantaneous
Pressure Change Guideline**

Charge Weight per Delay	Minimum Setback Distance, m		
kg	k=400	k=800	k=1500
12	10 m	15 m	22 m
86	26 m	40 m	60 m
250	45 m	69 m	102 m
420	58 m	89 m	132 m

The relationship between charge weight per delay and minimum setback distance to achieve the 100 kPa guideline for instantaneous pressure change is shown on Figure 5. The figure can be used as a guide to optimizing the blast designs. The relationships presented in the above table are shown on Figure 6 for a confinement value, k, of 800.

Based on the currently proposed de-watering dike configuration, the average distance from the pit crest to the outside (lake side) dike face will be on the order of 160 m. In order for the instantaneous pressure change measured on the outside (lake side) face of the dike to exceed 100 kPa, a charge weight in excess of 1300 kg would be required, based on the assumptions in this report. Consequently, for the range of charge weights considered in the analyses for the Meadowbank project, none will result in an instantaneous pressure change greater than 100 kPa.

5.0 CLOSING REMARKS

Cumberland is considering mining of both ore and waste at the Meadowbank Project using 3-m bench heights and small diameter (76 mm) blastholes. The reduced bench heights and small diameter blastholes will result in lighter charge weights, and hence lower vibration levels experienced on the outside (lake side) of the dikes. Based on the proposed 3-m bench configurations and 76 mm blasthole diameter, a 12 kg charge weight will be used.

An assessment of blast induced vibration and instantaneous pressure change was carried out to assess vibration levels resulting from the lower charge weights as these relate to Canadian fisheries guidelines. The maximum acceptable Peak Particle Velocity (PPV) resulting from the use of explosives in or near fisheries waters is 13 mm/s. The maximum acceptable instantaneous pressure change is 100 kPa.

The results of the assessment indicate that for the proposed 3-m bench configuration and 12 kg charge weight, PPV on the outside (lake side) of the dikes will not exceed 13 mm/s, and that with the exception of a short segment of the Third Portage Pit wall adjacent to the east shoreline of the Third Portage Peninsula, charge weights of 86 kg on 6 m benches will result in PPV less than the guideline 13 mm/s. Furthermore, with the exception of the segment of the Third Portage Pit wall just described, and short segments of the south end of the Goose Island Dike re-alignment, charge weights of 250 kg and 12 m bench heights can be used without exceeding the required 13 mm/s guideline. For the portions of the dike or shoreline where the 13 mm/s guideline is exceeded, modified blast designs can be used to meet the guideline requirements. Alternatively, additional fill materials could be placed along the shoreline or dike upstream (lake side) face to increase the distance from the blasting area.

The instantaneous pressure change along the upstream (lake side) face of the dikes is predicted to be less than the 100 kPa guideline for all charge weights that are currently being considered for the Meadowbank Project.

An assessment of blast induced vibration as it relates to threshold damage levels for structures was carried out. General guidelines for blasting near dams indicate vibration damage thresholds on the order of 50 mm/s to be acceptable for dams having medium to dense sand or silts within the dam or foundation materials. Based on the proposed toe setback of 80 m, a 3-m bench height and 12-kg charge weight, and assumed site conditions and confinement, the analyses indicate that the 50 mm/s guideline will not be exceeded at the toe of the proposed de-watering dikes and tailings dike. The analyses indicate that for the 80-m toe setback currently assumed for the dikes at the Meadowbank Project, a charge weight of up to 200 kg per delay could be used without exceeding PPV

of 50 mm/s at the toe, based on the assumptions presented in this report, and the preceding report. Where blast induced vibration is predicted to exceed general guidelines, modified blast designs can be used to reduce vibration levels.

The Vault Dike has not been considered in the analyses. The Vault Dike lies some 750 m from the nearest crest of the Vault Pit. Consequently, the proposed bench configurations and charge weights currently being considered will not exceed the Canadian fisheries guidelines for blasting induced vibration or for instantaneous pressure change.

It is recommended that the modified blast designs consisting of smaller blasthole diameter and lower bench heights only be used in those areas of the final pit walls where PPV along the lake shoreline, or along the upstream (lake side) of the dikes, is predicted to exceed guidelines, or within the ore zone where grade control is essential. The larger blast configurations (either 6 m or 12 m benches) should be adopted elsewhere within the waste rock. The smaller charge weights and lower bench heights will require more blasts on a daily basis to move the required amount of waste rock to obtain the daily ore tonnage to feed the mill. The number of blasts required per day for the lower bench heights may be impractical from a longer term operational perspective.

During mine development, a vibration monitoring program will be required in order to measure the response of the de-watering dikes and tailings dike to pit blasting, and to measure peak particle velocities on the upstream (lake side) of the dikes to assess the blast designs.



Yours very truly,


GOLDER ASSOCIATES LTD.

Cameron J. Clayton, P.Geo.
Mining Group



W.W. Forsyth, P.Eng.
Principal

CJC/WWF/vee
03-1413-427/4300








PROJECT				
CUMBERLAND RESOURCES LTD.				
TITLE				
CHARGE WEIGHT vs DISTANCE FROM BLAST - PPV = 13mm/s				
		PROJECT No.	03-1413-427	FILE No. FIGURE 4
		DESIGN	CJC 28JAN04	SCALE NTS
		CADD	SS 28JAN04	REV. 0
		CHECK	CJC 28JAN04	FIGURE 1
		REVIEW	10MAR04	

CADD FILE: N:\Bur-Graphics\Projects\2003\1413\03-1413-427\4300\Drafting\cad\031413427-F02.dwg
REVISION DATE: 04/03/9 10:35am By: sreddy



LEGEND

	12 kg Charge Weight, 46m Offset	Confinement, k = 800
	86 kg Charge Weight, 122m Offset	
	250 kg Charge Weight, 208m Offset	
	420 kg Charge Weight, 269m Offset	
	Aquatic areas that may experience 13mm/s vibration levels for a specific charge weight.	


NOTES

1) Area behind dikes is de-watered during operations.



REFERENCES

1) Drawing taken from AMEC, dated 28-01-04, Drawing # A1-131395-100-C-0001 Revision A - OVERALL SITE PLAN YEAR 1-5.

2) Golder Report on Blast Design, Feburary, 2004.



PROJECT		CUMBERLAND RESOURCES LTD.			
TITLE		REPORT ADDENDUM PEAK PARTICLE VELOCITY 13 mm/s ISOPLETH			
	PROJECT No.	03-1413-427	FILE No.	031413427-F02	
	DESIGN	CJC	08 MAR 04	SCALE	AS SHOWN
	CADD	SRR	09 MAR 04	REV.	0
	CHECK	CJC	10 MAR 04	FIGURE 2	
	REVIEW		10 MAR 04		




1500

PROJECT		CUMBERLAND RESOURCES LTD.		
TITLE		CHARGE WEIGHT vs DISTANCE FROM BLAST - PPV = 50mm/s		
		PROJECT No. 03-1413-427	FILE No. FIGURE 4	
DESIGN	CJC	28JAN04	SCALE NTS	REV. 0
CADD	SS	28JAN04		
CHECK	CJC	28JAN04		
REVIEW		10MAR04		



FIGURE 3

REVISION DATE: 04/03/09 11:33am By: sreddy CADD FILE: N:\Bur-Graphics\Projects\2003\1413\03-1413-427\4300\Drafting\cad\031413427-F04.dwg



LEGEND

- 12 kg Charge Weight, 20m Offset
- 86 kg Charge Weight, 53m Offset
- 250 kg Charge Weight, 89m Offset
- 420 kg Charge Weight, 116m Offset


Confinement, k = 800

NOTES

1) Area behind dikes is de-watered during operations.

REFERENCES

- 1) Drawing taken from AMEC, dated 28-01-04, Drawing # A1-131395-100-C-0001 Revision A - OVERALL SITE PLAN YEAR 1-5.
- 2) Golder Report on Blast Design, Feburary, 2004.




PROJECT

CUMBERLAND
RESOURCES LTD.



TITLE

REPORT ADDENDUM
PEAK PARTICLE VELOCITY
50 mm/s ISOPLETH

Golder
Associates

PROJECT No.	03-1413-427	FILE No.	031413427-F04
DESIGN	CJC 08 MAR 04	SCALE	AS SHOWN REV. 0
CADD	SRR 09 MAR 04		
CHECK	CJC 10 MAR 04		
REVIEW	10 MAR 04		

FIGURE 4




— k = 400 k = 800 - - - k = 1500
Site factor b = -1.6 for downhole blasting

PROJECT				
CUMBERLAND RESOURCES LTD.				
TITLE				
CHARGE WEIGHT vs SETBACK DISTANCE FOR 100 kPA OVERPRESSURE				
PROJECT No.		03-1413-427	FILE No.	
DESIGN	CJC	28JAN04	SCALE	NTS
CADD	SS	28JAN04	REV.	0
CHECK	CJC	28JAN04	FIGURE 5	
REVIEW		10MAR04		



REVISION DATE: 04/03/09 11:18am By: sreddy CADD FILE: N:\Bur-Graphics\Projects\2003\1413\03-1413-427\4300\Drafting\cad\031413427-F06.dwg



LEGEND

	12 kg Charge Weight, 15m Offset
	86 kg Charge Weight, 40m Offset
	250 kg Charge Weight, 69m Offset
	420 kg Charge Weight, 89m Offset

Confinement, $k = 800$


NOTES

1) Area behind dikes is de-watered during operations.

REFERENCES

1) Drawing taken from AMEC, dated 28-01-04, Drawing # A1-131395-100-C-0001
Revision A - OVERALL SITE PLAN YEAR 1-5.

2) Golder Report on Blast Design, February, 2004





PROJECT		CUMBERLAND RESOURCES LTD.			
TITLE		REPORT ADDENDUM INSTANTANEOUS OVERPRESSURE 100kPa ISOPLETH			
		PROJECT No.	03-1413-427	FILE No.	031413427-F06
		DESIGN	CJC 08 MAR 04	SCALE	AS SHOWN
		CADD	SRR 09 MAR 04	REV.	0
		CHECK	CJC 10 MAR 04	FIGURE 6	
		REVIEW	10 MAR 04		

APPENDIX I


FRAGMENTATION PREDICTIONS


3m Bench 100% Emulsion 76 mm Blasthole




PROJECT		CUMBERLAND RESOURCES LTD.			
TITLE		IRON FORMATION FRAGMENTATION PREDICTION 3m BENCH - 76mm BLASTHOLE			
		PROJECT No. 03-1413-427		FILE No. FIGURE 4	
		DESIGN	CJC	28JAN04	SCALE NTS
		CADD	SS	28JAN04	REV. 0
		CHECK	CJC	28JAN04	FIGURE I-1
		REVIEW		10MAR04	


3m Bench 100% Emulsion 76 mm Blasthole



PROJECT				
CUMBERLAND RESOURCES LTD.				
TITLE				
ULTRAMAFIC VOLCANIC FRAGMENTATION PREDICTION 3m BENCH - 76mm BLASTHOLE				
		PROJECT No. 03-1413-427		FILE No. FIGURE 4
		DESIGN	CJC 28JAN04	SCALE NTS
		CADD	SS 28JAN04	REV. 0
		CHECK	CJC 28JAN04	FIGURE I-2
		REVIEW	10MAR04	

3m Bench 100% Emulsion 76 mm Blasthole



PROJECT				
CUMBERLAND RESOURCES LTD.				
TITLE				
INTERMEDIATE VOLCANIC FRAGMENTATION PREDICTION 3m BENCH - 76mm BLASTHOLE				
	PROJECT No.		03-1413-427	FILE No. FIGURE 4
	DESIGN	CJC	28JAN04	SCALE NTS
	CADD	SS	28JAN04	REV. 0
	CHECK	CJC	28JAN04	FIGURE I-3
	REVIEW		10MAR04	

TECHNICAL MEMORANDUM



Golder Associates Ltd.

#500 - 4260 Still Creek Drive
Burnaby, B.C., Canada V5C 6C6

Telephone: 604-296-4200
Fax Access: 604-298-5253

TO: Cumberland Resources Ltd. **DATE:** October 6, 2005
FROM: Cameron Clayton **JOB NO:** 05-1413-036A
EMAIL: cclayton@golder.com
RE: **ITEM #85/85A – MEADOWBANK GOLD PROJECT – BLASTING
ADDENDUM**

A Technical Meeting was held in Baker Lake on June 2 and 3, 2005 to review the Draft Environmental Impact Statement (DEIS) for Cumberland Resources Limited (CRL), Meadowbank Gold Project. Following the technical meeting, a list of commitments by CRL was prepared, which would either be addressed as soon as possible or appear in the Final Environmental Impact Statement. This technical memorandum responds to Items #85 and #85a from this list which requested additional information relating to the annotation of a permafrost cross section through the project area.

Specifically, Items #85 and 85a requested to:

85. “Ensure that the blast management plan in the FEIS accounts for DFO addendum relating to blast design during periods when water bodies are ice covered:
- a. A Blast Design Report will be submitted, taking into account the DFO addendum relating to blast design during frozen conditions.”

1.0 INSTANTANEOUS PRESSURE CHANGE FOR CANADIAN FISHERIES GUIDELINES

Two blast design reports have been produced previously for the project:

- Golder Associates Ltd., Report on *Blast Design, Meadowbank Gold Project, Nunavut*, February 10, 2004.
- Addendum: Blasting Report Addendum, Golder Associates, May 25, 2004.



The reader is directed to review the two previous reports which describe in greater detail the development of assumptions on which the evaluations have been based, the procedures used to carry out the evaluations, and other parameters used in the evaluations that may be presented below but are not described.

The previous report, and the report addendum, included consideration of blast induced vibration from the perspective of the stability of the perimeter dikes and tailings dike, and from the perspective of the effect of blast induced vibration on fish and fish habitat. Estimates of blast induced vibration and instantaneous pressure change were presented for various charge weights based on initial evaluation of blast design. The feasibility study recently completed by Amec Americas Ltd recommended that a charge weight of 77 kg for a bench height of 6 m be used. The previously completed blast designs have been modified to reflect this recommendation, and are presented below.

The following sections are based on the previous work, and on new analyses to address additional concerns presented by Department of Fisheries and Oceans (DFO) and presented during the meetings in Baker Lake.

1.1 Blast Induced Vibration

Blast induced vibrations have the potential to reduce the stability and performance of nearby earthen structures such as dikes. Where saturated conditions exist within the foundation materials and within the earthen structural fills of the de-watering dikes and the tailings dike, blast induced vibrations could result in the development of increased pore water pressures within the foundation and structural fill materials. This could lead to potential settlement of the structures and consequently impact to the water retaining capacity of the dikes.

The effects of blasting are typically assessed in terms of Peak Particle Velocity (PPV).

1.1.1 Estimates of Peak Particle Velocity

The preliminary estimates of Peak Particle Velocity (PPV) are based on the current understanding of the site layout, mine plan, and blast design. Changes to the current site layout, mine plan, and blast design will result in changes to the estimates of PPV. Certain site specific factors that are required to calculate PPV have been estimated based on published values. However, site specific parameters can only be determined by site vibration monitoring of actual blasts. Consequently, the actual PPV values may differ from those presented here.

The US Bureau of Mines has established that the peak particle velocity, PPV, is related to the scaled distance by the following relationship:

$$PPV = k * (R/W^{0.5})^{-b}$$

Where:

- PPV = Peak Particle Velocity, mm/s
- R = Distance from blast to point of concern, m
- W = Charge weight per delay, kg
- k = confinement factor – specific to site
- b = site factor

The constants k and b are specific to the site, and can be determined by blast vibration monitoring.

For this evaluation, a value of b = 1.6 was assumed. The PPV was evaluated for a range of values of confinement, 'k', of 400, 800, and 1500, for down hole blasting. This range in values is considered to be reasonable for the site and to provide an estimate of the sensitivity of PPV to different values of confinement.

Based on the current understanding of site conditions and blast monitoring experience at two other northern sites, the confinement value of 800 is expected to be the most likely representative value for average conditions at the site. The actual value for confinement can only be determined through a detailed field monitoring program.

1.1.2 Minimum Setback Distance for Canadian Fisheries Guidelines

Design guidelines governing the use of explosives adjacent to Canadian fisheries waters (Guidelines for the Use of Explosives in or Near Canadian Fisheries Waters; Wright and Hopky, 1998) indicate that no explosive is to be detonated that produces a peak particle velocity greater than 13 mm/s in a spawning bed during the period of egg incubation.

The PPV's were evaluated for the Second Portage Lake East Dike, the Third Portage Peninsula east shoreline, the Bay Dike, and the Goose Island east shoreline.

1.1.3 Setback Distance for Peak Particle Velocity

The minimum setback distances to achieve a Peak Particle Velocity, PPV, of 13 mm/s have been estimated for various values of confinement, 'k', and for four potential charge weights per delay. The following table summarizes the estimates of minimum setback required to achieve a PPV value of 13 mm/s.

**Table 1: Minimum Setback Distance for 13 mm/s
Peak Particle Velocity Guideline**

k	12 kg charge weight per delay (3 m bench, 76 mm hole)	77 kg charge weight per delay (6 m bench, 165 mm hole)	250 kg charge weight per delay, (12 m bench, decked charge, 229 mm hole)
	Minimum Setback Distance to Achieve PPV = 13 mm/s		
400	30 m	75 m	135 m
800	46 m	115 m	208 m
1500	67 m	171 m	308 m

The relationships presented in the above table are shown on Figure 1 for a confinement value, k, of 800.

With the exception of a short segment of shoreline adjacent to the Portage Pit wall at the south end of the pit, the proposed charge weight of 77 kg per hole on 6 m benches will result in PPV less than the required 13 mm/s.

For the portions of the dike or shoreline where the 13 mm/s guideline is exceeded, modified blast designs consisting of lower charge weights on lower bench heights have been shown to result in PPV that meet the guideline requirement. For example, the figure indicates that a charge weight of 12 kg would result in acceptable PPV in the area of concern. Alternatively, additional fill materials could be placed along the shoreline or dike upstream (lake side) face to increase the distance from the blasting area.

1.1.4 Minimum Setback Distance for Threshold Damage Levels

General guidelines for blasting nears dams indicate vibration damage thresholds on the order of 50 mm/s to be reasonable for dams having medium to dense sand or silts within the dam or foundation materials. The following table summarizes the estimates of minimum setback required to achieve a PPV value of 50 mm/s for the charge weights considered.

Table 2: Comparison of Minimum Setback Distance for a Peak Particle Velocity of 50 mm/s for Various Blast Configurations

k	12 kg charge weight per delay (3 m bench, 76 mm hole)	77 kg charge weight per delay (6 m bench, 165 mm hole)	250 kg charge weight per delay, (12 m bench, decked charge, 229 mm hole)
	Minimum Setback Distance to Achieve PPV = 50 mm/s		
400	13 m	32 m	58 m
800	20 m	50 m	89 m
1500	29 m	74 m	133 m

The analysis indicates that for the proposed 80-m toe setback for the dikes at the Meadowbank Project, and the proposed 77 kg charge weight, PPV of 50 mm/s will not be exceeded in the toe areas of the perimeter dikes or tailings dike (see Figure 2).

1.1.5 Instantaneous Pressure Change for Canadian Fisheries Guidelines – 100 kPa Criteria

The required setback distance for confined explosives to achieve the 100 kPa instantaneous pressure change guideline can be estimated from relationships presented in “Guidelines for the Use of Explosives in or Near Canadian Fisheries Waters” (Wright and Hopky, 1998).

The following properties were used to assess the minimum setback distance.

Table 3: Properties Used to Assess Setback Distance for Instantaneous Pressure Change

Medium	Density, g/cm ³	Compressional Wave Velocity, cm/s
Water	1	146,300 ¹
Rock (Intermediate Volcanic)	2.8	457,200 ¹

1. Guidelines for the Use of Explosives in or Near Canadian Fisheries Waters; Wright and Hopky, 1998

Based on the above properties, the range of potential charge weights, and the range in confinement value, k, the following minimum setback distances, below which the 100 kPa overpressure guideline will not be exceeded, are estimated.

Table 4: Minimum Setback Distance for Instantaneous Pressure Change Guideline (<100kPa)

Charge Weight per Delay (kg)	Minimum Setback Distance (m)		
	k=400	k=800	k=1500
12	10 m	15 m	22 m
77	25 m	38 m	57 m
250	45 m	69 m	102 m

The results in the above table are presented on Figure 3 for a confinement of 800. For the proposed charge weight of 77 kg the instantaneous pressure change will not exceed the guideline of 100 kPa on the outside of the dikes.

1.1.6 Instantaneous Pressure Change for Ice Covered Waters – 50 kPa Criteria

In addition to the legislated criteria Department of Fisheries and Oceans has requested that Cumberland assess the effect of blast induced vibration and instantaneous overpressure resulting from blasting adjacent to waters during ice cover periods, although this is not currently legislated. For these conditions, Department of Fisheries has recommended an additional evaluation to consider an instantaneous pressure change of 50 kPa.

For the range of potential charge weights, and for a range in confinement value, k, the following minimum setback distances, below which the 50 kPa overpressure guideline will not be exceeded, are estimated.

Table 5: Minimum Setback Distance for Instantaneous Pressure Change Guideline (50 kPa Ice Covered Water)

Charge Weight per Delay (kg)	Bench Height (m)	Hole Diameter (mm)	Minimum Setback Distance (m)		
			k=400	k=800	k=1500
12	3 m (ore)	76	15	23	34
77	6 m (ore and waste)	165	38	59	87
250	6 m (waste)	165	69	106	157

The relationships presented in the above table are shown on Figure 4 for a confinement value, k , of 800. Based on the analysis, an instantaneous pressure change of 50 kPa will not be exceeded for the proposed 77 kg charge weight per hole, and for a confinement value, ' k ', of 800.

1.2 Conclusions

The following summarizes the conclusions of the previous and current assessment:

- With the exception of a short segment of shoreline adjacent to the southeast wall of the Portage Pit, the Peak Particle Velocity of 13 mm/s will not be exceeded for the proposed 77 kg charge weight per hole. This relates to fisheries guidelines.
- The Peak Particle Velocity of 50 mm/s will not be exceeded in the toe region of the perimeter dikes or tailings dike for the proposed 77 kg charge weight per hole. This relates to the structural stability of the dikes.
- The instantaneous pressure change along the upstream (lake side) face of the East Dike, Bay Zone Dike, and Goose Dike is predicted to be less than the 100 kPa guideline for the proposed 77 kg charge weight per hole. This relates to fisheries guidelines.
- The instantaneous pressure change along the upstream (lake side) face of the dikes during periods of ice cover is predicted to be less than 50 kPa for the proposed 77 kg charge weight per hole. This relates to an additional request by DFO to assess instantaneous pressure change for ice covered water conditions.
- For the Vault deposit, Peak Particle Velocity and instantaneous pressure change guidelines along the Vault Dike face will not be exceeded for any of the proposed blast designs or charge weights. The Vault Dike lies about 750 m from the nearest crest of the Vault Pit.

The analyses have shown that peak particle velocities and instantaneous overpressure can be effectively managed through the use of lighter charge weights, decreased blasthole diameters, and decreased operating bench heights, or a combination of these mitigative measures. During mine development and operations, a vibration monitoring program will be required in order to measure the response of the de-watering dikes and tailings dike to pit blasting, and to measure peak particle velocities on the upstream (lake side) of the dikes to assess the current blast designs. This will allow modifications to be made to the operational blast designs.

1.2.1 Monitoring

As part of the mine development, a vibration monitoring program will be required in order to measure the response of the de-watering dikes and tailings dike to pit blasting. The data from this program would be assessed in conjunction with continuous

measurements from piezometers that would be installed in the dikes, and within the dike foundation materials. From this analysis, the blasting could be adjusted to minimize the impact on the dikes. Mitigative measures to the blast design to minimize the development of blast induced vibration could include modifications to the blasthole patterns, reduction in blasthole size and hence charge weight in critical areas of the pit walls within a certain distance from the proposed de-watering and tailings dike, single blasthole initiation per delay, reduction in operating bench height in critical areas, or a combination of all these measures.


A more comprehensive program of blast vibration modelling and test blasting may be required during operations if blast vibration levels remain high and their frequency (cycles per second) is low.

CJC/vee

05-1413-036A

N:\FINAL\2005\1413\05-1413-036A\TM1006_05 ITEMS 85 & 85A - BLAST DESIGN 50KPA.DOC

REVISION DATE: 05/10/06 8:38am By: WLI CADD FILE: N:\Bur-Graphics\Projects\2005\1413\05-1413-036A\BLAST DESIGN\051413036A-SK13.dwg



LEGEND

	12 kg Charge Weight, 46m Offset
	77 kg Charge Weight, 115m Offset
	250 kg Charge Weight, 208m Offset
	Recommended Charge Weight
Confinement, k = 800	

NOTES


1. Contour Interval 2 Metre.
2. All Dimensions in Metres.
3. Elevations in Metres above Sea Level.
4. UTM Zone 14, NAD83.
5. Area behind Dikes is De-watered during Operations.
6. Reference: Feasibility Study Report, AMEC, June 2005.

REFERENCES

- 1) AMEC Americas LTD, Drawing # A1-131395-100-C-0001 (100-C-0001.dwg), Meadowbank Feasibility Study, April 2005.
- 2) Golder Associates: Report on Blast Design, Meadowbank Golder Project, February 2004.
- 3) Golder Associates: Blasting Report Addendum, May 2004.

PROJECT			
CUMBERLAND RESOURCES LTD.			
TITLE			
PEAK PARTICLE VELOCITY 13 mm/s ISOPLETH			
	PROJECT No. 05-1413-036A		FILE No. 051413036A-SK13
	DESIGN	CJC 03OCT05	SCALE AS SHOWN REV. A
	CADD	WLI 03OCT05	FIGURE 1
	CHECK	CJC 03OCT05	
REVIEW			

REVISION DATE: 05/10/06 8:42am By: WLI CADD FILE: N:\Bur-Graphics\Projects\2005\1413\05-1413-036A\BLAST DESIGN\051413036A-SK14.dwg



LEGEND

- 12 kg Charge Weight, 20m Offset
- 77 kg Charge Weight, 50m Offset
- 250 kg Charge Weight, 89m Offset
- Confinement, k = 800
- Recommended Charge Weight

NOTES

1. Contour Interval 2 Metre.
2. All Dimensions in Metres.
3. Elevations in Metres above Sea Level.
4. UTM Zone 14, NAD83.
5. Area behind Dikes is De-watered during Operations.
6. Reference: Feasibility Study Report, AMEC, June 2005.

REFERENCES

- 1) AMEC Americas LTD, Drawing # A1-131395-100-C-0001 (100-C-0001.dwg), Meadowbank Feasibility Study, April 2005.
- 2) Golder Associates: Report on Blast Design, Meadowbank Golder Project, February 2004.
- 3) Golder Associates: Blasting Report Addendum, May 2004.

PROJECT



CUMBERLAND
RESOURCES LTD.

TITLE

PEAK PARTICLE VELOCITY
50 mm/s ISOPLETH

	PROJECT No.	05-1413-036A	FILE No.	051413036A-SK14
	DESIGN	CJC	03OCT05	SCALE AS SHOWN
	CADD	WLI	03OCT05	REV. A
	CHECK	CJC	03OCT05	FIGURE 2
	REVIEW			

REVISION DATE: 05/10/06 8:41 am By: WLI CADD FILE: N:\Bur-Graphics\Projects\2005\1413\05-1413-036A\BLAST DESIGN\051413036A-SK15.dwg



LEGEND

- 12 kg Charge Weight, 15m Offset
- 77 kg Charge Weight, 38m Offset
- 250 kg Charge Weight, 69m Offset


Confinement, k = 800 Recommended Charge Weight

NOTES

1. Contour Interval 2 Metre.
2. All Dimensions in Metres.
3. Elevations in Metres above Sea Level.
4. UTM Zone 14, NAD83.
5. Area behind Dikes is De-watered during Operations.
6. Reference: Feasibility Study Report, AMEC, June 2005.

REFERENCES

- 1) AMEC Americas LTD, Drawing # A1-131395-100-C-0001 (100-C-0001.dwg), Meadowbank Feasibility Study, April 2005.
- 2) Golder Associates: Report on Blast Design, Meadowbank Golder Project, February 2004.
- 3) Golder Associates: Blasting Report Addendum, May 2004.



PROJECT

CUMBERLAND
RESOURCES LTD.

TITLE


INSTANTANEOUS OVERPRESSURE
100kPa ISOPLETH

DESIGN	CJC	03OCT05
CADD	WLI	03OCT05
CHECK	CJC	03OCT05
REVIEW		

PROJECT No. 05-1413-036A	FILE No. 051413036A-SK15
SCALE AS SHOWN	REV. A

FIGURE 3

REVISION DATE: 05/10/06 8:38am By: WLI CADD FILE: N:\Bur-Graphics\Projects\2005\1413\05-1413-036A\BLAST DESIGN\051413036A-SK02-1.dwg



LEGEND

- 12 kg Charge Weight, 23m Offset
- 77 kg Charge Weight, 59m Offset
- 250 kg Charge Weight, 106m Offset

Confinement, k = 800


Recommended Charge Weight


NOTES

1. Contour Interval 2 Metre.
2. All Dimensions in Metres.
3. Elevations in Metres above Sea Level.
4. UTM Zone 14, NAD83.
5. Area behind Dikes is De-watered during Operations.
6. Reference: Feasibility Study Report, AMEC, June 2005.

REFERENCES

- 1) AMEC Americas LTD, Drawing # A1-131395-100-C-0001 (100-C-0001.dwg), Meadowbank Feasibility Study, April 2005.
- 2) Golder Associates: Report on Blast Design, Meadowbank Golder Project, February 2004.
- 3) Golder Associates: Blasting Report Addendum, May 2004.



PROJECT		CUMBERLAND RESOURCES LTD.			
TITLE		INSTANTANEOUS OVERPRESSURE 50 kPa ISOPLETH UNDER ICE CONDITION			
		PROJECT No. 05-1413-036A		FILE No. 051413036A-SK2-1	
		DESIGN	CJC	03OCT05	SCALE AS SHOWN
		CADD	WLI	03OCT05	REV. 0
		CHECK	CJC	03OCT05	FIGURE 4
		REVIEW			

APPENDIX D

Perimeter Dike Slope Stability Analyses

Table D.1: Summary of Limit Equilibrium Slope Stability Analyses – Meadowbank Dikes

Figure No. (I-)	Section Analyzed	Conditions Modelled	Calculated Minimum FOS	Calculated Yield Acceleration (g)	Maximum Required Undrained Shear Strength of Overburden Till (kPa)	
					FOS=1.0	FOS=1.3
		<i>End of Construction</i>				
A1	A	Failure through Cutoff Wall; Circular Surfaces			13	19
A2		Failure through Cutoff Wall; Block Surfaces			13	18
A3		Failure through Rockfill; Circular Surfaces			20	28
A4		Failure through Rockfill; Block Surfaces			18	24
B1	B	Failure through Cutoff Wall; Circular Surfaces			n/a	n/a
B2		Failure through Cutoff Wall; Block Surfaces			16	23
B3		Failure through Rockfill; Circular Surfaces			n/a	5
B4		Failure through Rockfill; Block Surfaces			20	30
C1	C	Failure through Cutoff Wall; Circular Surfaces			7	9
C2		Failure through Cutoff Wall; Block Surfaces			9	13
C3		Failure through Rockfill; Circular Surfaces			11	16
C4		Failure through Rockfill; Block Surfaces			10	14
		<i>Long-Term Effective Strength</i>				
A5	A	Failure through Cutoff Wall; Circular Surfaces – Static	4.1			
A6		Failure through Cutoff Wall; Block Surfaces - Static	4.3			
A7		Failure through Rockfill; Circular Surfaces – Static	2.7			
A8		Failure through Rockfill; Block Surfaces - Static	2.8			
A9		Failure through Cutoff Wall; Circular Surfaces – Pseudostatic	3.5			
A10		Failure through Cutoff Wall; Block Surfaces - Pseudostatic	3.7			
A11		Failure through Rockfill; Circular Surfaces – Pseudostatic	2.5			
A12		Failure through Rockfill; Block Surfaces - Pseudostatic	2.6			
A13		Failure through Cutoff Wall; Circular Surfaces – Yield Acceleration		0.41		

Figure No. (I-)	Section Analyzed	Conditions Modelled	Calculated Minimum FOS	Calculated Yield Acceleration (g)	Maximum Required Undrained Shear Strength of Overburden Till (kPa)	
					FOS=1.0	FOS=1.3
A14		Failure through Cutoff Wall; Block Surfaces - Yield Acceleration		0.41		
A15		Failure through Rockfill; Circular Surfaces – Yield Acceleration		0.36		
A16		Failure through Rockfill; Block Surfaces - Yield Acceleration		0.38		
B5	B	Failure through Cutoff Wall; Circular Surfaces – Static	3.5			
B6		Failure through Cutoff Wall; Block Surfaces - Static	5.9			
B7		Failure through Rockfill; Circular Surfaces – Static	1.9			
B8		Failure through Rockfill; Block Surfaces - Static	3.1			
B9		Failure through Cutoff Wall; Circular Surfaces – Pseudostatic	3.0			
B10		Failure through Cutoff Wall; Block Surfaces - Pseudostatic	4.9			
B11		Failure through Rockfill; Circular Surfaces – Pseudostatic	1.7			
B12		Failure through Rockfill; Block Surfaces - Pseudostatic	2.8			
B13		Failure through Cutoff Wall; Circular Surfaces – Yield Acceleration		0.27		
B14		Failure through Cutoff Wall; Block Surfaces - Yield Acceleration		0.40		
B15		Failure through Rockfill; Circular Surfaces – Yield Acceleration		0.16		
B16		Failure through Rockfill; Block Surfaces - Yield Acceleration		0.34		
C5	C	Failure through Cutoff Wall; Circular Surfaces – Static	5.0			
C6		Failure through Cutoff Wall; Block Surfaces - Static	3.9			
C7		Failure through Rockfill; Circular Surfaces – Static	3.4			
C8		Failure through Rockfill; Block Surfaces - Static	3.2			
C9		Failure through Cutoff Wall; Circular Surfaces – Pseudostatic	3.7			

Figure No. (I-)	Section Analyzed	Conditions Modelled	Calculated Minimum FOS	Calculated Yield Acceleration (g)	Maximum Required Undrained Shear Strength of Overburden Till (kPa)	
					FOS=1.0	FOS=1.3
C10		Failure through Cutoff Wall; Block Surfaces - Pseudostatic	3.3			
C11		Failure through Rockfill; Circular Surfaces – Pseudostatic	2.4			
C12		Failure through Rockfill; Block Surfaces - Pseudostatic	2.8			
C13		Failure through Cutoff Wall; Circular Surfaces – Yield Acceleration		0.48		
C14		Failure through Cutoff Wall; Block Surfaces - Yield Acceleration		0.37		
C15		Failure through Rockfill; Circular Surfaces – Yield Acceleration		0.42		
C16		Failure through Rockfill; Block Surfaces - Yield Acceleration		0.36		