

[illegible][illegible][illegible]

1. ለፍርድ ቤቱ ማሳሰቢያ ላይ የተጠቀሱት ጽሑፎች

[illegible][illegible]

[illegible]

- [illegible]

[illegible][illegible]

[illegible][illegible][illegible]

[illegible][illegible][illegible][illegible]

[illegible][illegible]

ስለሆነም ለጥራት ማረጋገጫ ማስፈጸም የሚችል የፍጥነት ምርመራ ማድረግ አስፈላጊ ሲሆን፣
 ለጥራት ማረጋገጫ ማስፈጸም የሚችል የፍጥነት ምርመራ ማድረግ አስፈላጊ ሲሆን፣
 ለጥራት ማረጋገጫ ማስፈጸም የሚችል የፍጥነት ምርመራ ማድረግ አስፈላጊ ሲሆን፣

- [illegible]

- [illegible]

- [illegible]

[illegible][illegible]

- [illegible]

[illegible][illegible]

ᐃᐱᑦ ᐅᑦᐱᑦᐱᑦ ᐱᐱᑦ ᐱᑦ ᐱᑦ ᐱᑦ 1: ᐱᑦ ᐱᑦ ᐱᑦ ᐱᑦ ᐱᑦ

[illegible]

ΔῖΛῖΝ Ὡς ἔσῃ ἡ ἁγία

ወይም ሕዝብ ጥራት ርኅርሕ ለማድረግ ለሚችሉ ሰነዶች ላይ ማሳሰቢያ ማድረግ፡

[illegible]

P.O. Box 1360 Cambridge Bay, NU X0B 0C0 Phone: (867) 983-4600 Fax: (867) 983-2594
Page 14 of 27

[illegible]

ፈኛከቦቤ ጋፍ -ፈኛ ኖቦ ካህንደጌ ጋር ልቤ ጋኙርዎረኒ፣ ልፍ ሙሴ ይዋጋኛልና ገደርደረ።

[illegible][illegible]

P.O. Box 1360 Cambridge Bay, NU X0B 0C0 Phone: (867) 983-4600 Fax: (867) 983-2594

3. ክልሉ የጋራ ነፍሰ-ሰውና የፍትሕ ጥያቄዎችን ለማሟላት የሚያስፈልጉትን ሥልጣን ለሀገራዊ አስተዳደር ይሰጣል፡፡

- [illegible]

[illegible]

- [illegible]

[illegible][illegible]

1. መብት ለሕግ ተቀባይነት ለማግኘት ለሚችሉ ሰነዶች ላይ ማረጋገጥ አለባቸው፡፡ ለዚህም ምሳሌ ለሕግ ተቀባይነት ለማግኘት ለሚችሉ ሰነዶች ላይ ማረጋገጥ አለባቸው፡፡ ለዚህም ምሳሌ ለሕግ ተቀባይነት ለማግኘት ለሚችሉ ሰነዶች ላይ ማረጋገጥ አለባቸው፡፡
2. ለሕግ ተቀባይነት ለማግኘት ለሚችሉ ሰነዶች ላይ ማረጋገጥ አለባቸው፡፡ ለዚህም ምሳሌ ለሕግ ተቀባይነት ለማግኘት ለሚችሉ ሰነዶች ላይ ማረጋገጥ አለባቸው፡፡ ለዚህም ምሳሌ ለሕግ ተቀባይነት ለማግኘት ለሚችሉ ሰነዶች ላይ ማረጋገጥ አለባቸው፡፡
3. ለሕግ ተቀባይነት ለማግኘት ለሚችሉ ሰነዶች ላይ ማረጋገጥ አለባቸው፡፡ ለዚህም ምሳሌ ለሕግ ተቀባይነት ለማግኘት ለሚችሉ ሰነዶች ላይ ማረጋገጥ አለባቸው፡፡ ለዚህም ምሳሌ ለሕግ ተቀባይነት ለማግኘት ለሚችሉ ሰነዶች ላይ ማረጋገጥ አለባቸው፡፡
4. ለሕግ ተቀባይነት ለማግኘት ለሚችሉ ሰነዶች ላይ ማረጋገጥ አለባቸው፡፡ ለዚህም ምሳሌ ለሕግ ተቀባይነት ለማግኘት ለሚችሉ ሰነዶች ላይ ማረጋገጥ አለባቸው፡፡ ለዚህም ምሳሌ ለሕግ ተቀባይነት ለማግኘት ለሚችሉ ሰነዶች ላይ ማረጋገጥ አለባቸው፡፡ ለዚህም ምሳሌ ለሕግ ተቀባይነት ለማግኘት ለሚችሉ ሰነዶች ላይ ማረጋገጥ አለባቸው፡፡

APPENDIX A: PREVIOUSLY-SCREENED PROJECT PROPOSALS

The original project proposal (NIRB File No. 11EN010), was received by the NIRB from Agnico-Eagle Mines Ltd. (now Agnico Eagle Mines Ltd.; Agnico Eagle) for a Class A Land Use Permit (LUP) with Indian and Northern Affairs Canada (INAC; now Indigenous and Northern Affairs Canada) for the “Pipe Dream Winter Road and Mining Exploration” project proposal. On March 10, 2011 the NIRB received a positive conformity determination (Keewatin Regional Land Use Plan) from the Nunavut Planning Commission (NPC) for this file. Finally, on March 15, 2011 INAC referred Agnico Eagle’s “Pipe Dream Winter Road and Mining Exploration” project proposal to the NIRB for screening. The project proposal was screened by the Board in accordance with Part 4, Article 12 of the *Agreement between the Inuit of the Nunavut Settlement Area and Her Majesty the Queen in Right of Canada* (Nunavut Agreement). On April 21, 2011 the NIRB issued a Nunavut Agreement 12.4.4(a) screening decision to the Minister of Indian and Northern Affairs which indicated that the proposed project could proceed subject to the NIRB’s recommended project-specific terms and conditions.

Agnico Eagle’s original “Pipe Dream Winter Road and Mining Exploration” project was located within the Kivalliq region, on two (2) properties: the Meadowbank Exploration Project area, approximately 90 kilometers (km) north of the Hamlet of Baker Lake and the Greyhills Exploration Project area, approximately 43 km northeast of the Hamlet of Baker Lake. The Proponent indicated that it intended to continue conducting exploration activities, and construct and operate a winter road network near the Meadowbank project area.

These proposed activities were located near the Meadowbank Exploration Camp, which was included within the scope of the NIRB’s Review of the Meadowbank Gold Mine project (File No. 03MN107) that had been permitted to proceed pursuant to the NIRB’s Project Certificate No. 004 issued December 30, 2006. Following an evaluation of the project scope, the NIRB determined that the “Pipe Dream Winter Road and Mining Exploration” project activities were not included within the scope of the Board’s previous Review of the Meadowbank Gold Mine Project and as such, these activities were treated as a new project subject to screening in accordance with Article 12 of the Nunavut Agreement.

According to the previously screened project proposal, the scope of the project included the following undertakings, works or activities:

- Construction and operation of winter road network, approximately 26.5 km in length:
 - Originating at the Meadowbank Exploration Camp at km 100 of the Meadowbank All Weather Private Access Road,
 - Maximize passage over frozen lakes,
 - Preparation include removal of snow from lake ice without flooding;
- Approximately 13,000 metres (m) total on land and on ice diamond (exploration) drilling on Inuit Owned Land and Crown land at the Meadowbank and Greyhills Exploration Projects:
 - Approximately 78 drilling sites located within 19 different areas (areas to be connected via proposed winter road);
- Geological mapping, prospecting, some trenching, geophysical surveying;
- Access via winter road, supported by helicopter;
- Project personnel based out of the Meadowbank Exploration Camp (NIRB File No. 03MN107); and,
- Transportation of fuel and chemical materials on an as-needed basis to support drilling activities.

Additional authorization and extension requests associated with the “Amaruq Exploration” project previously known as “Pipe Dream Winter Road and Mining Exploration” project have also been reviewed by the NIRB following screening of the original project proposal (File No. 11EN010). In each instance where the NIRB received applications up to and including June 2014, the NIRB confirmed that the application was exempt from the requirement for further screening pursuant to Section 12.4.3 of the Nunavut Agreement and that the activities therein remained subject to the terms and conditions recommended in the original April 21, 2011 Screening Decision Report. On February 10, 2015, after receiving an application for additional activities at site, the NIRB issued additional terms and conditions associated with the “Amaruq Winter Access” project. On November 4, 2015 after receiving an application for additional activities at site, the NIRB issued additional terms and conditions associated with the “Amaruq Exploration Access Road” project. The following is a summary of the previously screened project activities:

The scope of the activities and components associated with the previous August 10, 2011 Nunavut Water Board (NWB) Type “B” Water Licence (No. 2BE-MEA0813) amendment application included:

- Conducting drilling activities within the 30 m high water mark of proximal water bodies; and
- Disposal of all drill waste a minimum of 30 m from the ordinary water mark of proximal water bodies.

The Proponent’s March 22, 2012 application to amend its AANDC (Aboriginal Affairs and Northern Development Canada; now renamed INAC) Land Use Permit (No. N2011C0010) included a request to conduct exploration activities on additional Crown land from April 2012 to August 2014 and included the following components:

- Approximately 30 drill sites per year for a total of 60 sites;
- Drilling to be conducted on land and on ice, with sites located approximately 15 km northwest and up to 20 km northeast of the previously permitted exploration sites (NIRB File No. 11EN010).

The Proponent’s May 29, 2012 application for a new KIA Land Use Licence (No. KVL312C03) proposed additional exploration activities associated with its “IVR property” to take place on Inuit Owned Lands, approximately 50 kilometres northwest of the Meadowbank Mine site. The activities and components were determined to be related to the NIRB’s 11EN010 screening, and included:

- Prospecting, geophysical work, and soil sampling;
- Trenching to enhance surface rock exposure for geological mapping and channel sampling (4 to 8 trenches);
- On-land and on-ice drilling of approximately 30 or more holes per year (dependent upon results obtained);
- Short term storage of fuel and chemicals at drill sites, including diesel, gasoline and propane;
- Transportation of personnel, fuel and equipment to exploration sites via helicopter;
- Use of water for drilling activities as permitted under the amended Type “B” Water Licence; and,
- Backhaul of any waste produced to the Meadowbank mine site for disposal (NIRB File No. 03MN107); and
- Use of Meadowbank Exploration Camp (NIRB File No. 03MN107).

The activities and components associated with the previous January 21, 2013 Type “B” Water licence (*associated* NIRB File No. EX160; NWB File No. 2BE-MEA0813) amendment included a request to add two (2) exploration areas to the licence: “IVR Exploration” and “south Meadowbank area”.

The Proponent requested a two (2) year extension to its AANDC Land Use Permit (No. N2011C0010) in the May 23, 2013 extension application, to continue land use operations.

The Proponent’s March 27, 2014 application for an amendment to its project and a new AANDC Land Use Permit (No. N2013F0030) included the following additional undertakings, works, or activities:

- Development and operation of a winter access road, approximately 53 km in length from the Meadowbank mine site to the IVR Exploration site;
 - Winter road mostly located on lakes with 9 km located on land;
 - No use of water for preparation of winter road;
- Use of winter access road to transport material, equipment and fuel for exploration activities;
- Archaeological investigation to be conducted in the summer of 2014.

In addition, Agnico Eagle’s June 27, 2014 Type “B” Water Licence (*associated* NIRB File No. EX211; NWB File No. 2BE-MEA1318) amendment application included the establishment of a 50 person temporary exploration camp consisting of 12 tents.

The Proponent’s November 18, 2014 applications for an amendment to its project and a Land Use Licence (No. KVCL314C01) included the following additional undertakings, works, or activities:

- Amendments under Agnico Eagle’s Land Use Permit (No. N2013F0030) with AANDC included:

- Development and operation of an alternative winter access road, approximately 79 kilometres in length and 5 metres (m) wide, from the Meadowbank mine site to the Amaruq (IVR) exploration area to transport materials, equipment and fuel for exploration activities;
 - Winter road mostly located on lakes with 7 km located on land with a total area of 3.5 hectares;
 - Winter access road to be used from February to May with approximately 4 trips per day;
 - No use of water for preparation of winter road;
 - Archaeological investigation of the proposed winter access route to be completed in the summer of 2015.
- Amendments under Agnico Eagle's NWB Water Licence (No. 2BE-MEA1318) included:
 - Potential installation of an airstrip approximately 15 m wide and 500 m long at the south side of the proposed exploration camp using gravel from an esker near proposed location;
 - Potential transportation of materials, drills and personnel between the Meadowbank and Amaruq sites via airplane;
 - Installation of accommodations trailers for up to 60 personnel;
 - Storage of fuel (diesel, gasoline, aviation fuel, and propane) and hazardous materials and chemicals (oil, glycol, and grease) in double-walled tanks and/or drums stored in lined berms;
 - Installation of a "Bionest" water treatment system to treat sewage and grey water before discharge into the environment;
 - Accumulated sludge (solid materials) to be disposed of in a pit near the site biennially (every two (2) years) and treated with lime and covered with a minimum of 30 centimetres (cm) of compacted soil;
 - Potential alternative disposal of grey water in a sump to be released to the environment following treatment;
 - Incineration of combustible solid waste;
 - Non-combustible solid waste including scrap metal, hazardous waste, contaminated soil and snow to be transported to an approved facility;
 - Empty barrels to be reused or transported to a recycling facility via barge;
 - Total water consumption of 299 cubic metres (m³/day) for all project related activities (including camp and drill activities).
 - Additional water consumption of 30 cubic m³/day to be used for drilling activities for a total 280 m³/day; and
 - Additional water consumption for domestic use of 10 m³/day to be used for a total of 19 m³/day.
 - The new Commercial Lease with the KIA (No. KVCL314C01) included the following additional undertakings, works, or activities:
 - Camp construction, including installation of accommodations trailers, construction of a garage and gravel pad, and installation of a Bionest waste water treatment system;
 - Camp to be re-opened February 2015;
 - Use and construction of two (2) gravel pits;
 - Construction of gravel roads to support exploration, approximately 5 m wide and 0.40 m thick, within the KIA commercial lease area;
 - Drilling activities to commence March 2015, with up to 6 drills anticipated to be in operation for the 2015 season;
 - Storage capacity of 400,000 Litres (L) with tanks to be refilled during the winter season;
 - Installation of 9 - 55,000 Litre (L) and 2 - 100,000 L double-walled tanks;
 - Continuation of archaeological investigations in the Amaruq region;
 - Additional water use for drilling activities as permitted under the amended NWB Type "B" water licence.

The Proponent's July 16, 2015 applications for amendments and new permits to its project included new AANDC LUP (No N2015F0026), new KIA Land Use Licence (Nos. KVRW1501 & KVCA15Q02) and new NWB Type "B" water licence (NWB File No.: 8BC-AEA1525) and included the following additional undertakings, works, or activities:

- Development of a private single lane, all-season exploration access road linking the Meadowbank mine site to the Amaruq exploration project site to facilitate year round exploration operations including transport of fuel, equipment and personnel to site and include the items listed below. The road will traverse approximately 40 km on Crown Land with the remaining 22.5 km on Inuit Owned Land (IOL).
 - All-season access road to be 62.5 kilometres (km) long and 6.5 metres wide;
 - Installation of three (3) bridges;
 - Installation of eight (8) large open bottomed arch culverts;
 - Installation of twenty-eight (28) corrugated round culverts;
 - Development of six (6) spur roads to access six (6) of the seven (7) eskers to be used for borrow pits;
 - Development of pullouts approximately every 400 ± 50 m to accommodate two (2) road traffic;
- Use of non-potentially acid generating (NPAG) waste rock from the Vault Pit as quarry material to construct first 17 km of road;
- Use of seven (7) eskers for borrow material to build remainder of road;
- Transportation of materials, equipment and fuel for construction activities;
- Storage and use of fuel in double-walled tanks along the road to distribute fuel to equipment;
- Construction crew to be accommodated at existing and approved Agnico Eagle facilities;
- Additional archaeological studies to be conducted prior to construction of road; and
- Winter road not expected to continue to be used once the single lane access road has been developed.

The Proponent's May 12, 2016 project proposal included the following additional undertakings, works, or activities:

- Construction of the new infrastructure in late 2016 with underground work on the ramp to continue through 2017, and operations then planned to occur year round from 2018 to 2020;
- Develop a portal and access ramp 5.2 m wide x 5.2 m high, up to 5,200 m in length and 340 m in depth;
- Develop a rock quarry with surface area up to 27,307 square metres (m²) for extraction of 150,000 to 350,000 tonnes of rock material for construction purposes;
 - Use of quarry material for construction of a services pad (1.5 to 2.0 m depth and surface area up to 31,716 m²) and an operations pad (1.5 to 2.0 m depth and surface area up to 42,506 m²) located near the portal;
- Develop a waste rock storage pad to store up to 319,800 m³ (612,400 tonnes) waste rock adjacent to the portal;
 - Use of waste rock material for construction of the underground development and/or elsewhere on the exploration site;
- Develop a storm water storage pond (AP-5);
- Develop a ramp laydown area with offices, a warehouse, and a garage constructed next to the portal;
- Advanced mineral exploration including underground drilling and ongoing surface drilling;
- Collect 9,000 to 15,000 tonnes bulk ore sample(s) from underground to explore deep sections of the gold ore body at Amaruq;
- Storage and use of explosives with two (2) cap and four (4) explosive magazines to be established;
- Use of fuel for equipment;
- Use of water for development of ramp;
- Use of calcium chloride for underground dust control and drilling with brine collected in small sumps for the brine re-circulation system for reuse;
- Amaruq modular camp facilities adapted to accommodate up to 200 personnel from 140 with the addition of two (2) new wings to the camp;
- Increase in sewage and grey water treatment capacity by adding one (1) Bionest with capacity to treat 13,500 litres/day and a second Bionest with a capacity to treat 6,000 litres/day) at the Amaruq camp;
- Increase on site fuel storage by addition of four (4) – 50,000 litre double-walled bulk fuel storage tanks at the Amaruq property; and
- Use of existing infrastructure including airstrip at the Amaruq property.

The Proponent's December 22, 2016 project proposal included the following additional undertakings, works, or activities:

- Development of six (6) additional hard rock quarry/borrow pit sites;
 - Each site selected for non-potentially acid generating (NPAG)/metal-leaching characteristics;

- Additional large aggregate material would provide a base to ensure reduced thaw susceptibility and washout in sections of the road;
 - Sites located immediately adjacent to the approved exploration access road;
 - Extraction of up to 1,400,630 cubic metres (m³) for construction purposes;
- Use of additional heavy equipment;
- Use of fuel for equipment;
- Use of explosives for blasting of quarry sites;
- Generation of non-combustible wastes;
- Increase in workforce (up to ten (10) contract workers); and
- Continued use of existing camps.