

March 4, 2025

Mr. Goump Djalogue
Senior Planner, Nunavut Planning Commission
P.O. Box 2101
Iqaluit, Nunavut X0B 0C0

Dear Mr. Djalogue:

RE: *Qikiqtarjuaq Marine Infrastructure Project, NU, Application for Land Use Conformity Review*

Introduction

The Government of Nunavut is proposing to construct a deep-sea port facility in Qikiqtarjuaq, Nunavut (the Project). CBCL Limited (CBCL) was retained by the Government of Nunavut to provide architectural and engineering services for the Project.

Project Contact Information

Project Name

Qikiqtarjuaq Marine Infrastructure Project

Proponent and Representative Details

Proponent

Government of Nunavut – Community and
Government Services

Proponent Contact

Justin McDonnell, P.Eng.
A/ Manager Project Management
PO Box 1000 Station 200
Iqaluit, Nunavut X0A 0H0
Phone: 867-975-5441
Email: jmcdonnell@GOV.NU.CA

Consultant Representative

CBCL Limited

Consultant Contact

Loretta Hardwick, M.Sc.
Regulatory and Permitting Lead
112 Kent Street, Suite 400
Place De Ville Tower B
Ottawa, Ontario K1P 5P2
Phone: 343-552-2235
Email: lhardwick@cbcl.ca

Project Description

Project Purpose and Need

The primary objective of the Project is to improve the marine infrastructure in Qikiqtarjuaq including the construction of a deep-sea port, to support the needs of northern marine trade corridors, and especially the Davis Strait and Baffin Bay marine traffic.

Project Location and Land Use

Project Location

The Project will be located at Qikiqtarjuaq, Nunavut (Figure 1, attached), specifically in and on the shore of Broughton Channel (Figure 2, attached). The footprint of the new deep-water port will fall partially within the upland, tidal zone, and seabed area along the shoreline of Broughton Channel approximately one kilometre south of the Qikiqtarjuaq Airport.

Planning Region

The project will be carried out in the Qikiqtaaluk Region in southeastern Baffin Island.

Land Use and Ownership

Based on the 2015 Qikiqtarjuaq Community Plan and Zoning By-law, current land use at the proposed location for the Project falls into the following categories:

- Transportation
- Industrial

The entire Project area—including portion of Broughton Channel between Broughton Island and the mainland of Baffin Island—is designated in the 2015 Qikiqtarjuaq Community Plan and Zoning By-law as municipal lands under the administration of the Hamlet of Qikiqtarjuaq.

Project Overview and Components

The Project is a coastal infrastructure project that consists of the construction and operation of a 75-metre (m) long closed face marginal wharf structure with 10 m depth at low tide, and 18,000 square metres (m²) of laydown space. The Project will also include an approximately 200-m long access road from municipal roads to the facility, a crane to offload cargo, wastewater receiving systems, VHF radio communications station, services to allow for freezer containers, operations and security office, and power distribution. The proposed locations of project components are shown on Figure 2 (attached); Port Area 1 on Figure 2 shows the wharf and laydown area while Port Area 2 shows the armour stone protection around the marine perimeter.

In addition to the physical components of the Project, the following activities will be carried out during construction:

- ▶ Establishment of temporary construction work camp
- ▶ Establishment of temporary construction staging, laydown, and storage areas
- ▶ Dredging and reuse of dredged material
- ▶ Quarrying (drilling, blasting, excavation)
- ▶ Hauling quarried material from the quarry to the port site
- ▶ Upland pile driving
- ▶ Infilling
- ▶ Utility pole and lighting installation
- ▶ Building construction
- ▶ Marine-based concrete caisson installation (built off-site)

Construction of the Project will involve land-based (e.g., site preparation, quarrying rock) and marine-based activities (e.g., marine construction, dredging of material from the harbour bottom). Dredged materials may be reused as fill during construction. Rock sourced from a new local quarry will be used during construction. Rock will be hauled from the quarry via existing hamlet roads.

Project Schedule

Construction is scheduled to commence with mobilization of equipment and materials, and potentially some site preparation work in 2026. Site construction works will commence in 2026 and be completed by fall of 2029, with construction shut down over the winter seasons. Operation of the port is expected to commence at the start of the open water season in 2030.

Personnel

During construction, it is estimated that there will be 25 to 30 personnel required. Construction personnel will be required during the open-water season and those that are not residents of Qikiqtarjuaq will depart for the winter. During the active construction seasons, personnel will be onsite over a period of approximately 130 days for a total of 520 construction days per person over the course of the four-year construction phase. During operation, the port will be managed by the Department of Economic Development and Transportation (EDT). The number of personnel required during operation has not yet been determined.

Equipment and Materials

Equipment and materials required during construction of the Project will be determined by the contractor; however, the following sections provide an estimate of the equipment and materials that are likely to be required, based on the schematic design of the Project, the Project location, and experience with similar projects.

Equipment

Table 1 provides a summary of the types and quantities (units) of equipment that is estimated to be used during construction of the Project, along with the size (weight or dimensions) and proposed use. Equipment for managing the port during operation will include a mobile crane for loading and unloading ships, freezer units for storage of perishable goods, a forklift for material handling, and personal vehicles of employees.

Table 1 Estimate of Equipment Use During Project Construction

Type	Units	Description	Size (m)	Use
Drilling rig	2	5 ton	5.5 x 2.3	Quarrying
Excavator	5	30 - 60 ton	4 x 3.5	Quarrying, material handling, excavating
Rock truck	4	35 ton articulating	11.1 x 4.2	Transporting quarried rock
Transport truck	2	40 tons	16 x 2.9	Transporting equipment and materials
Front end loader	3	966 - 988	7.5 x 2.5	Material loading and handling
Compactor	1	20 ton	6.2 x 2.5	Work surface and road compaction
Bulldozer	1	D8	3.2 x 2.7	Work surface and road levelling
Grader	1	140 ton	10.1 x 2.5	Work surface and road grading
Spud barge/ derrick	1	20m x 50m deck with 150 ton crane	20 x 50	Dredging, transporting material and equipment
Material scow	2	500 cubic metre	47 x 11	Dredging and disposal of dredged material
Tug	1	1000 - 1500 horsepower	14.85 x 5.8	Transport and movement of marine equipment
Work boat	2	50 - 500 horsepower	9.75 x 2.9	Transport and movement of marine equipment and personnel
Pick-up truck	3	3/4 ton	4.8 x 1.9	Transport and movement of equipment and personnel
Fuel/service truck	1	10 ton	13 x 2.5	Transport fuel from Government of Nunavut Petroleum Products Division dispensers to mobile equipment
Water truck	1	10 ton	9.5 x 2.5	Transport water from municipal water to work camp and construction site
Wastewater truck	1	10 ton	9.5 x 2.5	Transport wastewater from work camp and construction site to municipal wastewater treatment facility
Telehandler/ forklift	1	5 ton	6.2 x 2.6	Material and equipment loading, handling, and movement

Type	Units	Description	Size (m)	Use
Rough terrain crane	1	250 ton	14.5 x 7.9	Material and equipment loading, handling, and movement
Rock Crusher for quarry	1	125 ton	14.6 x 4.2 14.3 x 4.2 17 x 3.6	Portable jaw crusher, cone and screening plant for the manufacturing of aggregate
Supply ship (Might Servant 2)	1	29,193 gross tonnage, 40,190 deadweight tonnage	190.03 length x 40 beam x 4 minimum draft	Transporting concrete caissons site

Fuel

Table 2 provides a summary of the types and quantities (units and volume) of fuel that is estimated to be used during construction of the Project, along with the proposed storage and use. Fuel storage and dispensing is not currently part of the project design but is expected to be required in the future.

Table 2 Estimate of Fuel Use During Project Construction

Fuel	Storage Method / Container Volume	Number of Containers	Total Volume (m ³)	Use
Diesel	Fuel will be dispensed on a daily basis from existing facilities in Qikiqtarjuaq	n/a	5,700	Mobile equipment, remote generators and heaters
Gasoline	Fuel will be dispensed on a daily basis from existing facilities in Qikiqtarjuaq	n/a	140	Small work boats, small generators and ATVs
Propane	100-lb (25 gallon) compressed gas tanks	10	1	Camp use (heating, cooking, refrigeration)
Acetylene	4 m ³ compressed gas cylinder	20	80	Metal cutting and welding torches

Hazardous Materials and Chemicals

Table 3 provides a summary of the types and quantities (units and volume) of hazardous materials and chemicals that are estimated to be used during construction of the Project, along with the proposed storage and use. During operation, hazardous materials and chemicals are expected to be similar to that used during construction, with the exception of explosives, which are not expected to be used during operation.

Table 3 Estimate of Hazardous Materials and Chemicals Use During Project Construction

Chemical / Material	Storage Method / Container Volume	Number of Containers	Total Volume	Use
Oils and lubricants	22.7-L (5-gallon) supplier containers	10	227 L (50 gallons)	Maintenance of mobile equipment
Paint	4.5-L (1-gallon) supplier containers	10	45 L (10 gallons)	Painting wharf hardware and miscellaneous components
Explosives	To be determined. Storage and handling will be in accordance with licence, certificate or permit issued under the Explosives Act and Regulations			Quarrying

Water Use

Because commercial accommodations in Qikiqtarjuaq are limited, it is expected that the contractor will establish a temporary work camp to accommodate personnel during construction. Water will be required primarily for cooking and consumption at the work camp and to a lesser degree at the construction site. During construction, it is estimated that approximately 6 m³ per day will be required for a total of 520 construction days. Water is not required during the winter shut-down periods.

During construction and operation, potable water will be delivered by bulk truck from the community water supply. The amount of water required during operation of the port has not been determined as it is not currently part of the project design but is expected to be required in the future.

Waste Management

Table 4 provides a summary of the types and quantities (units and volume) of fuel that is estimated to be used during construction of the Project, along with the proposed storage and use. During operation, wastes are expected to consist of combustible and non-combustible waste generated from the on-site office, as well as small amounts of hazardous waste that may be generated during routine maintenance activities. Waste generated during operation will be managed in a manner similar to that during construction.

Table 4 Estimate of Waste Production and Disposal During Project Construction

Waste Type	Associated Project Activity	Projected Amount Generated	Method of Disposal
Hazardous	Construction	100 L	Packaged, sealed and transported south in shipping containers for

Waste Type	Associated Project Activity	Projected Amount Generated	Method of Disposal
			disposal in accordance with applicable regulations
Combustible wastes	Camp	2 tonnes	Municipal landfill
Non-Combustible wastes	Camp	0.5 tonnes	Municipal landfill
Greywater	Camp	800 m ³	Collected in wastewater truck and transported to municipal wastewater treatment facility
Sewage (human waste)	Camp	1500 m ³	Collected in wastewater truck and transported to municipal wastewater treatment facility
Overburden (organic soil, waste rock)	Quarrying	Negligible	Stockpiled at quarry
Marine sediment	Dredging	25,000 m ³	Infilling, reuse, and/or land disposal

Permits, Authorizations, and Approvals

Table 5 presents a list of approvals, permits, authorizations, and licenses that are expected to be required for construction of the Project, after the Nunavut Planning Commission completes a review of the Project proposal to determine conformity.

Table 5 Approvals, Permits, and Authorizations for Project Construction

Approval / Permit / License /Authorization	Regulatory Authority	Associated Component or Activity
Screening of Project Proposal	Nunavut Impact Review Board	Entire Project
<i>Fisheries Act</i> Authorization	Fisheries and Oceans Canada (DFO)	Construction below high-water mark
Approval under <i>Canadian Navigable Waters Act</i>	Transport Canada	Installation of structures that will impact navigation
Explosives License	Natural Resources Canada	Quarrying
Type B Water License	Nunavut Water Board (NWB)	Water use for camp
Explosives License	Government of Nunavut Workers Safety & Compensation Commission (WSCC)	Quarrying (acquisition and storage of explosives)
Commercial / Industrial Land Lease	Hamlet of Qikiqtarjuaq	Port
Land Use Permit	Hamlet of Qikiqtarjuaq	Quarrying, camp site
Quarrying Permit	Hamlet of Qikiqtarjuaq	Quarrying
Fire Marshall Approval	Hamlet of Qikiqtarjuaq	Port, work camp

Approval / Permit / License /Authorization	Regulatory Authority	Associated Component or Activity
Development Permit/ Agreement	Hamlet of Qikiqtarjuaq	Port, work camp, quarry
Obstacle Notice and Assessment	Transport Canada, Civil Aviation Office, Prairie and Northern	Proximity to airport
Land Use Review	NAV Canada, Land Use Office	Qikiqtarjuaq Airport zoning regulations
Qikiqtarjuaq Airport Zoning	GN – Nunavut Airports, Operations & Safety	Proximity to airport
Aids to Navigation Review	Canadian Coast Guard (CCG)	Safe marine navigation measures

Consultation

Community consultation sessions have included members of the Hamlet Council, local elders, community members, as well as other organizations. Additionally, independent from the port project, Qikiqtarjuaq is undergoing long term community planning. Community consultation will help to ensure that the port project and long-term port master plan is consistent with the community strategy and plans. The Team will continue to gather and summarize input, concerns, knowledge, and experience from community members and local/regional businesses and share the updates with regional/territorial/national stakeholders who have lobbied for the long anticipated deep-sea harbour.

Community consultations have been broken down into three separate consultation meetings taking place within the community.

Community Consultation 1

The initial consultation on the Project design took place in December 2023. At the time of the initial meeting, design elements were in early stages. For the information that was available at the time of the meeting, the project team met with community representatives by meeting with Hunters and Trappers Organization (HTO), Hamlet Council, and Qikiqtani Inuit Association (QIA). The purpose of the initial stakeholder meeting was to update community members on the following:

- ▶ Introduce the project team.
- ▶ Layout the design process and present project timeframes.
- ▶ Present preliminary findings from initial coastal and bathymetric survey and present justification for the proposed project site.
- ▶ Confirm community agreement for the proposed project site.
- ▶ Identity any community concerns or applicable information associated with the proposed site.

A critical milestone for this consultation was to verify the community agreement with the site location. Information from this session was required to then begin conversations with shipping companies about locations, mooring, and ship movement logistics. Additionally, this information was required to confirm borehole locations for the upcoming field programs and permitting applications.

Community Consultation 2

The second community consultation took place in the Hamlet of Qikiqtarjuaq March 18 to 20, 2024 to update the Hamlet, HTO, QIA, Arctic Fisheries Alliance and public on the following:

- ▶ The preferred option that was being presented in a high level site plan.
- ▶ Overview of the upcoming field programs
- ▶ Proposed work areas

The following input from the community was sought during these sessions:

- ▶ Set up working group
- ▶ Identify members for Traditional Knowledge (TK) study
- ▶ Identify areas of concern with work that is proposed
- ▶ Begin discussion on land use in the vicinity of the harbour

The material provided and presented during Consultation Number 2 was to present the various field studies that are to take place and determine if there was any concern or additional information that would be beneficial to the design team.

Community Consultation 3

The third community consultation took place in the Hamlet of Qikiqtarjuaq the week of October 7 to 9, 2024. The following meetings were held:

- ▶ October 7, 2024, with Working Group for general update and Traditional Knowledge Gathering
- ▶ October 7, 2024, with Hamlet Council and HTO for general update
- ▶ October 8, 2024, meeting with Elders and HTO for Traditional Knowledge Gathering
- ▶ October 8, 2024, Community Open House

This was the third of the three consultations planned for this project with the objective to obtain community concerns, address questions, and provide information to stakeholders on the project planning and development.

Environmental Impacts, Mitigation, and Management

Environmental and Socio-economic Impacts

The potential adverse environmental and socio-economic effects of the Project are anticipated to occur primarily during construction. The potential effects during operation are expected to be predominantly positive socio-economic effects. The potential adverse and positive environmental and socio-economic effects associated with construction and operation of the Project are outlined below:

- ▶ Atmospheric Environment
 - Changes in local air quality (emissions from operation of combustion engines, dust)
 - Changes in local acoustic environment (noise from operation of equipment, blasting, and pile driving)
 - Changes in local ambient light (lighting during construction and operation)
- ▶ Terrestrial Environment
 - Change in terrain (from quarrying and infilling)
 - Changes in soil quality (impacts from accidental spill of fuel or hazardous material)
 - Disturbance to terrestrial wildlife
- ▶ Aquatic Environment
 - Changes in water quality (impacts from accidental spill of fuel or hazardous material, increase in suspended sediment during construction)
 - Disturbance to marine wildlife
 - Alteration or loss of fish habitat
- ▶ Socio-economic Environment
 - Change in land use
 - Conflict with resource users (disruption to navigation, hunting, or fishing)
 - Disturbance to local community from increase in traffic, noise, light, and dust
 - Increased pressure on municipal services and infrastructure
 - Increase in capacity for marine infrastructure users (fishing, shipping, docking)
 - Increase in potential for economic development during operation
 - Increase potential for local employment
 - Improved function and capacity for storage

Environmental Mitigation and Management

Potential adverse environmental effects of the Project will be mitigated and managed through the development and implementation of a Construction Environmental Management Plan (CEMP) and an Operation Environmental Management Plan (OEMP). The CEMP and OEMP will detail the environmental protection requirements and mitigation measures that will be adhered to on the Project site and will provide a framework for the development and implementation of safe and environmentally responsible practices to reduce environmental effects of the Project. The CEMP

and OEMP will provide overall strategies and guidance for compliance with relevant environmental legislation and policies, as well as compliance with the terms and conditions of permits and approvals obtained. Construction personnel will be trained in the requirements of the CEMP and advised of the regulatory requirements and conditions for the Project construction. Operation personnel will be trained in the requirements of the OEMP and advised of the regulatory requirements and conditions for the Project operation.

The CEMP will include the following, some of which will be developed by the contractor:

- ▶ Project overview and purpose of the plan
- ▶ Outline of relevant regulatory requirements and conditions
- ▶ Description of roles and responsibilities
- ▶ Mitigation and management plans
- ▶ Spill prevention, contingency, and emergency response plan
- ▶ Erosion and sediment control plan
- ▶ Waste management plan
- ▶ Traffic management plan
- ▶ Blasting management plan
- ▶ Marine construction management plan
- ▶ Wildlife mitigation and monitoring plan
- ▶ Monitoring and reporting requirements

The OEMP will include the following, which will be developed by the Government of Nunavut Department of Community and Government Services (CGS) or Department of Economic Development and Transportation (EDT):


- ▶ Project overview and purpose of the plan
- ▶ Outline of relevant regulatory requirements and conditions
- ▶ Description of roles and responsibilities
- ▶ Mitigation and management plans
- ▶ Spill prevention, contingency, and emergency response plan
- ▶ Erosion and sediment control plan
- ▶ Waste management plan
- ▶ Traffic management plan
- ▶ Safety plan
- ▶ Wildlife mitigation and monitoring plan
- ▶ Monitoring and reporting requirements
- ▶ Inspection, reporting, and conformance requirements
- ▶ Training and competency requirements
- ▶ Communications procedures

Closure

We trust this letter provides the information required to support the Nunavut Planning Commission's review of the proposal for the Qikiqtarjuaq Marine Infrastructure Project to determine conformity land use plans. If you have any questions or require further details, please do not hesitate to contact the undersigned.

Yours very truly,

CBCL Limited



Loretta Hardwick, M.Sc.
Director, Environmental Science
Direct: 343-552-2235
E-Mail: lhawdwick@cbcl.ca



David Parsons, P.Eng.
Project Manager

Attachments: Figures

CC: Justin McDonnell, P.Eng., Government of Nunavut, Community and Government Services

Report No: 234414.00

This document was prepared for the party indicated herein. The material and information in the document reflect CBCL Limited's opinion and best judgment based on the information available at the time of preparation. Any use of this document or reliance on its content by third parties is the responsibility of the third party. CBCL Limited accepts no responsibility for any damages suffered as a result of third-party use of this document.

Attachment A



Figures

Document Path: Y:\Halifax\Data\Projects\2023\234414.00 Gov of NU A&E Marine Infrastructure\44 CAD\03 GIS\PROJ\234414_Qikiqtarjuaq.aprx - cmacdonald - 18/Feb/2025



LEGEND

- Qikiqtarjuaq Marine Infrastructure Site





**QIKIQTARJUAQ
MARINE INFRASTRUCTURE**

PROJECT LOCATION


DATE: 2025-02-18	PROJ N°: 234414.00	FIGURE: 1
DRAWN BY: CM	CHECKED BY: KH	APPROVED: LH

NOTES:





1:1,000,000 Coordinate System: NAD 1983 CSRS UTM Zone 20N

Document Path: Y:\Halifax\Data\Projects\2023\234414.00 Gov of NU A&E Marine Infrastructure\44 CAD\03 GIS\PROJ\234414_Qikiqtarjuaq.aprx - cmacdonald - 18/Feb/2025



- LEGEND**
- Port - Area 1
 - Port - Area 2
 - Proposed Camp Pad Area
 - Proposed Quarry Location
 - Proposed Stockpile Area
 - Quarry Site
 - Service Road





**QIKIQTARJUAQ
MARINE INFRASTRUCTURE**

**PROPOSED LOCATIONS OF
PROJECT COMPONENTS**

DATE: 2025-02-18	PROJ N°: 234414.00	FIGURE: 1
DRAWN BY: CM	CHECKED BY: KH	APPROVED: LH

NOTES:



1:20,000 Coordinate System: NAD 1983 CSRS UTM Zone 20N