



1 Project Overview

1.1 Introduction

The Municipality of the Corporation of Baker Lake (the Hamlet), with support from the Government of Nunavut (GN) received funding from Transport Canada (TC) under the Oceans Protection Plan (OPP) for the construction of the sealift and laydown area (the Project) in the Hamlet of Baker Lake, Nunavut. Worley Canada Services Ltd., operating as Worley Consulting, has been retained by the Hamlet to design and support the construction of the Project in the Hamlet of Baker Lake. Dynamic Ocean Consulting Ltd. (Dynamic Ocean) is supporting Worley Consulting on the permitting requirements for the Project.

The Project is within municipal boundaries and will require a resolution by the Hamlet Council once the design is finalized. Council has accepted the design in concept (see Drawing 3-1, Appendix A). The Project is consistent with the community's land use and zoning plan, and the land is already appropriately zoned. The Baker Lake Community Plan and Zoning By-Law is provided in Appendix B.


This letter provides details for the Project to support screening by the Nunavut Impact Review Board (NIRB).

1.2 Project Location


The Hamlet of Baker Lake is located on the northwestern shore of Baker Lake in the Kivalliq Region of Nunavut (64°18.583' N, 95°58.485' W) (Figure 1-1). The community conforms with the Keewatin Regional Land Use Plan (KRLUP) (NPC, 2000)). While Baker Lake is within the NBRLUP, the Recommended Nunavut Land Use Plan (RNLUP) (NPC, 2023) will replace the NBRLUP once it is approved.

1.3 Project Name

Baker Lake Sealift and Laydown Area Project (hereafter referred to as the Project).



- New Sealift
- Quarries
- Existing Sealift



GCS: NAD 1983
 Datum: NAD 83
 Projection: UTM Zone 8N
 Map Units: Meters
 Exported: 07/04/2025
 Drawn: C Laidlaw

Figure 1-1

Project Location

2 Proponent and Representative Details

Contact information for the proponent and representative are provided in Table 2-1.

Table 2-1: Proponent and Contact Information

Information Request	Details
Application: Municipality of Baker Lake	
Applicant's Name	Sheldon Dorey Senior Administrative Officer
Address	P.O. Box 149, 3022 - 4th Avenue Baker Lake, NU X0C 0A0
Telephone	1-867-793-2874
Email	sdorey@bakerlake.ca
Applicant Representative: Dynamic Ocean Consulting Ltd.	
Name	Victoria Burdett-Coutts, MSc, RPBio Senior Marine Scientist and Regulatory Professional
Address	2901 Murray Street Port Moody, British Columbia V3H 1X3
Telephone	1-778-839-2372
Email	victoria@dynamicocean.ca
Design Engineer: Worley Canada Services Ltd.	
Name	Andre Dratwa, MEng, PEng Marine Structural Engineer
Address	Suite 200, 2930 Virtual Way Vancouver, British Columbia VM5 0A5
Telephone	1-778-945-5233
Email	andre.dratwa@worley.com



3 Project Description

3.1 Project Scope

The Project includes the following components:

- A new sealift laydown area.
- Access roads to the laydown area from adjacent existing roads.
- A new landing ramp for normal small ramp-onboard barges.

Design drawings are provided in Appendix A, with the General Arrangement provided in Drawing 3-1.


The Project will not require additional infrastructure to be developed for a haul road or quarry, as existing Hamlet infrastructure will be utilized. Aggregates that are imported to the site will be taken from either the quarry site, approximately six kilometres (km) north of the Hamlet along the road to Agnico Eagle Meadowbank (AEM) or the gravel pit to the west of the Hamlet, both of which are within the municipal boundaries.




PLAN
1:750

NOTES:


- FOR GENERAL NOTES, SEE DWG. 317086-48113-00-MA-DGA-0001.
- NO WORK IS TO BE EXECUTED WITHIN THE WATER. PUSHOUT AND RAMP TO BE SET BACK 0.5m FROM HIGH WATER LEVEL.



REV	DATE	REVISION DESCRIPTION	DRAWN	DRAFT CHK	DESIGNED	ENG CHK	APPROVED	QAR	REF DRAWING No	REFERENCE DRAWING TITLE
D	29-MAY-25	ISSUED FOR PERMITTING	AAL	BJM	AD	-	AD	-		
C	20-MAR-25	RE-ISSUED FOR CLIENT REVIEW	JLC	-	AD	-	AD	-		
B	23-OCT-23	RE-ISSUED FOR CLIENT REVIEW	JLC	-	AD	-	HGK	-		
A	29-MAY-23	ISSUED FOR CLIENT REVIEW	JLC	-	AD	-	HGK	-		

D SHEET	SCALE	SHOWN	ENGINEERING AND PERMIT STAMPS (As Required)	CUSTOMER
			<div style="border: 1px solid black; padding: 5px; display: inline-block;"> PRELIMINARY DO NOT USE FOR CONSTRUCTION Last Saved: May 29/25 10:23am </div>	
WORLEY PROJECT No				
317086-48113				

This drawing is prepared for the use of the contractual customer of Worley Canada Services Ltd. and Worley Canada Services Ltd. assumes no liability to any other party for any representations contained in this drawing.



**HAMLET OF BAKER LAKE
SEALIFT INFRASTRUCTURE
GENERAL ARRANGEMENT**

DRG No	Drawing 3-1	REV	D
--------	-------------	-----	---

3.2 Project Background

Most dry goods throughout Nunavut are delivered to communities by Nunavut Sealink and Supply Inc. (NSSI) and Nunavut Eastern Arctic Shipping Inc. (NEAS). These carriers typically use ships originating from Montreal, Quebec and occasionally from the Port of Churchill, Manitoba. These ships will carry cargo for numerous communities and make many stops during their voyage before returning to the port of departure to pick up cargo for another voyage.

Front-end loaders and operators from the ships are brought to the beach to unload barges and stack and store cargo upland, above the High-Water Line (HWL). In some cases, the carrier is also contracted to deliver the cargo into the community, such as in the case of the Northern Store and the Co-Op. In other cases, a local company is hired to deliver the cargo from the laydown area, and much of the smaller private cargo is claimed at the laydown area by the owners. All arriving cargo must be signed for before the carrier is able to leave.

Often, and especially in the case of project cargo (such as construction materials for buildings), the cargo is stored at the laydown area after being signed for and can stay in the laydown area for weeks or even months. Empty containers are frequently returned to the laydown area throughout the winter as retrograde cargo for the following season.

Baker Lake is the fourth largest community in Nunavut with a population of 2,067 residents according to 2016 census data from Statistics Canada, which also noted a 10.5 % increase in population since 2011 (Statistics Canada, 2017). Considerable population growth and supporting services to the AEM mine has resulted in Baker Lake seeing a steady increase in sealift cargo. Baker Lake is also unique as the only inland community in Nunavut, and navigating the Chesterfield Narrows to access the lake adds extra logistical complications to cargo delivery.

3.3 Sealift Infrastructure Purpose & Community Benefits

Improvements to the existing sealift area are not practical given it has outgrown the open space designation of the original sealift space. The overflow on the opposite side of the road has commercial zoning, which is not suitable for sealift marshalling/storage. The Project will improve the safety of the sealift operation in the Hamlet as well as any other communities in the Kivalliq Region being subsequently serviced by the sealift. A faster, safer, and more efficient sealift operation in Baker Lake will contribute to speeding up the overall sealift operations within the region and reduce the overall risk of weather on the carrier.

3.4 Study Areas

The Project Study Area includes the footprint of the Project components plus a 100 metres (m) buffer.

3.5 Project Components & Construction Activities

3.5.1 Aggregates

The laydown and storage area, access road, and sealift ramp will be constructed using a combination of fill imported to the site as well as locally excavated fill and will be built up and graded as per design drawings. The sealift ramp is designed to be set back 0.5 m from the HWL.

The infill placement and shaping of the sealift features will be completed using land-based equipment, where a working platform will be constructed at the shore side and fill will be placed from the shore to the seaward extent of the Sealift site using an excavator. The working platform will not extend beyond the footprint of the Sealift site, and no work will be required to be completed in-water. Fill material will be placed in uniform layers as per design notes and compacted prior to placing the succeeding layer.

Aggregates material will be required to support construction of the sealift laydown, access road and barge ramp. A total of 22,370 m³ of material is expected to be required, which may be partially obtained during excavation at the Project site.

3.5.2 Sealift Laydown

A new laydown area will be constructed approximately 500 m east of the easternmost extent of the current developed zones. The new laydown area will initially measure approximately 1.5 hectares (ha) but will retain the potential for further eastward or northward expansion. Due to the approximately 1V:10H ground slope in the proposed area, the laydown area will consist of a single bench, partially cut and partially filled, and covered by 0.3 m of processed gravel at a 4 % slope. Drainage ditches on the upland side will redirect surface water both east and west, and down toward the lakeshore.

A desktop geological assessment of the site, together with data from approximately 800 m down the shoreline, shows that an overlying granular layer should be available for cutting and filling works (Worley Consulting, in prep). An allowance is carried to remove surficial organics.

3.5.3 Access Road

A new access road will be constructed to link the existing road with the laydown area. The road will be approximately 135 m long, 10 m wide and consist of 1.2 m of pit-run fill covered by 0.3 m of processed gravel. Drainage for the site will be a ditch cut alongside the road, and a culvert beneath to roadway access to the laydown area. The access road will be built via cut/fill of existing materials and will be topped with road base and sub-base gravels. This road is part of the permanent installation, although it may support some haul traffic as it is the primary access to the major area of construction. Beyond the access road, all proposed segments of the haul route use existing roads.

3.5.4 Barge Ramp

A new landing ramp will be constructed to the edge of the lakeshore and will be accessible from the lower bench of the laydown area. The ramp will be 30 m wide to allow for two barges to unload simultaneously and will be surfaced with 0.5 m of processed gravel. The ramp will not extend below the HWL.

3.5.5 Power and Lighting

Power is planned to be brought in from the Hamlet, approximately 500 m to the west of the new sealift area. Lighting for the laydown area and the ramp will be provided. The components will be standard Qulliq Energy Corporation (QEC) poles and LED flood lights.

3.5.6 Fencing

Approximately 600 m of fencing is planned to be installed around the perimeter of the laydown area, including rolling gates at the main road access. Additional rolling gates or sections of movable fencing



may be installed at the inshore end of the barge landing ramp provided they do not impede operating equipment during sealift operations.

3.5.7 Signage

Signage is planned to be installed at the sealift site and at the roadway junction, and will include standard road signs, caution at the entrance, and instructions/demarcation for sealift in both Inuktitut and English.

3.6 Schedule

Construction is planned to begin in summer 2025 and is expected to take approximately four months to complete, over a period of 124 days. Construction is expected to occur daily over a 10-hour period. The Project is expected to be operational in the open-water season of 2026.

3.7 Personnel

A crew of approximately 15 project personnel are anticipated to be at the Project site during construction (see Table 3-1).

The workforce will be comprised of skilled and semi-skilled labour including, heavy equipment operator, truck driver, mechanic, electrician, and general labourers. Work rotations for non-local labour are presently unknown but will be determined by the contractor, and will comply with all applicable Workers Safety and Compensation Commission (WSCC) regulations (WSCC, 2021).

The Project aims to comply fully with the GN’s Nunavummi Nangminiaqqtunik Ikajuuti (NNI) Policy (01 April 2017) and will aim to maximize participation of Inuit labour, training and Inuit-owned businesses on the Project (GN, 2017).

The Project anticipates the community will see further economic benefits and training opportunities with the hiring of local labour during construction. In addition, there will be secondary economic benefits through the Project’s expenditures in local businesses.

Project personnel travelling to the site (if using a non-local labour force) will use air travel and are expected to use chartered flights, with limited use of scheduled flights.

Table 3-1: Personnel Numbers for the Project

Shift Type	Total Number of Personnel	Total Number of Days on Site per Season	Total number of Person Days per Season
10-hour	15	124	1,860

4 Consultation

The concept has been developed by Worley Consulting in collaboration with the community following a joint meeting with the Hamlet, the Baker Lake Hunters and Trappers Organization (HTO), and public engagement sessions at an information booth at the Co-Op store in February 2020. Consultations were facilitated using a one-page information leaflet about the OPP, maps, aerial photographs, and large-scale drawings. All consultation materials were provided in both Inuktitut and English. Local radio and Facebook posts were placed to inform the community of the location, date, and time of the information booth.

Letters of support has been provided by the Hamlet and HTO (see Appendix C).

In addition, Worley Consulting consulted with the marine carriers regarding the needs of delivery vessels and the community, and obtained positive feedback on the proposed improvements. Worley Consulting recently completed a similar project in Kinngait and received positive feedback from carriers on the new sealift.

5 Project Map

See Figure 1-1.

6 Land Use and Licensing

6.1 Land Use

The Project will occur within the land use areas described in Table 6-1.

Table 6-1: Land Use and Ownership

Administrative Boundary	Kivalliq Region
Planning Reion	Keewatin
Land Use	The Project, which by NPC’s descriptions, would be most closely categorized as Transportation and/or Communications Corridor.
Land Ownership	Municipal

6.2 Permitting

A summary of permits expected to be required, based on construction activities, is provided in Table 6-2.

Table 6-2: Licenses and Permits Relevant to the Program

Permit	Regulatory Authority	Construction Activity	Comment
Determination of Referral to the NIRB	NPC	Any development of land and water resources within Nunavut.	NPC will be engaged to determine if the Project will be referred to the NIRB. The Project sits entirely within municipal lands.
Screening Decision Report	NIRB	Any development of land and water resources within Nunavut.	If the Project is referred to the NIRB, a Part 4 Screening is expected.
Minor Works or Approval	TC	Navigational interferences during construction or change to navigation during operations.	While there are no works below the HWL, TC will be engaged to confirm any requirements for navigation during the operational phase of the Project.
Letter of Advice (LoA) or <i>Fisheries Act Authorization</i> (FAA)	Fisheries and Oceans Canada – Fish and Fish Habitat Protection Program (DFO-FFHPP)	In-water or near-water works associated with the construction that have the ability to result in the Harmful Alteration, Disruption or Destruction (HADD) to fish or fish habitat , as defined under the <i>Fisheries Act</i> .	There are no works below the HWL, therefore it is not expected that the HADD (Section 35) or death of fish (Section 34) will occur. A request for review (RFR) has been submitted to DFO-FFHPP (Dynamic Ocean, 2025a) to confirm if there are requirements, in addition to those proposed in the Construction Environmental Management Plan (CEMP) (Dynamic Ocean, 2025b) for the protection of fish and fish habitat.
Design and Development Permit/Approval	Hamlet of Baker Lake	Engagement with council to confirm approval for the Project design.	The Hamlet will be engaged to obtain necessary development permits.
Land Use Permit (LUP)	Crown-Indigenous Relations and Northern Affairs Canada (CIRNAC)	Construction below Ordinary High-Water Line (OHWL) for land tenure under Commissioners or Untitled Municipal lands.	A LUP will be required from CIRNAC as there are no components of the Project below the OHWL. However, the Project will respond to Information Requests (IRs) as needed during the NIRB process (should it be required).



Permit	Regulatory Authority	Construction Activity	Comment
Class 2 Nunavut Territory Archeologist Permit	Government of Nunavut - Culture and Heritage (GN-C&H)	Any development of previously undisturbed land resources in Nunavut.	Permit application to conduct an Archaeological Impact Assessment (AIA) has been submitted.

7 Material Use

The following equipment and materials are indicative and are subject to change depending on the contractor’s methodology and equipment. Measures will be in place to confirm that all equipment and materials are safely stored, utilized and when pertinent disposed of. The contractor will maintain an equipment and materials manifest.

7.1 Equipment

Typical equipment type, approximate quantity, size/dimensions and proposed use are outlined in Table 7-1.

Table 7-1: Equipment Use

Equipment Type and Quantity	Size - Dimensions	Proposed Use
Excavator - 2	30 to 40 tons	Handling aggregates and earthworks.
Front-end Loader - 1	20.25 ft. high by 7.91 ft. wide	Loading aggregates.
Rock Truck - 3	21 ft. long by 8.5 ft. wide	Hauling aggregates.
Roller Compactor - 1	-	Road construction.
Crusher - 1	-	Processing aggregates.
Screener - 1	-	Processing aggregates.

Note: Design drawing (Appendix A, 317086-48113-00-MA-DGA-0003) specifies that no work will be executed in-water and the ramp will be set 0.5 m back from the HWL

7.2 Fuel Use

Fuel use and storage methods are outlined in Table 7-2.

Table 7-2: Fuel Use and Storage Methods

Fuel	Number of Containers and Capacity	Total Amount of Fuel (in Litres [L])	Proposed Storage Methods	Proposed Use
Diesel	4 – 100,00 L	400,000	N/A, fuel will be dispensed on a daily basis from existing facilities in the Hamlet.	Mobile equipment, generators, and heaters.
Gasoline	2 – 500 L	1000	N/A, fuel will be dispensed on daily basis from existing facilities in the Hamlet.	Mobile equipment, generators, and heaters.

7.3 Hazardous Materials

Hazardous and chemical materials expected to be required during construction are outlined in Table 7-3.

Table 7-3: Hazardous Materials and Chemical Use

Hazardous Materials and Chemicals	Number of Containers and Capacity	Total Amount of Hazardous Materials and Chemicals	Proposed Storage Methods	Proposed Use
Lubes and Oils	8 – 5 Gallons	40 Gallons	Drums on pallets in lined and bunded storage area.	Maintenance of mobile equipment.

7.4 Water Use

Water for the Project will be used for municipal and industrial purposes. The Project water use requirements and proposed sourcing are outlined in Table 7-4.

Table 7-4: Water Use

Daily Amount (m ³)	Proposed Water Retrieval Methods	Proposed Water Retrieval Location
Average of 3.5 m ³ will be used per day.	Municipal equipment.	Municipal water supply.

7.5 Waste Management

Waste management activities are outlined in Table 7-5.

Table 7-5: Waste Management – Types and Disposal Methods

Type of Waste	Projected Amount Generated	Method of Disposal
Hazardous Waste	1,600 L	Returned to south in sealed drums or lined bags, transported in 20 ft. shipping containers and disposed in accordance with regulatory procedures.
Greywater and Sewage (Human Waste)	400 m ³	Municipal sanitary truck to Hamlet sewage lagoon.

8 Environmental Management

8.1 Potential Environmental and Social Impacts

Potential environmental and social impacts that may occur during the construction and operation of the Project are described in Table 8-1.

Table 8-1: Environmental Effects and Mitigation

Environmental Effect	Mitigation
Change of Disturbance Risk to Terrestrial Habitats and Wildlife from Construction	<ul style="list-style-type: none"> • A CEMP has been developed to implement mitigation and monitoring measures for the Project to prevent impacts to the environment and community. • A pre-construction terrestrial wildlife sweep will be conducted prior to construction to mitigate harm to wildlife. • Terrestrial habitat will be impacted within the Project footprint where the infrastructure will be placed. For terrestrial habitats outside of the Project footprint, flagging tape or other visible markers may be used to identify sensitive vegetation communities or other sensitive features that should not be impacted within a 30 m buffer from the Project site. • Flagging tape and other markers will be removed upon completion of works.
Change of Terrestrial Land Use	<ul style="list-style-type: none"> • A notice will be provided to the community prior to construction to describe the planned work and potential impacts to community access as fencing will be set up for human health and safety purposes.
Change to Ambient Noise, Dust, and Light Related to Construction Activities	<ul style="list-style-type: none"> • The Project is expected to be completed over a four-month period and will be limited to the Project footprint. • Noise will generally be restricted to 10-hour shifts. • Lights, if needed, will be positioned towards the work area to reduce ambient light to outside the Project area. • Mitigations will be outlined in the CEMP for the Project and will be developed to confirm to government guidelines, including Ambient Air Quality (GN, 2023a) and Dust Suppressants (GN, 2023c).
Change in Risk of Accidental Leaks and Spills to the Environment	<ul style="list-style-type: none"> • A Spill Prevention and Emergency Response Plan (SPERP) has been developed as a component of the CEMP and implemented by the contractor that will include requirements for spill response kits, proper fuelling techniques and the required use of secondary containment.

Environmental Effect	Mitigation
	<ul style="list-style-type: none"> The SPERP conforms to the requirements as outlined in the Contaminant Spill Remediation (GN, 2023b) and Spill Contingency Planning and Reporting Regulations (GN, 2023d).
Risk of Sediment Run-Off Into the Aquatic Environment During Construction Activities	<ul style="list-style-type: none"> A Sediment and Erosion Control (SEC) Plan has been developed as a component of the CEMP. The CEMP will be implemented by the contractor for the Project. Mitigation measures will be implemented and managed, and adaptive management using sediment control will be applied to continually manage unforeseen environmental conditions to prevent sediments/sedimentation to any waterbody.
Change in Risk to Accidental Unearthing of Archaeological Artifacts During Ground Disturbance Work	<ul style="list-style-type: none"> An Archaeological Discovery Plan (ARDP) will be developed to mitigate and manage archaeological discovery. Any archaeological artifacts/fossils unearthed during ground disturbance will be reported to the Territorial Archaeologist and work will be halted immediately until the Territorial Archaeologist provides direction for the continuation of works.
Change in Personnel Numbers Within Community that Increase Personnel Infrastructure Needs and Support Services	<ul style="list-style-type: none"> There is potential for the additional, non-local personnel requiring community infrastructure and support services during construction. However, construction is anticipated to be completed within one open-water season.
Change in Truck Occurrence and Traffic Through Community	<ul style="list-style-type: none"> A Traffic Management Plan has been developed as a component of the CEMP and will be implemented by the contractor to manage site access, traffic through the community, and inform the community of any on-going construction traffic safety or maintenance concerns (e.g., dust suppression).

8.2 Construction Environmental Management Plan

A CEMP has been developed to support permitting, and to confirm mitigation and monitoring measures to minimize negative effects to socio-economic and environmental factors. The mitigations and monitoring measures will be implemented during construction.

9 Reference

- DFO. (2025). Letter of Advice. Baker Lake Sealift and Laydown Area, NU – Implementation of Measures to Avoid and Mitigate the Potential for Prohibited Effects to Fish and Fish Habitat. File No. 25-HCAA-01230. 4 July 2025. Issued to the Municipality of Corporation of Baker Lake (Sheldon Dorey).
- Dynamic Ocean. (2025a). Baker Lake Sealift and Laydown Area Fisheries and Oceans Canada Request for Review Supplemental Report. Doc No: REP-WRL-10-Baker Lake Sealift Laydown RFR Supplemental Report-0001-25. June 8, 2025. Rev1.
- Dynamic Ocean. (2025b). Baker Lake Sealift and Laydown Area: Construction Environmental Management Plan. Prepared for the Municipality of the Corporation of Baker Lake. Doc No: PLN-WRL-10-Baker Lake Construction Environmental Management Plan-0001-25 May 2025. Rev6.
- Fisheries Act*. R.S.C. 1985, c F-14. Last amended: August 28, 2019. Available at: <https://laws-lois.justice.gc.ca/eng/acts/f-14/>. Accessed: March 2025.
- GN. (2017). Nunavummi Nangminiqqtunik Ikajuuti Implementation Act. Available at: <https://nni.gov.nu.ca/>. Accessed: November 2024. *Department of Economic Development and Transportation*.
- GN. (2023a). Environmental Guideline for Ambient Air Quality. Department of Environment. Available at: <https://www.gov.nu.ca/sites/default/files/publications/2024-05/Ambient%20Air%20Quality%202023-03.pdf>. Accessed: March 2025.
- GN. (2023b). Environmental Guideline for Contaminant Spill Remediation. Department of Environment. Available at: <https://www.gov.nu.ca/sites/default/files/publications/2024-05/Contaminant%20Spill%20Remediation%202023-03.pdf>. Accessed: March 2025.
- GN. (2023c). Environmental Guideline for Dust Suppression. Department of Sustainable Development Environmental Protection Service. January 2002. Available at: <https://gov.nu.ca/sites/default/files/Guideline%20Dust%20Suppression.pdf> Accessed: March 2025.
- GN. (2023d). Environmental Guideline for Spill Contingency Planning and Reporting Regulations. Department of Environment. Available at: <https://www.gov.nu.ca/sites/default/files/publications/2024-05/Spill%20Contingency%20Planning%20and%20Reporting%20Regulations%202023-03.pdf>. Accessed: March 2025.
- NPC. (2000). Keewatin Regional Land Use Plan. Available at: <https://www.nunavut.ca/land-use-plans/keewatin-regional-land-use-plan> Accessed: June 2025.
- NPC. (2023). Recommended Nunavut Land Use Plan (RNLUP). Available at: https://www.nunavut.ca/sites/default/files/23-001e-2023-06-20-recommended_nunavut_land_use_plan-eng_r.pdf. Accessed: November 2024. 136p.
- Statistics Canada. (2017). Baker Lake [Population centre], Nunavut and Nunavut [Territory] (table). Census Profile. 2016 Census. Statistics Canada Catalogue no. 98-316-X2016001. Ottawa.



Released November 29, 2017. <https://www12.statcan.gc.ca/census-recensement/2016/dp-pd/prof/index.cfm?Lang=E>. Accessed: April 2025.

Worley Consulting. (in prep). Appendix 4 of Comprehensive Marine Infrastructure Scoping Study. Doc No. 317071-00019-00-MA-REP-0001.

WSCC. (2021). Workers Safety & Compensation Commission Legislation. Available at: <https://www.wsc.nt.ca/about-wsc/policy-and-legislation/legislation#SafetyAct> Accessed: November 2024.

Appendix A: Design Drawings





HAMLET OF BAKER LAKE OCEANS PROTECTION PLAN FUNDED SEALIFT INFRASTRUCTURE

DRAWING NO.	DESCRIPTION
317086-48113-00-MA-DGA-0001	COVER SHEET, DRAWING LIST AND GENERAL NOTES
317086-48113-00-MA-DGA-0002	EXISTING SITE PLAN
317086-48113-00-MA-DGA-0003	GENERAL ARRANGEMENT
317086-48113-00-MA-DGA-0004	TYPICAL SECTIONS

GENERAL NOTES:

1.0 GENERAL




- 1.1 ALL WORK SHALL BE COMPLETED IN ACCORDANCE WITH ENVIRONMENTAL AND REGULATORY DOCUMENTATION PROVIDED BY THE OWNER OR AS REQUIRED BY MUNICIPAL, TERRITORIAL, OR FEDERAL LEGISLATION.
- 1.2 NO WORK IS TO BE EXECUTED WITHIN THE WATER.
- 1.3 ANY DAMAGE INCURRED IN THE EXECUTION OF THIS WORK TO ANY PART OF THE PROPERTY NOT SPECIFICALLY DESIGNATED FOR CONSTRUCTION SHALL BE REPAIRED, REPLACED AND RECONSTRUCTED BY THE CONTRACTOR TO SUIT EXISTING CONDITIONS.

2.0 PROJECT DATUM

- 2.1 THE PROJECT COORDINATE SYSTEM IS UTM NAD83 ZONE 14 NORTH.
- 2.2 TO CONVERT FROM UTM TO GROUND, DIVIDE THE NORTHING AND EASTING BY THE COMBINED SCALE FACTOR 0.99985658 AT THE PROJECT ORIGIN OF (0,0).
- 2.3 ELEVATIONS AND CONTOURS ARE IN METRES AND DECIMALS THEREOF TO CHART DATUM (CD). REFER TO CANADIAN HYDROGRAPHIC SERVICE CHART NO. 5626 FOR CHART DATUM DEFINITION AT BAKER LAKE.

3.0 EARTHWORKS

- 3.1 PROVIDE TEMPORARY EROSION AND SEDIMENTATION CONTROL MEASURES TO PREVENT SOIL EROSION AND DISCHARGE OF SOIL BEARING WATER RUNOFF OR AIRBORNE DUST TO THE RECEIVING ENVIRONMENT. REMOVE EROSION AND SEDIMENTATION CONTROLS, AND RESTORE AND STABILIZE AREAS DISTURBED CONSTRUCTION TO SUIT ORIGINAL STATE.
- 3.2 SHORE AND BRACE EXCAVATIONS, PROTECT SLOPES AND BANKS, AND PERFORM WORK IN ACCORDANCE WITH NUNAVUT REGULATIONS.
- 3.3 STRIP TOPSOIL OVER AREAS TO BE COVERED BY NEW CONSTRUCTION, OVER AREAS WHERE GRADE CHANGES ARE REQUIRED, AND SO THAT EXCAVATED MATERIAL MAY BE STOCKPILED WITHOUT COVERING TOPSOIL. AVOID MIXING TOPSOIL WITH SUBSOIL.
- 3.4 DO NOT BURY SNOW OR ICE IN FILL MATERIAL.
- 3.5 PLACE BACKFILL MATERIAL IN UNIFORM LAYERS NOT EXCEEDING 150mm COMPACTED THICKNESS UP TO GRADES INDICATED. COMPACT EACH LAYER BEFORE PLACING SUCCEEDING LAYER.

REV	DATE	REVISION DESCRIPTION	DRAWN	DRAFT CHK	DESIGNED	ENG CHK	APPROVED	QAR	REF DRAWING No	REFERENCE DRAWING TITLE	D SHEET	SCALE	ENGINEERING AND PERMIT STAMPS (As Required)	CUSTOMER	DRG No	REV
D	29-MAY-25	ISSUED FOR PERMITTING	AAL	BJM	AD	-	AD	-					 	 HAMLET OF BAKER LAKE SEALIFT INFRASTRUCTURE COVER SHEET, DRAWING LIST AND GENERAL NOTES	317086-48113-00-MA-DGA-0001	D
C	20-MAR-25	RE-ISSUED FOR CLIENT REVIEW	JLC	-	AD	-	AD	-								
B	23-OCT-23	RE-ISSUED FOR CLIENT REVIEW	JLC	-	AD	-	HGK	-								
A	29-MAY-23	ISSUED FOR CLIENT REVIEW	JLC	-	AD	-	HGK	-								


LOCATION: U:\V\317086\48113_MCBL_BAKERLAKOP111_DRAWINGS\15_L_AND_E\02_MARINE\317086-48113-00-MA-DGA-0001.DWG
 USER NAME: baron.leisham
 PLOT DATE & TIME: 29/5/2025 10:36:42 AM
 SAVE DATE & TIME: 29/5/2025 10:31:01 AM



KEY PLAN
1:30000




PLAN
1:2000



NOTES:
1. FOR GENERAL NOTES, SEE DWG. 317086-48113-00-MA-DGA-0001.

REV	DATE	REVISION DESCRIPTION	DRAWN	DRAFT CHK	DESIGNED	ENG CHK	APPROVED	QAR	REF DRAWING No	REFERENCE DRAWING TITLE
D	29-MAY-25	ISSUED FOR PERMITTING	AAL	BJM	AD	-	AD	-		
C	20-MAR-25	RE-ISSUED FOR CLIENT REVIEW	JLC	-	AD	-	AD	-		
B	23-OCT-23	RE-ISSUED FOR CLIENT REVIEW	JLC	-	AD	-	HGK	-		
A	29-MAY-23	ISSUED FOR CLIENT REVIEW	JLC	-	AD	-	HGK	-		

D SHEET	SCALE	SHOWN	ENGINEERING AND PERMIT STAMPS (As Required)	CUSTOMER
			PRELIMINARY DO NOT USE FOR CONSTRUCTION Last Saved: Mar. 20/25 9:48am	 MUNICIPALITY OF BAKER LAKE
WORLEY PROJECT No				
317086-48113				

This drawing is prepared for the use of the contractual customer of Worley Canada Services Ltd. and Worley Canada Services Ltd. assumes no liability to any other party for any representations contained in this drawing.

worley consulting

**HAMLET OF BAKER LAKE
SEALIFT INFRASTRUCTURE
EXISTING SITE PLAN**


DRG No **317086-48113-00-MA-DGA-0002** REV **D**




PLAN
1:750

NOTES:


- FOR GENERAL NOTES, SEE DWG. 317086-48113-00-MA-DGA-0001.
- NO WORK IS TO BE EXECUTED WITHIN THE WATER. PUSHOUT AND RAMP TO BE SET BACK 0.5m FROM HIGH WATER LEVEL.



REV	DATE	REVISION DESCRIPTION	DRAWN	DRAFT CHK	DESIGNED	ENG CHK	APPROVED	QAR	REF DRAWING No	REFERENCE DRAWING TITLE
D	29-MAY-25	ISSUED FOR PERMITTING	AAL	BJM	AD	-	AD	-		
C	20-MAR-25	RE-ISSUED FOR CLIENT REVIEW	JLC	-	AD	-	AD	-		
B	23-OCT-23	RE-ISSUED FOR CLIENT REVIEW	JLC	-	AD	-	HGK	-		
A	29-MAY-23	ISSUED FOR CLIENT REVIEW	JLC	-	AD	-	HGK	-		


D SHEET	SCALE	SHOWN	ENGINEERING AND PERMIT STAMPS (As Required)	CUSTOMER
			<div style="border: 1px solid black; padding: 5px;"> PRELIMINARY DO NOT USE FOR CONSTRUCTION Last Saved: May 29/25 10:23am </div>	
WORLEY PROJECT No				
317086-48113				

This drawing is prepared for the use of the contractual customer of Worley Canada Services Ltd. and Worley Canada Services Ltd. assumes no liability to any other party for any representations contained in this drawing.




**HAMLET OF BAKER LAKE
SEALIFT INFRASTRUCTURE
GENERAL ARRANGEMENT**


DRG No	317086-48113-00-MA-DGA-0003	REV	D
--------	-----------------------------	-----	---




SECTION A LAYDOWN WITH RAMP
1:150





SECTION B LAYDOWN
1:150



SECTION E ACCESS ROAD
1:150



NOTES:
1. FOR GENERAL NOTES, SEE DWG. 317086-48113-00-MA-DGA-0001.

REV	DATE	REVISION DESCRIPTION	DRAWN	DRAFT CHK	DESIGNED	ENG CHK	APPROVED	QAR	REF DRAWING No	REFERENCE DRAWING TITLE	D SHEET	SCALE	SHOWN	ENGINEERING AND PERMIT STAMPS (As Required)	CUSTOMER	DRG No	REV	
D	29-MAY-25	ISSUED FOR PERMITTING	AAL	BJM	AD	-	AD	-							 HAMLET OF BAKER LAKE SEALIFT INFRASTRUCTURE TYPICAL SECTIONS	317086-48113-00-MA-DGA-0004	D	
C	20-MAR-25	RE-ISSUED FOR CLIENT REVIEW	JLC	-	AD	-	AD	-										
B	23-OCT-23	RE-ISSUED FOR CLIENT REVIEW	JLC	-	AD	-	HGK	-										
A	29-MAY-23	ISSUED FOR CLIENT REVIEW	JLC	-	AD	-	HGK	-										
											WORLEY PROJECT No	317086-48113						
											PRELIMINARY DO NOT USE FOR CONSTRUCTION Last Saved: Mar. 20/25 9:49am							
											<small>*This drawing is prepared for the use of the contractual customer of Worley Canada Services Ltd. and Worley Canada Services Ltd. assumes no liability to any other party for any representations contained in this drawing.*</small>							

USER NAME: jennifer.coppensdale
 LOCATION: U:\YVR\317086\48113_MCB\BAKER\KOP\11_DRAWINGS\15_L_AND_E\02_MARINE\317086-48113-00-MA-DGA-0004.DWG
 PLOT DATE & TIME: 29/5/2025 10:57:54 AM
 SAVE DATE & TIME: 20/5/2025 9:49:28 AM

Appendix B: Community Plan and Zoning By-law



Appendix C: Letter of Support





Telephone: 867-793-2874
Fax: 867-793-2509

BAKER LAKE, NU
XOC 0A0

March 6th 2020

Mr. Matthew Bowler
Government of Nunavut
Department of Economic Development & Transportation
P.O. Box 1000, Station 1570
Iqaluit, Nunavut X0A 0H0

Dear Mr. Matthew Bowler:

RE: Baker Lake Marine Needs

On behalf of the Mayor and Council of the Municipality of Baker Lake, please accept this letter as our support for the work of Advisian regarding marine needs in Baker Lake.

Our community has seen steady growth since Agnico Eagle opened its first gold mine outside of Baker Lake some 10 plus years ago; we anticipate this growth to continue. This growth has seen a significant increase in marine traffic over this period and as indicated we expect this to continue.


Our current "community sealift docking and staging area", where all the communities annual sealift supplies are offloaded and marshalled is in the center of our community. During the offloading times this area becomes very congested and causes safety concerns for our residents.

Another concern, our community has, relates to the proximity of this docking / staging area to our intake for the potable drinking water supply; the docking area is approximately 1,500 feet away from the water intake.

The Municipality of Baker Lake is in need of new marine infrastructure that can accommodate our community's reliance on the annual sealift to replenish supplies for our growing community as well as reduce the concerns related to our potable water supply by relocating the sealift area to a proposed area some 2 km down the shore.

Our Mayor and Council fully supports Advisian's work and we look forward to continuing the efforts that will improve the marine infrastructure situation in our growing community. If you require any further information, please feel free to contact me at (867) 793 – 2874.

Thank you,


Sheldon Dorey
Senior Administrative Officer
Municipality of Baker Lake



April 17, 2020

Harald Kullman
Senior Project Manager, Parts and Marine Terminals
Suite 500, 4321 Still Creek Drive
Burnaby, BC
V5C 6S7

Dear Harald,

RE: Support Letter for OPP Sealift Project in Baker Lake, NU

The BLHTO board of directors fully support your proposed project on our sealift location project in Baker Lake. We also appreciate you coming into Baker Lake to discuss your plans on this project with the Baker Lake Hunters and Trappers Organization board.

If you have any questions, feel free to contact our office at 867-793-2520 or email to bakerlake@kivallighto.ca

Thank you.

Sincerely,

Philip Putumiraqtuq
Chairperson
Baker Lake Hunters and Trappers Organization