

**Part 1            General**

**1.1            FIRES**

- .1      Fires and burning of rubbish on site not permitted.

**1.2            DRAINAGE**

- .1      Provide temporary drainage and pumping required to keep excavations and site free from water.
- .2      Ensure pumped water into waterways or drainage systems is free of suspended materials.
- .3      Control disposal or runoff of water containing suspended materials or other harmful substances in accordance with local authority requirements.

**1.3            WORK ADJACENT TO WATERWAYS**

- .1      Do not operate construction equipment in waterways. Construction equipment to be operated on land only.
- .2      Do not use waterway beds for borrow material
- .3      Waterways to be free of excavated fill, waste material and debris.
- .4      Design and construct temporary crossings to minimize erosion to waterways.

**1.4            POLLUTION CONTROL**

- .1      Maintain temporary erosion and pollution control features installed under this Contract.
- .2      Control emissions from equipment and plant to local authorities' emission requirements.
- .3      Cover or wet down dry materials and rubbish to prevent blowing dust and debris. Provide dust control for temporary roads.

**Part 2           Products**

**2.1           NOT USED**

- .1      Not Used.

**Part 3           Execution**

**3.1           NOT USED**

- .1      Not Used.

**END OF SECTION**