





## Activities

Location	Activity Type	Land Status	Site history	Site archaeological or paleontological value	Proximity to the nearest communities and any protected areas
Small Craft Harbour Location	Harbour infrastructure	Crown	The harbour area has been used for fishing, harvesting, transportation of goods for at least 60 years since the community of Clyde River was established in its current location.	An archaeological Impact Assessment (AIA) was completed by Lifeways of Canada Limited in 2019. The AIA results state that there are no known archaeological or paleontological sites in the project area.	The closest community is Clyde River, which is located within 100 m of the Project area. The closest protected area is Isabella Bay, which is approximately 80 km southwest of the Project area.
Quarry Location	Quarry/Borrow pit	Municipal	There has been a quarry in the area for at least 16 years.	An archaeological Impact Assessment (AIA) was completed by Lifeways of Canada Limited in 2019. The AIA results state that there are no known archaeological or paleontological sites in the project area.	The closest community is Clyde River, which is approximately 1.5 km northwest of the quarry. The closest protected area is Isabella Bay, which is approximately 80 km southwest of the Project area.
Disposal at Sea Location	Marine Based Activities	Crown	Marine environment	No known archaeological resources.	The closest community is Clyde River, which is located within approximately 700 m of the disposal area. The closest protected area is Isabella Bay, which is approximately 80 km southwest of the Project area.
Haul Route	Access Road	Municipal	The road from the harbour location to the Clyde River airport has been in place since at least 1985. The haul route between the quarry and the airport was established in 2019.	No known archaeological resources.	The closest community is Clyde River, which the haul route goes through. The closest protected area is Isabella Bay, which is approximately 80 km southwest of the Project area.

## Community Involvement & Regional Benefits

Community	Name	Organization	Date Contacted
Clyde River	Hamlet Council Members - Mayor, Councilors, SAO, etc	Hamlet of Clyde River	2019-05-24

Clyde River	Nangmoutaq HTO members	Nangmoutaq HTO	2019-05-24
Clyde River	Hamlet Council Members - Mayor, Councilors, SAO, etc	Hamlet of Clyde River	2018-11-08
Clyde River	Nangmoutaq HTO members	Nangmoutaq HTO	2018-11-08
Clyde River	Hamlet Council Members - Mayor, Councilors, SAO, etc	Hamlet of Clyde River	2019-11-04
Clyde River	Nangmoutaq HTO members	Nangmoutaq HTO	2019-11-04
Clyde River	Clyde River community members	Community Open House	2020-02-24
Clyde River	Nangmoutaq HTO members	Nangmoutaq HTO	2020-02-25
Clyde River	Hamlet Council Members - Mayor, Councilors, SAO, etc	Hamlet of Clyde River	2020-02-26
Clyde River	Hamlet Council Members - Mayor, Councilors, SAO, etc.	Hamlet of Clyde River	2020-09-29
Clyde River	Nangmoutaq HTO members	Nangmoutaq HTO	2020-10-01
Clyde River	Guardian Members	Guardians	2020-10-02
Clyde River	QIA local Members	Qikiqtani Inuit Association	2020-10-02
Clyde River	Hamlet Council Members - Mayor, Councilors, SAO, etc.	Hamlet of Clyde River	2021-02-20
Clyde River	Nangmoutaq HTO members	Nangmoutaq HTO	2021-02-21
Clyde River	Guardian Members	Guardians	2021-02-22
Clyde River	QIA local Members	Qikiqtani Inuit Association	2021-02-24

# Authorizations

Indicate the areas in which the project is located:

North Baffin

## Authorizations

Regulatory Authority	Authorization Description	Current Status	Date Issued / Applied	Expiry Date
Environment and Climate Change Canada	Disposal at Sea (DAS) is not considered likely, however if required a DAS application will be submitted to Environment and Climate Change Canada (ECCC). A sample analysis plan (SAP) was submitted to and approved by ECCC for sediment analysis in the dredge footprint of the SCH. ECCC has been engaged from an early stage in project planning as the proponent (DFO-SCH) is a federal agency.	Not Yet Applied		
Transport Canada	A Notice of Works (NoW) is expected to be required from Transport Canada due to the potential for interferences to navigation during construction, and to confirm navigational markers required during operations of the SCH. TC has been engaged from an early stage in project planning as the proponent (DFO-SCH) is a federal agency. Maintaining access for harvesters to the marine environment during construction has been a key part of consultation and measures will be in place during construction to confirm there are no access restrictions for hunters.	Not Yet Applied		
Natural Resources	A permit from NRCan	Not Yet Applied		

Canada	is expected to be required for the transportation and storage of explosives (required for blasting). NRCan compliance requirements will be the responsibility of the contractor and will be applied for after contract award and before the start of construction.			
Nunavut Water Board	A Type B license may be required if the haul road upgrades requires culverts to be installed or if stream alteration is required for the Project. The haul route will cross a river close to Clyde River. Any temporary structures used to cross the river may require review and licensing from NWB. NWB compliance requirements will be the responsibility of the contractor and will be applied for after contract award and before the start of construction.	Not Yet Applied		
Fisheries and Oceans Canada	A Fisheries Act Authorization (FAA) will be required due to the permanent loss of seabed habitat due to the construction of the Small Craft Harbour. Any impacts resulting from a haul road river crossing structure will also be recognized by DFO-Fish and Fish Habitat Protection Program (FFHPP). DFO-FFHPP has been engaged from an early stage in project planning as the proponent (DFO-SCH) is a federal agency.	Not Yet Applied		

### Project transportation types

Transportation Type	Proposed Use	Length of Use
Air	During construction, the Project will use commercially scheduled flights, with the potential for use of chartered flights but may need to use chartered	

	flights if the existing service cannot support the additional throughput. In addition, the Project will confirm that if commercial flights are used, that there is no effect to availability of flight service to locals	
Water	During construction, the Project will use the existing scheduled sealift deliveries	
Land	Heavy Equipment, and contractor light vehicles (pick-up trucks) will be used during construction.	

**Project accomodation types**

Temporary Camp

## Material Use

Equipment to be used (including drills, pumps, aircraft, vehicles, etc)

Equipment Type	Quantity	Size - Dimensions	Proposed Use
Drill Rig	2	5.5 x 2.3.m	Quarrying
Excavator	5	4 x 3.4m	Quarrying, material handling, excavating
Rock Truck 35 ton - Articulating	4	11.1 x 4.2 m	Transporting quarried rock
Front end loader 966 - 988	3	7.5 x 2.5 m	Material loading & handling
Compactor - 20 ton	1	6.2 x 2.5m	Work surface and road compaction
Bulldozer D8	1	3.2 x 2.7m	Work surface and road levelling
Grader 140 ton	1	10.1 x 2.5m	Work surface and road grading
Spud Bard/derrick with 150 ton crane	1	20 x 50m	Dredging, transporting material and equipment
Material Scow 500 cubic meter	2	47 x 11m	Dredging and disposal of dredged material
Tug 1000 - 1500 hp	1	14.85 x 5.8m	Transport and movement of marine equipment
Work boat - 50-500ho	2	9.75 x 2.9m	Transport and movement of marine equipment and personnel
Pick -up truck 3/4 ton	3	4.8 x 1.9m	Material and personnel transport
Fuel/service truck 10 ton	1	13 x 2.5m	Transport fuel from GN PPD dispensers to construction equipment
Water truck 10 ton	1	9.5 x 2.5m	Transport water from municipal water supply to work camp and construction site
Wastewater truck 10 ton	1	9.5 x 2.5m	Transport wastewater from work camp and construction site to municipal treatment facility
Telehandler/forklifts	1	6.2 x 2.6m	Material and equipment handling
Rough terrain crane 250 ton	1	14.5 x 7.9 m	Material and equipment loading/handling/movement
Rock crusher for quarry 125 ton	1	14.6 x 4.2 m; 14.3 x 4.2 m; 17 x 3.6 m	Portable jaw crusher, cone and screening plant for the manufacturing of aggregate

### Detail Fuel and Hazardous Material Use

Detail fuel material use:	Fuel Type	Number of containers	Container Capacity	Total Amount	Units	Proposed Use
Diesel	fuel	1	3800	3800	Cubic Meters	Fuel for equipment, generators, heaters. Fuel will be dispensed on a daily basis from existing facilities in Clyde River. Container capacity field contains estimated total value.
Gasoline	fuel	1	140	140	Cubic Meters	Fuel for small equipment, trucks, work boats. Fuel will

						be dispensed on a daily basis from existing facilities in Clyde River. Container capacity field contains estimated total volume
Propane	fuel	10	100	1000	Lbs	Camp use - heating, refrigeration, cooking
Other	fuel	10	4	40	Cubic Meters	Acetylene - metal cutting and welding torches
Oils & Lubricants	hazardous	10	5	50	Gallons	Equipment maintenance
Paint	hazardous	10	1	10	Gallons	Painting wharf hardware & mics. components
Explosives	hazardous	1	1	1	Cubic ft	ANFO explosives for quarrying. Quantity to be determined. Storage and handling will be in accordance with license/cert/permit issued under the Explosives Act and Regulations

#### Water Consumption

Daily amount (m3)	Proposed water retrieval methods	Proposed water retrieval location
6	Water truck.	Community water supply.

# Waste

## Waste Management

Project Activity	Type of Waste	Projected Amount Generated	Method of Disposal	Additional treatment procedures
Camp	Combustible wastes	2 tonnes	Deposit in municipal landfill.	n/a
Camp	Greywater	800 m <sup>3</sup>	Collected in wastewater truck and transported to municipal wastewater treatment facility.	n/a
Harbour infrastructure	Hazardous	100 L	Package, sealed and transported south in shipping containers for disposal in accordance with applicable regulations.	n/a
Camp	Non-Combustible wastes	0.5 tonnes	Deposit in municipal landfill.	n/a
Quarry/Borrow pit	Overburden (organic soil, waste material, tailings)	Negligible	Stockpiled at quarry.	n/a
Dredging	Overburden (organic soil, waste material, tailings)	12, 000 m <sup>3</sup>	Infilling and/or disposal at sea	n/a
Camp	Sewage (human waste)	1,500 m <sup>3</sup>	Collected in wastewater truck and transported to municipal wastewater treatment facility.	n/a

### Environmental Impacts:

Potential environmental impacts and mitigation measures are described in the Project Proposal (Chapter 7 and Chapter 8) and Construction Environmental Management Plan. There may be some negative residual environmental effects that will remain despite mitigation measures, predominantly with respect to ambient light, air quality, noise, marine water and sediments, marine fish and fish habitat and marine mammals, however, no residual effects are predicted to be significant.

# **Additional Information**

## **SECTION A1: Project Info**

Details can be found in the Project Proposal sections: Chapter 1 and 4

## **SECTION A2: Allweather Road**

An existing road is planned to be used to support the transportation of rock materials from the quarry to the SCH. Upgrades to the road will occur prior to construction and will be described in the Project Proposal document. In required, the contractor will be responsible for necessary permits from the NWB. Measures to manage traffic interactions with the community will be described in the CEMP, and the contractor will be required to develop a Traffic Management Plan (TMP) to detail methodologies (e.g. use of dust suppressants, speed limits, training requirements) to be undertaken to support CEMP requirements.

## **SECTION A3: Winter Road**

## **SECTION B1: Project Info**

## **SECTION B2: Exploration Activity**

## **SECTION B3: Geosciences**

## **SECTION B4: Drilling**

## **SECTION B5: Stripping**

## **SECTION B6: Underground Activity**

## **SECTION B7: Waste Rock**

## **SECTION B8: Stockpiles**

## **SECTION B9: Mine Development**

## **SECTION B10: Geology**

## **SECTION B11: Mine**

## **SECTION B12: Mill**

## **SECTION C1: Pits**

Details can be found in the Project Proposal sections: 4.5.3

## **SECTION D1: Facility**

Details can be found in the Project Proposal sections: Chapter 4

## **SECTION D2: Facility Construction**

Details can be found in the Project Proposal sections: Chapter 4

### **SECTION D3: Facility Operation**

The SCH once operational will remain the responsibility of DFO-SCH. An Operations Environmental Management Plan (OEMP) will be prepared prior to operations of the SCH. There are not expected to be any differences in vessel use before and after the construction of the SCH. Details can be found in the Project Proposal sections: Chapter 4.4

### **SECTION D4: Vessel Use**

### **SECTION E1: Offshore Survey**

### **SECTION E2: Nearshore Survey**

### **SECTION E3: Vessel Use**

### **SECTION F1: Site Cleanup**

### **SECTION G1: Well Authorization**

### **SECTION G2: Onland Exploration**

### **SECTION G3: Offshore Exploration**

### **SECTION G4: Rig**

### **SECTION H1: Vessel Use**

There is no shipping associated with the project construction as all materials will arrive under existing scheduled sealift deliveries. It is anticipated that small vessels related to the construction of the Harbour

### **SECTION H2: Disposal At Sea**

It has not been determined if disposal at sea is required, however the preferred DAS site is shown in the Project Proposal.

### **SECTION I1: Municipal Development**

#### **Description of Existing Environment: Physical Environment**

Details can be found in the Environmental and Socio-Economic Baseline Report sections: 2, 4-5. Details can be found in the Project Proposal sections: Chapter 5

#### **Description of Existing Environment: Biological Environment**

Details can be found in the Environmental and Socio-Economic Baseline Report sections: 2, 6-10. Details can be found in the Project Proposal sections: Chapter 5

#### **Description of Existing Environment: Socio-economic Environment**

Details can be found in the Environmental and Socio-Economic Baseline Report sections: 11. Details can be found in the Project Proposal sections: Chapter 6

### **Miscellaneous Project Information**

## **Identification of Impacts and Proposed Mitigation Measures**

Details can be found in the Project Proposal sections: Chapter 7. Additional mitigations will be found in the Construction Environmental Management Plan (CEMP)

## **Cumulative Effects**

There may be some negative residual environmental effects that will remain despite mitigation measures, predominantly with respect to ambient light, air quality, noise, marine water and sediments, marine fish and fish habitat and marine mammals, however, no residual effects are predicted to be significant. Details can be found in the Project Proposal sections: Chapter 8


# Impacts

## Identification of Environmental Impacts

	PHYSICAL													BIOLOGICAL				SOCIO-ECONOMIC				
	Designated environmental areas	Ground stability	Permafrost	Hydrology / Limnology	Water quality	Climate conditions	Eskers and other unique or fragile landscapes	Surface and bedrock geology	Sediment and soil quality	Tidal processes and bathymetry	Air quality	Noise levels	Vegetation	Wildlife, including habitat and migration patterns	Birds, including habitat and migration patterns	Aquatic species, incl. habitat and migration/spawning	Wildlife protected areas	Archaeological and cultural historic sites	Employment	Community wellness	Community infrastructure	Human health
<b>Construction</b>																						
Harbour infrastructure	-	-	M	-	M	-	-	M	M	-	M	M	N	N	N	N	-	-	P	-	M	M
Quarry/Borrow pit	-	-	N	-	-	-	-	N	N	-	N	N	M	N	-	N	-	-	-	-	-	N
Access Road	-	-	M	-	M	-	-	-	M	-	M	M	M	M	-	M	-	-	-	P	M	
Marine Based Activities	-	-	-	-	M	-	-	-	-	-	-	M	-	-	-	M	-	-	P	-	-	-
<b>Operation</b>																						
Harbour infrastructure	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	P	P	P	-
Access Road	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	P	-	-
Marine Based Activities	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	P	P	P	P
<b>Decommissioning</b>																						
-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-

(P = Positive, N = Negative and non-mitigatable, M = Negative and mitigatable, U = Unknown)

## Project Location



## List of Project Geometries

1	polygon	Small Craft Harbour Location
2	polygon	Quarry Location
3	polygon	Disposal at Sea Location
4	polyline	Haul Route